Pecyn Dogfennau



Wendy Walters
Prif Weithredwr,
Chief Executive,
Neuadd y Sir, Caerfyrddin. SA31 1JP
County Hall, Carmarthen. SA31 1JP

DYDD MAWRTH, 13 AWST 2019

AT: HOLL AELODAU'R PWYLLGOR CYNLLUNIO

YR WYF DRWY HYN YN EICH GALW I FYNYCHU CYFARFOD O'R **PWYLLGOR CYNLLUNIO** A GYNHELIR YN **Y SIAMBR, NEUADD Y SIR** AM **10.00 YB, DYDD IAU, 22AIN AWST, 2019** ER MWYN CYFLAWNI'R MATERION A AMLINELLIR AR YR AGENDA SYDD YNGHLWM

Wendy Walters

PRIF WEITHREDWR



Swyddog Democrataidd:	Emma Bryer
Ffôn (Ilinell uniongyrchol):	01267 224029
E-bost:	Democraticservices@sirgar.gov.uk
Cyf:	AD016-001



PWYLLGOR CYNLLUNIO

20 AELOD

Y GRŴP PLAID CYMRU - 10 AELOD

Y Cynghorydd Mansel Charles
 Y Cynghorydd Tyssul Evans
 Y Cynghorydd Jeanette Gilasbey
 Aelod o Gyngor Cymuned Llanegwad
 Aelod o Gyngor Cymuned Llanegwad

Aelod o Gyngor Tref Caerfyrddin

4. Y Cynghorydd Ken Howell

5. Y Cynghorydd Carys Jones

Y Cynghorydd Alun Lenny (Cadeirydd)

7. Y Cynghorydd Jean Lewis

8 Y Cynghorydd Dorian Phillips

9. Y Cynghorydd Gareth Thomas

10 Y Cynghorydd Eirwyn Williams

Y GRŴP LLAFUR - 4 AELOD

1. Y Cynghorydd Penny Edwards

Y Cynghorydd John James
 Y Cynghorydd Dot Jones
 Y Cynghorydd Kevin Madge
 Aelod o Gyngor Tref Pen-bre a Phorth Tywyn Aelod o Gyngor Cymuned Llannon Aelod o Gyngor Tref Cwmaman

Y GRŴP ANNIBYNNOL – 4 AELOD

1. Y Cynghorydd Sue Allen Aelod o Gyngor Tref Hendy-Gwyn

2. Y Cynghorydd Ieuan Davies

3. Y Cynghorydd Joseph Davies

4. Y Cynghorydd Irfon Jones (Is- Aelod o Gyngor Cymuned Bronwydd

Gadeirydd)

Y GRŴP ANNIBYNNOL NEWYDD - 2 AELOD

- 1. Lle Gwag
- 2. Lle Gwag

NI CHANIATEIR EILYDDION MEWN CYFARFODYDD O'R PWYLLGOR YMA



AGENDA

1.	YMDDIHEURIADAU AM ABSENOLDEB	
2.	DATGAN BUDDIANNAU PERSONOL	
3.	RHANBARTH Y DWYRAIN - PENDERFYNU AR GEISIADAU CYNLLUNIO	5 - 14
4.	RHANBARTH Y DE - PENDERFYNU AR GEISIADAU CYNLLUNIO	15 - 88
5.	RHANBARTH Y GORLLEWIN - PENDERFYNU AR GEISIADAU CYNLLUNIO	89 - 98
6.	LLOFNODI YN GOFNOD CYWIR COFNODION Y CYFARFOD A	99 - 102



ADRODDIAD PENNAETH CYNLLUNIO, CYFARWYDDIAETH YR AMGYLCHEDD

REPORT OF THE HEAD OF PLANNING, DIRECTORATE OF ENVIRONMENT


AR GYFER PWYLLGOR CYNLLUNIO CYNGOR SIR CAERFYRDDIN

TO CARMARTHENSHIRE COUNTY COUNCIL'S PLANNING COMMITTEE

AR 22 AWST 2019

ON 22 AUGUST 2019

I'W BENDERFYNU FOR DECISION Ardal Dwyrain/ Area East



Mewn perthynas â cheisiadau y mae gan y Cyngor ddiddordeb ynddynt un ai fel ymgeisydd/asiant neu fel perchennog tir neu eiddo, atgoffir yr Aelodau fod yna rhaid iddynt anwybyddu'r agwedd hon, gan ystyried ceisiadau o'r fath a phenderfynu yn eu cylch ar sail rhinweddau'r ceisiadau cynllunio yn unig. Ni ddylid ystyried swyddogaeth y Cyngor fel perchennog tir, na materion cysylltiedig, wrth benderfynu ynghylch ceisiadau cynllunio o'r fath.

In relation to those applications which are identified as one in which the Council has an interest either as applicant/agent or in terms of land or property ownership, Members are reminded that they must set aside this aspect, and confine their consideration and determination of such applications exclusively to the merits of the planning issues arising. The Council's land owning function, or other interests in the matter, must not be taken into account when determining such planning applications.

COMMITTEE:	PLANNING COMMITTEE
DATE:	22 AUGUST 2019
REPORT OF:	HEAD OF PLANNING

INDEX - AREA EAST

REF.	APPLICATIONS RECOMMENDED FOR APPROVAL	PAGE NO
E/38980	Conversion of terraced property into 6 bed HMO at 44 Quay Street, Ammanford, SA18 3EN	9 - 14

APPLICATION	S RECOMMEND	ED FOR APPRO	VAL	
APPLICATION	S RECOMMEND	ED FOR APPRO	OVAL	
APPLICATION	SRECOMMEND	ED FOR APPRO	OVAL	

Application No	E/38980
Application Type	Full Planning
Proposal & Location	CONVERSION OF TERRACED PROPERTY INTO 6 BED HMO AT 44 QUAY STREET, AMMANFORD, SA18 3EN
Applicant(s)	PSW PROJECT MANAGEMENT LTD, CWM COTTAGE, CWMFFERWS ROAD, TYCROES, AMMANFORD, SA18 3TU
Agent	DARKIN ARCHITECTS - ASHLEY WOOD, 1 JOHN STREET, LLANELLI, SA15 1UH
Case Officer	Andrew Francis

Reason for Committee

Ammanford

14/06/2019

This application is being reported to the Planning Committee following the receipt of more than one objection from third parties.

Site

Ward

Date of validation

The application site consists of an existing residential terraced two storey three bedroom dwelling addressed at 44 Quay Street, Ammanford. The existing dwelling is one of a row of six units situated at the southern end of Quay Street, beyond the pedestrianised area, opposite the Ammanford Pensioners Hall and the Railway Hotel.

Not all the units in this row are residential – there is one art gallery and three hot food takeaways amongst the 6 units. As such, there area is clearly mixed use when taking into account the public house and pensioner's hall opposite also.

There is no on-site parking, though the site is served by a narrow rear lane.

The current dwelling is situated outside the Ammanford Town Centre Retail Core and Retail Frontage so falls to be considered under general LDP policies. However, the site is extremely close to the town centre and all its amenities so qualifies as a sustainable location and achieves the maximum reduction in car parking spaces.

Proposal

The application seeks planning permission to change the use of the existing residential dwelling (C3 Use) to a House in Multiple Occupation (HMO – C4 Use). The existing 3 bed residential dwelling seeks to accommodate 6 individual bedsits, split over both floors, with a communal kitchen, lounge, wet-room and bathroom on the ground floor. No external changes are proposed to the building.

As per the current dwelling, no parking is formally available on the plot and none is shown as part of the application.

Planning Site History

There is no planning history at this property.

Planning Policy

The following policies are of relevance to the proposal:-

<u>Carmarthenshire Local Development Plan</u> (Adopted December 2014) ('the LDP')

Policy GP1 Sustainability and High Quality Design Policy H3 Conversion or Subdivision of Existing Dwellings

Carmarthenshire Supplementary Planning Guidance

National Planning Policy and Guidance is provided in <u>Planning Policy Wales</u> (PPW) Edition 10, December 2018 and associated <u>Technical Advice Notes</u> (TANs) published by Welsh Government.

Summary of Consultation Responses

Head of Transportation & Highways – Offers no observations regarding this proposal.

Ammanford Town Council – Objects to the proposal as there will be an increase in the number of occupants, based on 6 occupants living at the property but there is a lack of parking provision, particularly given the number of parking restrictions in the vicinity.

Local Member - County Councillor D Harries has not commented to date.

Dwr Cymru/Welsh Water – No objections subject to the imposition of planning conditions.

Natural Resources Wales – No comments received to date.

All representations can be viewed in full on our <u>website</u>.

Summary of Public Representations

The application was the subject of notification by way of neighbouring letters.

Two representations were received, both objecting. The matters raised are summarised as follows:

- There are major issues currently with parking in the area. This will make the situation worse.
- The area is also very busy and noisy. The proposed use will add to that, not to mention the upheaval of builders working there all day.
- The application documents seems vague, are there more details?
- This part of Ammanford has turned into a ghetto.

All representations can be viewed in full on our <u>website</u>.

Appraisal

Principle of Development

The use of existing residential properties as HMO's in areas close to town centres is a long established practice. What is more, prior to February 2015, in cases of 6 residents or less, where the occupants were living as a single family unit, the practice did not require planning permission.

Since February 2015, and the introduction of the C4 Use Class, such conversions now require planning permission. In turn, this allows the neighbouring occupiers of the properties to raise concerns they might have. In many cases, perhaps due to the size of the property, the intensity of the use of the building would be similar as if a family were to be living in the property. In this instance, up to 6 individuals would be accommodated. This would be up to the previous permitted development limit, but likely a more intense use than the current 3 bedroom family dwelling.

What is undeniable is that such uses tend to be most acceptable in locations close to the town centre. Taking into account this specific location, there is a varied mix of other uses also so the introduction of a HMO would not detrimentally detract from the area.

Amenity Impacts

The submitted plans show that no external changes are proposed to building. As such, it would be difficult to consider the impact of any amenity issues the proposal might raise. The potential intensification of the use of the building may lead to more noise but until the building is occupied, this will not be known. The issue would also be safeguarded by other legislation.

Highway Impacts

The main point of concern from Ammanford Town Council and one objector relates to the lack of parking spaces in the area. This is true, but it also affects the current dwelling which also has no parking spaces. The Authority's Head of Transport has been consulted and offers no observations on the proposal, essentially because the existing dwelling has no parking spaces and the new Use under the CSS South parking Guidelines is the same,

there would be no requirement to have to provide parking. It should also be noted that the site is in a very sustainable location close to the town centre and public transport links.

All three objectors have raised concerns relating to the access to the site off Plas Gwyn Road and via the busy private access lane that passes through the yard of the car repair garage. In considering this proposal carefully, the Authority's Head of Transport has advised that the proposal is considered to be acceptable from a highways perspective. As such, it is considered that the visibility from the private lane access onto Plas Gwyn Road is acceptable, private lane itself is acceptable and the plot can provide adequate parking and turning facilities to serve the proposed development.

Other Matters

With regard to the other matters raised as objections, the application as submitted might be considered to be vague by an objector, however, it provides all the information required to consider the proposal.

That objector also states that this part of Ammanford has become shabby and the provision of a HMO will facilitate the change of the area into a ghetto. This concern raised is understandable, but in the last few years, all of the buildings in the row have become occupied and are now in beneficial use and the provision of affordable accommodation will hopefully ensure that this property remains in beneficial use also.

The concern that the noise and disturbance caused by the building works will negatively affect an already busy and noisy area is, as Members will be aware, not a point that is material to the consideration of the application. It is the finished and occupied product that must be considered as some disruption is inevitable during development.

Planning Obligations

As the proposal is utilising exactly the same footprint as the existing building, no contribution is being sought for this development.

Well-Being of Future Generations (Wales) Act 2015

The decision considers the duty to improve the economic, social, environmental and cultural well-being of Wales, in accordance with the sustainable development principle, under section 3 of the Well-Being of Future Generations (Wales) Act 2015 (the WBFG Act). The decision takes into account the ways of working set out at section 5 of the WBFG Act and it is considered that this decision is in accordance with the sustainable development principle through its contribution towards one or more of the Welsh Ministers' well-being objectives set out in section 8 of the WBFG Act.

Conclusion

The site is within the settlement limits of Ammanford and within 60 metres of the defined Town Centre of Ammanford. This establishes it as a very sustainable location for such a development and as therefore, the principle this type of development would normally be considered as acceptable, provided all other material considerations can be met.

Prior to the change in the Use Classes Order in Wales in 2015, dwellings such as this could change into houses of multiple occupation supporting up to 6 people, living as a family unit, without planning permission. It was only after this change to the Order that a new Use Class was introduced – C4 and applications were required. It is considered that in this instance, the proposal would not lead to a detrimental impact on the surrounding land uses as it may be expected that a family of 6 could occupy this dwelling with a similar impact.

In addition, the applicant would also be required to comply with HMO regulations and obtain a license prior to any occupation, and the building would have to be compliant with the relevant building regulations set out by Building Control.

The material issues raised have been addressed by conditions to be imposed on the permission, should it be minded to approve. On balance, the concerns relating to the development which are considered to be planning related have been identified and addressed accordingly.

The proposed development is not considered to be detrimental to the existing street scene or the character of the street as there is no change and it will allow for the continued beneficial use of this building. As such, the application is recommended for approval, subject to the following conditions.

Recommendation – Approval

Conditions

- 1 The development hereby permitted shall be commenced no later than the five years from the date of this permission.
- The works hereby granted consent shall be carried out strictly in accordance with the details shown on the following schedule of plans dated 22 May 2019:-
 - Block Plan [002] 1:500 @ A4;
 - Location Plan [001] 1:1250 @ A4;
 - Proposed Block Plan [003] 1:500 @ A4;
 - Proposed Elevations [302] 1:100 @ A3;
 - Proposed Floor Plan [102 A] 1:100 @ A4.
- The premises shall be used as a house in multiple occupation for no more than six persons and shall not be used for any other purpose.

Reasons

- 1 Required to be imposed pursuant to Section 91 of the Town and Country Planning Act 1990.
- 2 To ensure that only the approved works are carried out.
- 3 To ensure the proposed development does not prejudice the enjoyment of neighbouring occupiers of their properties.

Reasons for Granting Planning Permission

The decision to grant planning permission has been taken in accordance with Section 38 of the Planning and Compulsory Purchase Act 2004, which requires that, in determining a planning application the determination must be in accordance with the Development Plan unless material considerations indicate otherwise.

- It is considered that the proposed development complies with Policy GP1 of the Carmarthenshire Local Development Plan (LDP) in that the proposal conforms with and respects the character of the original dwelling and appearance of the site by virtue of its unchanged external design. It is considered that the proposed use would not have an unacceptable impact upon the amenity of adjacent land uses or the residents of the properties. The proposal, by virtue of its sustainable location does not give rise to parking or highway safety issues and provides for the satisfactory generation, treatment and disposal of surface and foul water.
- It is considered that the proposed development complies with Policy GP2 of the Carmarthenshire Local Development Plan (LDP) in that the site is located within the development limits and within the Town Centre in a sustainable location.
- It is considered that the proposed development complies with Policy H3 of the Carmarthenshire Local Development Plan (LDP) in that the submitted plans submitted show that dwelling's conversion to a six bedroom House in Multiple Occupation would not result in over intensification of use as the property as a house could be occupied by 6 people.

Notes/Informatives

Please note that this consent is specific to the plans and particulars approved as part of the application. Any departure from the approved plans will constitute unauthorised development and may be liable to enforcement action. You (or any subsequent developer) should advise the Council of any actual or proposed variations from the approved plans immediately so that you can be advised how to best resolve the matter.

In addition, any conditions which the Council has imposed on this consent will be listed above and should be read carefully. It is your (or any subsequent developers') responsibility to ensure that the terms of all conditions are met in full at the appropriate time (as outlined in the specific condition).

The commencement of development without firstly meeting in full the terms of any conditions which require the submission of details prior to the commencement of development will constitute unauthorised development. This will necessitate the submission of a further application to retain the unauthorised development and may render you liable to formal enforcement action.

ADRODDIAD PENNAETH CYNLLUNIO, CYFARWYDDIAETH

YR AMGYLCHEDD

REPORT OF THE HEAD OF PLANNING, DIRECTORATE OF ENVIRONMENT

AR GYFER PWYLLGOR CYNLLUNIO CYNGOR SIR CAERFYRDDIN

TO CARMARTHENSHIRE COUNTY COUNCIL'S PLANNING COMMITTEE


AR 22 AWST 2019

ON 22 AUGUST 2019

I'W BENDERFYNU FOR DECISION

Ardal De/ Area South

Eitem Rhif 4



Mewn perthynas â cheisiadau y mae gan y Cyngor ddiddordeb ynddynt un ai fel ymgeisydd/asiant neu fel perchennog tir neu eiddo, atgoffir yr Aelodau fod yna rhaid iddynt anwybyddu'r agwedd hon, gan ystyried ceisiadau o'r fath a phenderfynu yn eu cylch ar sail rhinweddau'r ceisiadau cynllunio yn unig. Ni ddylid ystyried swyddogaeth y Cyngor fel perchennog tir, na materion cysylltiedig, wrth benderfynu ynghylch ceisiadau cynllunio o'r fath.

In relation to those applications which are identified as one in which the Council has an interest either as applicant/agent or in terms of land or property ownership, Members are reminded that they must set aside this aspect, and confine their consideration and determination of such applications exclusively to the merits of the planning issues arising. The Council's land owning function, or other interests in the matter, must not be taken into account when determining such planning applications.

COMMITTEE:	PLANNING COMMITTEE
DATE:	22 AUGUST 2019
REPORT OF:	HEAD OF PLANNING

INDEX - AREA SOUTH

REF.	APPLICATIONS RECOMMENDED FOR APPROVAL	PAGE NO.
S/21597	Construction of 100 dwellings and associated works at land off Garreglwyd, Pembrey, Carmarthenshire	19 - 70
S/38939	Single storey rear extension and new driveway to front at 46 Heol Nant, Swiss Valley, Llanelli, SA14 8EN	71 - 76
S/38967	Proposed conversion of existing garage, link extension and front porch at 29 Saron Road, Bynea, Llanelli, SA14 9LT	77 - 82
S/39013	New teaching and practice bays at Ashburnham Golf Club, Cliff Terrace, Burry Port, SA16 0HN	83 - 88

APPLICATIONS REC	OMMENDED FOR APPR	ROVAL
APPLICATIONS REC	OMMENDED FOR APPR	ROVAL
APPLICATIONS REC	OMMENDED FOR APPR	ROVAL

Application No	S/21597
Application Type	Full Planning
Proposal & Location	CONSTRUCTION OF 100 DWELLINGS AND ASSOCIATED WORKS AT LAND OFF GARREGLWYD, PEMBREY,
Location	CARMARTHENSHIRE

Applicant(s)	PERSIMMON HOMES, C/O AGENT
Agent	ASBRI PLANNING LTD - PETE SULLEY, UNIT 9, OAK TREE COURT, CARDIFF GATE BUSINESS PARK, CARDIFF, CF23 8RS
Case Officer	Robert Davies
Ward	Pembrey
Date of validation	21/10/2013

CONSULTATIONS

Head of Transport – No objection subject to conditions.

Head of Housing – Has confirmed that the ward of Pembrey is an area of high housing need which must be supported by affordable housing in perpetuity on this site.

Head of Education – Has requested a contribution of £146,000 towards improving local education facilities.

Head of Leisure - No response received to date.

Land Drainage Officer – No objection. Has requested a contribution of £50,000 towards improving offsite culverts

Head of Public Protection – No objection subject to conditions.

Disabled Access Officer – No response received to date.

Public Rights of Way Officer – No objection. Reference is drawn to the footpath that abuts the proposed development which is a Public Right of Way, and the requirement not to obstruct or encroach upon it at any time.

Pembrey and Burry Port Town Council – Recommend that the application is refused on the following grounds:-

- Drainage;
- Inadequate access;
- · Traffic generation and congestion on the main road;
- Negative impact on the character and Welsh culture of the community.

The Town Council respectfully requests that the Planning Committee undertake a site visit prior to making a decision on the application.

Local Members – County Councillor H B Shepardson has objected to the application on the following grounds:-

- The construction of 100 dwellings will destroy the visual amenity of an attractive Greenfield site that has a rural aspect.
- No local demand for a development of this scale.
- The development will exacerbate existing problems with the sewerage system.
- Increased surface water run-off from the site to properties below which already experience flooding.
- Increased traffic generation and congestion.
- Inadequate access and visibility.
- The existing school in Pembrey is over-subscribed.
- Lack of medical care in the locality with further demand placed as a result of the development proposed.

County Councillor Shepardson has respectfully requested that the Planning Committee undertake a site visit prior to making a decision on the application.

County Councillor S Matthews has not responded to date.

Dwr Cymru/Welsh Water (DCWW) – No objection subject to the imposition of conditions and advisory notes on any planning permission granted.

Natural Resources Wales (NRW) - No objection subject to conditions.

Network Rail – No objection.

Dyfed Archaeological Trust – No objection.

Sustrans – No response received to date.

Cadw - No objection.

Neighbours/Public – This long standing planning application was subject to the original consultation in 2009, and subsequent re-consultation exercises in 2012, 2013, 2016 and most recently twice in 2019 following the receipt of additional information. The consultation was undertaken via neighbour letters, press notices and numerous site notices.

The most recent re-consultations in 2019 resulted in 162 letters of objection being received. The previous consultation exercises resulted in 88 letters of objection being received along with a petition against the development signed by 276 members of the public.

The reasons for objection were as follows:-

- Inadequate infrastructure.
- Surface water runoff and flooding properties along Gwscwm Road and the allotments already flood and this would be exacerbated by the development of this greenfield sloping site at a higher level; the site at present is a natural soakaway; the ground is already saturated and has a high water table; can assurances be given that the attenuation tanks will work and who will maintain them; the eastern ditch which is piped underneath properties along Gwscwm Road is too small; permission will not be given to improve this pipework; the ditches outfall to the canal where the old railway is now a cycle path; the cycle path which is a safe routes path currently floods; who will be responsible for cleaning and dredging the canal; concern over surface water runoff to properties and allotments during construction.
- Foul drainage Health and safety concerns; drains already overflow and back into properties; currently cannot use showers during heavy rain as sewer backflows; local capacity issues and overflow discharges into the estuary/CBEEMS; lack of capacity at waste water treatment works; Welsh Water have recently had to do major improvements at Danlan Park; the applicant's budget to improve the sewer system has decreased from £750k to £400k.
- Low water pressure. This will decrease further.
- Highway and pedestrian safety significant increase in the volume of traffic and congestion on A484 both close to the site and further afield at Sandy Roundabout; the A484 is already the second busiest road in the County; the site is close to Pembrey Country Park, Ffos Las and the Racing Circuit all of which attract traffic especially in summer months; cumulative impact of traffic associated with other developments including Gwdig and harbour sites; already tailbacks at the Garreglwyd junction with a further 14 houses already approved and 100 proposed; priority junction arrangement proposed will not address this; the bottom of Garreglwyd is a bottleneck, especially at peak times with a high degree of on street parking and three commercial businesses; Inadequate road infrastructure; Poor visibility on to main A484 at Garreglwyd junction; the junction is already dangerous; lot of accidents occur already and the risk will be increased; cars already speed in this location; No pavements; no crossing points at the A484; Mountain Road is not suitable; issues at the M4 junction.
- The layout allows for a potential future access off Mountain Road.
- The impact from construction traffic in terms of safety and damage to roads.
- Inadequate bus service.
- Adverse impact on local schools which are up to capacity and over-subscribed.
- Adverse impact on local health services including local surgery and dental practices there is only one surgery serving Pembrey, Burry Port and surrounding areas.
- Police, fire and ambulance services stretched.
- Lack of local amenities in the village in terms of post office, shops and banks.

- Adverse impact on ecology e.g. foxes, badgers, birds, bats, dormice, slow worm and voles. The site is a natural wildlife habitat and will be lost.
- Loss of trees and hedgerows.
- Adverse impact on the adjacent Grade II* listed Court Farm which is one of the few remaining Manor Houses of its kind in Carmarthenshire; the proposed development would adversely affect the setting of the listed building; the setting will be lost in a sea of housing; the view of the building will be lost; the proposed green space within the scheme is not enough; the land used to be part of the demise of Court Farm and is therefore an integral part of its setting; the proposal will jeopardise the future restoration proposals; it will have a negative impact on the economic viability of the restoration project; inaccuracies in Heritage Impact Assessment; future generations won't be able to appreciate due to close encroachment of housing; unstable walls of the building could be affected by earth movement.
- The proposed development would have an adverse impact on an ancient sunken footpath to the immediate south of Court Farm known as 'Mucky Lane'.
- The proposed development would affect a right of way.
- Adverse impact on heritage and archaeology.
- The application to build 100 houses does not conform to the Local Development Plan for the land in question. The LDP allocates the site for 75 units.
- The site was incorrectly allocated for housing in the first place lack of local involvement in the LDP process.
- Reference is drawn to the cumulative impact with LDP candidate sites.
- There is no demand for so many houses in Pembrey. There are already numerous empty homes.
- Adverse visual impact on the character of the area due to the exposed and elevated position – loss of a greenfield site of rural character; adjacent to a Special Landscape Area; 100 dwellings of the same style and character; high density; overdevelopment; should develop vacant brownfield sites in locality.
- Environmental damage.
- Nature of ground not suitable for development.
- Adverse impact on residential amenity nuisance and disruption during construction.
- Air pollution and dust.
- Noise impact construction and increased traffic.
- Adverse effect on the Welsh language and culture.

- Lack of publicity and consultation.
- Ownership and boundary disputes.
- Notice has been served on Highways with an ownership interest conflict of interest?
- Devaluation of property.

RELEVANT PLANNING HISTORY

The following previous applications have been received on the application site:-

S/17923	Construction of 100 dwellings and associated works Withdrawn	03 April 2008
D5/14109	Residential development for large detached houses built to a low density (outline) Refused Appeal Withdrawn	09 December 1991
D5/8125	New residential development Refused	29 November 1984
75.A.8.	Residential development Refused	02 November 1972

APPRAISAL

THE SITE

The application site consists of an irregular shaped parcel of land, which is approximately 4.6 hectares in area, and is located in an elevated position within the village of Pembrey in Carmarthenshire. The site is divided into two field parcels of pasture land by a hedgerow running north-south through the site. The site slopes down from its highest point in the north east corner to the lowest point towards the south west.

The site is bounded on three sides by existing residential development. The southern site boundary runs along the rear of gardens of properties at a lower level fronting a stretch of the main A484 known as Danlan Road/Gwscwm Road. To the south east of the site there are allotments with Pembrey Community Centre beyond.

The site is bounded to the east by a small cul-de-sac of 4no. detached residential properties accessed via a T Junction off Heol Y Mynydd/Mountain Road. A gated access off this cul-de-sac provides the existing means of access to the site. Further residential properties along Mountain Road and Mumbles Head Park are located to the east and north east of the application site.

To the west of the site is a residential estate known as Garreglwyd, which emerges on to Danlan Road via a T Junction to the south. A garage and carpet shop are located on the corner of Dan Lan Road and Garreglwyd and a car dealership is situated opposite the

junction on the southern side of Dan Lan Road. The western site boundary fronts on to Garreglwyd beyond a row of mature trees.

Open countryside, which is designated as a Special Landscape Area lies to the north of the site boundary, beyond an ancient tree lined sunken lane known as 'Mucky Lane', which is a public right of way. A Grade II* Listed Building known as Court Farm and its curtilage buildings are located further to the north east of the application site beyond the mature tree lined sunken public right of way. Each boundary, except a section in the east is lined by mature trees and hedgerows.

The centre of Pembrey which consists of two public houses, a post office, pottery shop and a guest house lie just to the south of the site in a small cluster of development around Randell Square, beyond which lies St. Illtyd's Church, a Grade II listed building, which occupies a prominent position on Gwscwm Road.

Pembrey Primary School lies approximately 0.5km to the south of the site on Ashburnham Road, with planning permission recently granted for a new school on land adjacent to the existing. Access to a country park is signposted just to the west of the site along Dan Lan Road.

THE PROPOSAL

This long standing planning application seeks full planning permission to construct 100, two, three, four and five bed homes (including 20% affordable homes), public open space, ecological enhancements, landscaping and associated highways and drainage works.

The application was originally received in 2009, and was accompanied by the following supporting information:-

- Planning Statement;
- Design and Access Statement;
- Transport Assessment;
- Ecology Assessment;
- Tree Report;
- Archaeological Appraisal;
- Drainage Statement;
- Statement of Dust Mitigation;
- Travel Plan;
- Site Investigation Report;
- Bat and Reptile Assessment.

During the time that the application was received by the Local Planning Authority (LPA), there were concerns relating to water quality in the European Protected Estuary. As a result, and like many other planning applications received around that time, the LPA issued a positive screening opinion under the Environmental Impact Assessment Regulations, requiring the application to be accompanied by an Environmental Statement. Shortly afterwards, and following advice from the then Environment Agency and Countryside Council for Wales, the LPA issued a Scoping Opinion requiring a tightly scoped Environmental Impact Assessment (EIA) to assess water quality and drainage issues.

In order to inform this EIA, the applicant commissioned Dwr Cymru/Welsh Water to undertake a Development Impact Assessment (DIA) of the existing drainage infrastructure serving the Pembrey area. The purpose of the DIA was to quantify the effects, if any, of the proposed development on the existing drainage system and to identify notional solutions to resolve any potential detriment.

The Environmental Statement was subsequently received by the LPA in February, 2012 which in accordance with the regulations at the time assessed both the construction and operational effects of the proposed development, cumulative impacts and any relevant mitigation measures necessary. The following supporting reports were also received:-

- Design and Access Statement;
- Transport Assessment;
- Travel Plan;
- Ecological Walkover Survey;
- Ecology Mitigation Statement;
- Bat and Reptile Assessment;
- Tree Report;
- Archaeological Appraisal;
- Development Impact Assessment;
- Drainage Statement;
- Statement of Dust Mitigation;
- Site Investigation Report;
- Air Quality Assessment;
- Construction Noise Assessment;
- Heritage Statement.

In 2013 additional details were received including a further Heritage Report and Drainage Strategy informed by infiltration tests. Additional drawings were also received.

In 2016, a revised package of information was received with key changes made to the scheme to address matters raised in terms of highway safety, drainage and impact on the setting of the Grade II* listed building of Court Farm. In terms of highways, instead of the two access points originally proposed, namely off Mountain Road to the east and Garreglwyd to the west, only one now remained off Garreglwyd to the west. The revised layout also proposed three large public open space areas within the site. The purpose of the large green area to the north east corner of the site was to provide a buffer between the proposed housing and the listed building to the north east. The purpose of the two southern areas of open space were two fold, one in association with both providing open space, but also to accommodate attenuation basins in association with the revised surface water drainage strategy. Prior to this surface water attenuation was proposed to be attenuated in engineered tanks below the internal road.

The revised 2016 package also included the following updated reports:-

- Updated Heritage Statement;
- Updated Ecological Report;
- Updated Arboricultural Report;
- Updated Planning Statement;
- Updated Drainage Strategy;
- Updated DAS;
- Dust Mitigation;

- SI Report;
- Archaeology;
- Planning Statement;
- Tree Survey;
- Transport Assessment;
- Environmental Statement Addendum.

As a result of matters that arose during the re-consultation exercise and consideration of the package of information submitted in 2016, the most recent package of information was received in December 2018. In addition to revised drawings, the following supporting information was submitted:-

- Revised Heritage Impact Statement in light of recent legislative changes;
- Revised Drainage Strategy following further discussions with DCWW;
- Updated Ecological Appraisal in response to previous comments from NRW and Planning Ecologist;
- Welsh Language Action Plan;
- Updated Landscaping Proposals
- Drainage Plan During Construction;
- Silt Management Daily Checklist;
- Construction Method Statement:
- Dust Emission Control Plan;
- Waste Management Plan;
- Construction Management Plan;
- Revised Transport Statement;
- Planning Statement;
- Design and Access Statement;
- Environmental Statement Addendum in light of revised information and changes to the EIA Regulations;
- Habitat Regulations Screening Report.

The following additional and revised information was subsequently received in July 2019 as a result of comments received from consultees during the consultation exercise:-

- Boundary Wall and Fencing elevation drawings;
- Revised Drainage Strategy and associated drawings:
- DCWW e-mail confirming adoption of attenuation ponds;
- Drainage Technical Note outlining options for Offsite Sewer Improvements;
- Revised Soft Landscaping Proposals;
- Landscape Specification and Management Plan;
- Tree Technical Note;
- Revised Construction Management Plan;
- Revised Construction Method Statement:
- Revised Construction Traffic Management Plan;
- Management Company Plan identifying areas within the site that will be maintained by a management company.

The scheme as currently proposed includes a mixture of house types that are detached, semi-detached and terraced in nature whilst being 2 or 2.5 storey in height. The proposal is spatially denser to the western half of the site, with larger, detached properties with

more spacious curtilages proposed to the eastern half. The palette of materials proposed consist of a mixture of facing brick and render to the walls and grey concrete tiles to the roof. Some of the proposed house types have detached or integral garages in addition to driveways. The proposed boundary treatment measures consist of different height fencing to less prominent boundaries and brick walls with infill fencing panels to more visible boundaries.

As aforementioned, only one means of vehicular access is now proposed via Garreglwyd to the west. Offsite highway works are proposed at Garreglwyd in order to provide a new priority junction arrangement that will give vehicles travelling northwards along Garreglwyd priority. A standard estate road is proposed within the development with a 5.5m width carriageway with 1.8m footways either side.

There are three open space areas proposed within the revised layout, with their purpose already summarised above. A detailed landscaping scheme submitted indicates what existing trees and hedgerows are being retained and enhanced with further planting, whilst native woodland planting is proposed to the north east and a section of hedgerow translocated.

PLANNING POLICY

Local Planning Policy Context

The application site is located within the defined settlement limits of Pembrey as delineated within the Adopted Carmarthenshire Local Development Plan 2014 (LDP), and is in fact a housing allocation.

Burry Port and Pembrey are identified as a Service Centre in the Adopted LDP. Service Centres are defined as being settlements that are well located on sustainable transport corridors and demonstrate a broad range of facilities and services which provide for the needs of the settlement and a wider local catchment. Their respective status within the County and their regional contribution is reflected within the Wales Spatial Plan.

In respect of the applications policy context reference is drawn to the following Strategic and Specific planning policies: -

Policy SP1 of the LDP promotes environmentally sustainable proposals and encourages the efficient use of vacant, underused or previously developed land.

Policy SP2 of the LDP supports proposals which respond to, are resilient to and adapt to minimise for the causes and impacts of climate change. Proposals should reflect sustainable transport principles and minimise the risk of flooding including the incorporation of SUDS.

Policy SP3 of the LDP refers to the settlement framework and states that provision for growth and development will be at sustainable locations in accordance with the LDP's settlement framework. In this respect Pembrey is identified as a Service Centre.

Policy SP5 of the LDP ensures enough housing land is allocated in accordance with the settlement framework.

Policy SP6 of the LDP ensures the delivery of affordable housing that in turn will contribute to the creation of sustainable communities within the Plan area.

Policy SP9 of the LDP promotes the provision of an efficient, effective, safe and sustainable integrated transport system.

Policy SP13 of the LDP states that development proposals should preserve or enhance the built and historic environment of the County, its cultural, townscape and landscape assets, and, where appropriate, their setting in accordance with national guidance and legislation.

Policy SP14 of the LDP states that development should reflect the need to protect, and wherever possible enhance the County's natural environment in accordance with national guidance and legislation.

Policy SP17 of the LDP states that development will be directed to locations where adequate and appropriate infrastructure is available or can be readily available.

Policy SP18 of the LDP states that the interests of the Welsh language will be safeguarded and promoted.

Policy GP1 of the LDP promotes sustainability and high quality design, and seeks to ensure that development conforms with and enhances the character and appearance of the site, building or area in terms of siting, appearance, scale, height, massing, elevation treatment and detailing.

Policy GP2 of the LDP states that proposals within defined development limits will be permitted, subject to policies and proposals of the plan, national policies and other material planning considerations.

Policy GP3 of the LDP states that the Council, where necessary seek developers to enter into Planning Obligations (Section 106 Agreements), or to contribute via the Community Infrastructure Levy to secure contributions to fund improvements to infrastructure, community facilities and other services to meet requirements arising from new development. The LPA has produced Supplementary Planning Guidance on planning obligations.

Policy GP4 of the LDP states that proposals for development will be permitted where the infrastructure is adequate to meet the needs of the development. Proposals where new or improved infrastructure is required but does not form part of an infrastructure provider's improvement programme may be permitted where it can be satisfactorily demonstrated that this infrastructure will exist, or where the required work is funded by the developer. Planning obligations and conditions will be used to ensure that new or improved facilities are provided to serve the new development.

Policy H1 of the LDP refers to Housing Allocations and as aforementioned the application site is identified for housing. The housing allocation referenced T2/1/h2 has a non-committed allocation of 75 units.

Policy AH1 of the LDP requires a contribution to affordable housing on all housing allocations and windfall sites.

Policy TR1 of the LDP states that proposals which do not restrict traffic movement and/or compromise the safety of the primary road network and core network will, where appropriate be supported.

Policy TR2 of the LDP states that developments which have the potential for significant trip generation, should be located in a manner consistent with the plan's objectives and in locations which are well served by public transport and are accessible by cycling and walking.

Policy TR3 of the LDP highlights the highway design and layout considerations of developments and states that proposals which do not generate unacceptable levels of traffic on the surrounding road network, and would not be detrimental to highway safety or cause significant harm to the amenity of residents will be permitted.

Policy EQ1 of the LDP states that proposals affecting landscapes, townscapes buildings and sites or features of historic or archaeological interest will only be permitted where it preserves or enhances the built and historic environment.

Policy EQ4 of the LDP relates to biodiversity and states that proposals for development which have an adverse impact on priority species, habitats and features of recognised principal importance to the conservation of biodiversity and nature conservation (i.e. NERC & Local BAP, and other sites protected under European or UK legislation), will not be permitted unless satisfactory mitigation is proposed, and where exceptional circumstances where the reasons for development outweigh the need to safeguard biodiversity and where alternative habitat provision can be made.

Policy EQ5 of the LDP states that proposals for development which would not adversely affect those features which contribute local distinctiveness/qualities of the County, and to the management and/or development of ecological networks (wildlife corridor networks), accessible green corridors and their continuity and integrity will be permitted.

Policy EQ6 of the LDP states that proposals which enhance or improve the Special Landscape Area through their design, appearance and landscape schemes will be permitted

Policy EP1 of the LDP states that proposals will be permitted where they do not lead to a deterioration of either the water environment and/or the quality of controlled waters. Proposals will, where appropriate, be expected to contribute towards improvements to water quality.

Policy EP2 of the LDP states that proposals should wherever possible seek to minimise the impacts of pollution. New developments will be required to demonstrate and satisfactorily address any issues in terms of air quality, water quality, light and noise pollution, and contaminated land.

Policy EP3 of the LDP requires proposals to demonstrate that the impact of surface water drainage, including the effectiveness of incorporating Sustainable Urban Drainage Systems (SUDS), has been fully investigated.

Policy REC2 of the LDP requires all new developments of five or more units to provide onsite open space in accordance with the Council's adopted standards of 2.4ha per 1000 population.

Supplementary Planning Guidance

There are a number of Adopted SPG's relevant to the consideration of this planning application including:-

- Archaeology and Development;
- Nature Conservation and Biodiversity;
- Place Making and Design;
- Planning Obligations;
- Welsh Language;
- Leisure and Open Space Requirements for New Developments;
- Affordable Housing.

National Planning Policy Context

National Planning Policy is contained within the Wales Spatial Plan, which provides an overall strategic framework, together with Planning Policy Wales (PPW), originally published by the Welsh Assembly Government in March 2002 with the most recent edition published in December 2018. PPW is supplemented by a series of Technical Advice Notes (TANs).

Planning Policy Wales is the principle planning document of the Welsh Assembly Government which sets out the land-use policy context for the consideration and evaluation of all types of development. The main thrust of PPW is to promote sustainable development by ensuring that the planning system provides for an adequate and continuous supply of land available and suitable for development to meet society's needs in a way that is consistent with overall sustainability principles.

Planning Policy Wales confirms at Paragraph 1.2 that:-

"The primary objective of PPW is to ensure that the planning system contributes towards the delivery of sustainable development and improves the social, economic, environmental and cultural well being of Wales, as required by the Planning (Wales) Act 2015, the Wellbeing of Future Generations (Wales) Act 2015 and other key legislation. A well-functioning planning system is fundamental for sustainable development and achieving sustainable places."

Planning Policy Wales has always promoted the notion of sustainable development as being central to all planning decisions in Wales. PPW defines sustainable development as:-

"Sustainable Development" means the process of improving the economic, social, environmental and cultural well-being of Wales by taking action, in accordance with the sustainable development principle, aimed at achieving the well-being goals.

Acting in accordance with the sustainable development principle means that a body must act in a manner which seeks to ensure that the needs of the present are met without compromising the ability of future generations to meet their own needs"

Paragraph 1.11 of PPW states that:-

"The Well-being of Future Generations Act places a duty on public bodies to carry out sustainable development. This is not a new concept for the planning system as the principles of sustainable development have been at the heart of planning policy since PPW was first published in 2002. However, the concept has been expanded under the Wellbeing Act and it requires an improvement in the delivery of all four aspects of well-being: social, economic, environmental and cultural."

The document outlines a number of relevant sustainable development principles, chief amongst which is the promotion of resource efficient settlement patterns and minimising land-take. There is also recognition that the location of development should aim to reduce demand for travel, especially journeys by private car.

Paragraph 1.15 of PPW states that:-

"The Planning Act introduced a statutory purpose for the planning system. Any statutory body carrying out a planning function must exercise those functions in accordance with the principles of sustainable development as defined in the Well-being of Future Generations Act. The planning system is central to achieving sustainable development in Wales. It provides the legislative and policy framework to manage the use and development of land in the public interest so that it contributes positively to the achievement of the well-being goals."

Planning Policy Wales is supplemented by various Technical Advice Notes (TAN's) which provide more in depth guidance on specific issues. In this instance guidance contained in the following TAN's are applicable:-

- TAN 2 Planning and Affordable Housing (2006) advise on the role of the planning system in delivering affordable housing.
- TAN 5 Nature Conservation and Planning (2009) seeks to ensure that protected species, habitats and designated sites are both protected and conserved by the planning system.
- TAN 11 Noise (1997) provides advice on how the planning system can be used to minimise the adverse impact of noise without placing unreasonable restrictions on development.
- TAN 12 Design (2016) seeks to promote sustainability principles through good design and identifies how local planning authorities can facilitate this process through the planning system.
- TAN18 Transport (2007) endeavours to ensure Wales develops an efficient and sustainable transport system to meet the needs of a modern, prosperous and inclusive society.
- TAN 20 Planning and the Welsh Language (2017) provides guidance on how the
 planning system considers the implications of the Welsh language when LDPs are
 prepared. Further advice is provided in terms of determining planning applications
 where the needs and interests of the Welsh language may be a material
 consideration. In essence, the TAN advises that planning applications should not
 routinely be subject to Welsh language impact assessment as this would duplicate

LDP site selection processes where LDP objectives indicated the need for such an assessment.

 TAN 24 The Historic Environment (2017) provides guidance on how the planning system considers the historic environment during development plan preparation and decision making on planning and listed building applications.

With regard to protecting the integrity of the European designated site, Regulation 63 of The Conservation of Habitats and Species Regulations 2017 reads as follows:-

Assessment of implications for European sites and European offshore marine sites

- 63-(1) A competent authority, before deciding to undertake, or give any consent, permission or other authorisation for, a plan or project which—
 - (a) is likely to have a significant effect on a European site or a European offshore marine site (either alone or in combination with other plans or projects), and
 - (b) is not directly connected with or necessary to the management of that site, must make an appropriate assessment of the implications of the plan or project for that site in view of that site's conservation objectives.
- (2) A person applying for any such consent, permission or other authorisation must provide such information as the competent authority may reasonably require for the purposes of the assessment or to enable it to determine whether an appropriate assessment is required.
- (3) The competent authority must for the purposes of the assessment consult the appropriate nature conservation body and have regard to any representations made by that body within such reasonable time as the authority specifies.
- (4) It must also, if it considers it appropriate, take the opinion of the general public, and if it does so, it must take such steps for that purpose as it considers appropriate.
- (5) In the light of the conclusions of the assessment, and subject to regulation 64, the competent authority may agree to the plan or project only after having ascertained that it will not adversely affect the integrity of the European site or the European offshore marine site (as the case may be).
- (6) In considering whether a plan or project will adversely affect the integrity of the site, the competent authority must have regard to the manner in which it is proposed to be carried out or to any conditions or restrictions subject to which it proposes that the consent, permission or other authorisation should be given.
- (7) This regulation does not apply in relation to—
 - (a) a site which is a European site by reason of regulation 8(1)(c);
 - (b) a site which is a European offshore marine site by reason of regulation 18(c) of the Offshore Marine Conservation Regulations; or
 - (c) a plan or project to which any of the following apply—

- (i) the Offshore Petroleum Activities (Conservation of Habitats) Regulations 2001(a) (in so far as this regulation is not disapplied by regulation 4 (plans or projects relating to offshore marine area or offshore marine installations) in relation to plans or projects to which those Regulations apply);
- (ii) the Environmental Impact Assessment (Agriculture) (England) (No. 2) Regulations 2006(b);
- (iii) the Environmental Impact Assessment (Agriculture) (Wales) Regulations 2017(c); or
- (iv) the Merchant Shipping (Ship-to-Ship Transfers) Regulations 2010(d).
- (8) Where a plan or project requires an appropriate assessment both under this regulation and under the Offshore Marine Conservation Regulations, the assessment required by this regulation need not identify those effects of the plan or project that are specifically attributable to that part of it that is to be carried out in the United Kingdom, provided that an assessment made for the purpose of this regulation and the Offshore Marine Conservation Regulations assesses the effects of the plan or project as a whole.
- (9) In paragraph (1) the reference to the competent authority deciding to undertake a plan or project includes the competent authority deciding to vary any plan or project undertaken or to be undertaken.

Planning Policy Wales Technical Advice Note 5 'Nature Conservation and Planning' also re-iterates this advice and seeks to ensure that protected species, habitats and designated sites are both protected and conserved by the planning system. In the case of this proposed development, where there is no direct on-site impact, it concentrates on those designated Natura 2000 sites to the south within the Loughor Estuary and Carmarthen Bay area.

THIRD PARTY REPRESENTATIONS

As aforementioned, a significant number of objection letters have been received in relation to this proposed development over the last 10 years. The material reasons for concern and objection raised will now be addressed in this section of the report under the following subheadings.

Heritage Assessment

As aforementioned in this report, objectors opine that the proposed development will have an unacceptable detrimental impact on the Grade II* listed Court Farm and its associated Grade II listed outbuilding, by adversely affecting the setting of these two heritage assets. It is envisaged that the setting of these buildings will be lost in a sea of housing and that the proposed mitigation in the form of a green buffer is not sufficient. The objectors are of the opinion that the proposed development will adversely affect the future restoration proposals and the economic viability of such a project. It is also opined that the proposed development will adversely impact upon the ancient sunken lane (Mucky Lane) and the historic landscape.

Whilst the Historic Environment (Wales) Act 2016 made some amendments to the Planning (Listed Buildings and Conservation Areas) Act 1990, the 1990 act is still the primary legislative instrument addressing the treatment of listed buildings through the planning process in both England and Wales.

The way in which historic assets are assessed remains largely the same. In this respect Section 66(1) of the 1990 Act is particularly relevant in this instance and sets out the statutory duty of the decision-maker, where proposed development would affect a listed building or its setting:

"...in considering whether to grant planning permission for development which affects a listed building or its setting, the local planning authority or, as the case may be, the Secretary of State shall have special regard to the desirability of preserving the building or its setting or any features of special architectural or historic interest which it possesses."

This section of the report will apply the "special regard" test referred to in Section 66(1) in considering the potential impact on the setting of the listed buildings. In doing so reference will be drawn to the Heritage Impact Statement submitted on behalf of the applicant, relevant legislation, and relevant national and local planning policies.

Heritage Impact Statement

In order to inform the LPA's consideration of this issue, the applicant was asked to produce a Heritage Impact Statement (HIS) produced in line with relevant CADW guidelines and in conjunction with this to provide detailed cross section drawings showing the relationship between the proposed development and the existing listed buildings. The key points and conclusions of the HIS are as follows.

The site itself does not contain any 'designated' historic assets e.g. listed buildings, and is not situated within the boundary of a conservation area or historic park and garden. Therefore, the HIS opines that any potential impacts can only be indirect and expressed in terms of change to an asset's 'setting', such that its significance would be either lost or diminished.

The HIS goes on to identify the nearby heritage assets, which include the Grade II* listed church of St. Illtyd located 150m to the south. The aspect of the asset's setting which contribute to its setting are its associative relationships with its churchyard enclosure and the central part of the village that it serves. The application site is separated from the church by the main A484. Significant spatial and topographical differences exist with the application site at a much higher level. The HIS opines that the church will remain a focal point of the village and the development of the site would not compromise this.

The HIS goes on to focus on the potential for impacts on the off-site heritage assets at Court Farm. These assets are located between 40-80m north-east of the northern boundary and consist of Court Farmhouse (Grade II* listed) and the outbuilding to the south of the main farmhouse (Grade II listed). The HIS states that the highest point of application site is at 40m AOD to north east corner, whilst the land adjacent to the listed farmhouse is at 55m AOD and the listed outbuilding is at 44m AOD. The application site and these historic assets are separated by a sunken lane with mature trees either side.

The HIS also states that additional landscaping is proposed along the northern boundary and hedge translocation as part of the proposed development.

The HIS refers to the application site's allocated status for residential development in the Adopted Carmarthenshire Local Development Plan 2014, and states that this confirms that the principle of residential development on the application site is considered acceptable. With this in mind the HIS is critical of the previous Conservation Officer's comments on the basis that they did not acknowledge the allocated status of the site.

The HIS draws reference to amendments made to the proposed layout during the course of the application process by creating a buffer in the north east corner. The result of this is to focus the built form to the south and western parts of the application site on lower lying land. The eastern part of the application site is to have lower density housing.

The HIS goes on to assess the "significance" of the historic assets by using the definition of "significance" taken from Cadw's Conservation Principles, Policies and Guidance for the Sustainable Management of the Historic Environment in Wales (2011). This states that four component values make up significance namely - evidential value, historical value, aesthetic value and communal value. The report goes on to address each of these in turn before assessing whether the change within their setting would lead to a loss of "significance" in accordance with guidance set out in Cadw's 'Setting of Historic Assets in Wales' (2017).

In terms of the aforementioned Heritage Values, the HIS opines as follows:-

- Evidential Value the farmhouse and outbuilding are assessed as having 'high' evidential value because of their ability to add to and enhance our understanding of building design and construction techniques, as well as patterns of occupation and use in the 16th and 17th century Wales.
- Historic Value assessed as having 'moderate-high' value due to the long-established history of occupation on this site, reputed to go back to the 14th or 15th century albeit the structures are of a later date.
- Aesthetic Value assessed as having 'moderate-high' because despite deterioration and dilapidation some significant internal and external features remain.
- Communal Value assessed as having 'low' communal value due to the fact that
 neither building is currently occupied and are now in a poor/deteriorating condition with
 the absence of formal and progressive conservation and management. Whilst there is
 a local interest/action group, and presumed aspiration towards restoration and future
 use, the HIS opines that at the moment domestic occupation appears to be a distant
 prospect. The dilapidated nature of the buildings, and the fact that they are fenced off
 from public access and enjoyment, limits their communal value despite being nationally
 important.

Before evaluating the potential impact of development on the assets significance, the HIS addresses both the assets historic and current setting.

In terms of the assets historic setting, the report addresses the history of Court Farm in detail, and by referring to historic maps shows how the setting of the listed buildings have changed over time. When Court Farm was owned by the wealthy Vaughan family from

circa 1500 onwards it formed part of a significant estate (21,000 acres). When it was sold on centuries later and became home to tenant farmers the estate amounted to circa 200 acres and 12 acres of marshland (1831 survey). By referring to historic maps dated 1839, 1880, 1969 and 1991, the HIS shows how the setting has changed over time with the expansion of Pembrey northwards. The HIS acknowledges that historically the listed building and the application site were separate from the rest of Pembrey which was focussed around by the church, however the village has expanded northwards.

In terms of the assets current setting the HIS states that the buildings are currently both derelict and unoccupied and located on private land with no direct access. The surrounding farmland has been improved and is in separate ownership now but acknowledges that the application site would have once formed part of the Court estate. The listed buildings are within an area of trees and scrub, which presumably represents the grown-out gardens associated with the farmhouse on historic maps.

The HIS includes a series of photographs, both historic and current from different viewpoints to show how the buildings can be appreciated and their relationship with each other. It states that you can get a better appreciation from Mountain Road to the north as vegetation has been removed. Court was originally sited to take advantage of the steeply sloping ground which slopes downwards to the south in order to take advantage of the views. Due to the topography outward views overlook the application site. The report acknowledges that the dwelling and outbuilding were intentionally sited in an agricultural location and in an elevated position but states that this sense of separation has diminished during the mid-late 20th century. Whilst it acknowledges that the application site fields provide a degree of separation between the two listed buildings and the village, it opines that this is difficult to experience and appreciate from the steep hillslope to the north or the flat ground beyond Pembrey to the south due to the topography, which largely conceals the land within the site.

For the most part, it is only from along Mucky Lane or the land within the site that there is a clear and appreciable sense of separation from the village. Nonetheless, even then, it is very apparent that the immediate built surroundings of the farmhouse and the site are modern 'residential' in form and character.

The land within the site is visually and functionally separated by the north east to south west course of Mucky Lane. This feature, which is shown on the early maps, is a gently curving and deeply incised track cutting the angle between Heol y Mynydd and the east-west alignment of the A484. It is well wooded along its length, meaning that in summer at least there is a strong and well-defined sense of separation and enclosure walking along it, other than at the extreme north east and south west ends, where the margins become more open and there is an increased engagement with the surroundings.

The HIS states that the setting of the two assets contributes to their significance, in this case in terms of the ability to understand and appreciate the evidential, historic and aesthetic values that are enshrined in their standing form and fabric.

The HIS then goes on to evaluate the potential impact of the proposed development on the historic assets significance. In this respect it opines that the proposed development would have no direct physical impact on the special interest of either of the two listed buildings at Court Farm.

However it goes on to state that the implementation of the proposed development would, give rise to some loss of special interest (or significance) from the two listed buildings as a result of the change that would take place within their setting.

The HIS opines that this loss of significance/special interest would be relatively limited, and would derive from the following:

- The loss of undeveloped farmland from around Court Farm, which historically formed part of its Estate and would have underpinned the economy of the farmhouse; and
- The reduced spatial separation between the village of Pembrey and Court Farm, which was originally sited further up the slope and separate from the settlement.

The report says that even if the land use changes from agricultural to residential, it will remain a matter of historical fact that the site formed part of the Court Farm Estate. Nevertheless, the relationship between the farm buildings and the farmland that supported this farm complex will be visibly different if the development proceeds; with the appreciation that the farm buildings occupied a rural landholding separating them from the village of Pembrey being diminished.

The HIS opines that there is nothing about the fields (other than mere proximity) which shows there was an historic functional relationship with Court Farm; to all intents and purposes the site comprises two relatively nondescript fields of managed grassland surrounded and enclosed by mature hedgerows. The fields only amount to a relatively small part of the historic estate which means that the impact to the listed buildings is considered to be only limited.

The degree of spatial separation between Court Farm and the village of Pembrey has rapidly reduced during the 20th century. In that sense the HIS opines that the impact of development within the site would arise from the cumulative erosion of the buildings' spatial separation from the village over time, as opposed to being a result of this development in and of itself.

Furthermore, the topographic relationship between the village, the site and Court Farm is such that the ability to experience the spatial separation is relatively restricted in location and extent. It is concluded that, because of the intervening tree cover and steep hillslopes, the impact of this change would be relatively limited in its geographic scope, in large part concentrated around the periphery of the site.

The HIS also states that the proposals have also been developed and refined to minimise their impact on the two listed buildings, principally in terms of the layout, where a significantly enlarged area of open space has been sited in the north east corner nearest to the listed buildings. By the retention, improved management and reinforcement of the tree stock fringing the northern boundary of the site along Mucky Lane, and also in terms of storey heights, where modelling shows that the outward vista towards the Burry Inlet and the Bristol Channel beyond will be maintained and uninterrupted because of the natural hillslope and the intervening tree cover along Mucky Lane.

The HIS concludes by re-enforcing the view that there is no direct impact, and that the acknowledged loss of significance as a result of change to the buildings setting is assessed as being relatively limited.

The conclusion states that the following need to be taken into account in evaluating and assessing the impact of the proposals:-

- 1 The principle of development has long been established with its inclusion as an allocation firstly within the UDP (2006) and then in the LDP (2014).
- 2 The Inspector for the LDP found the allocation sound to include within the LDP.
- 3 The far bigger threat to the "significance" of the two listed buildings is their redundancy and long-term vacancy which has caused dereliction as opposed to changes within their wider setting.
- The physical and visual separation between the application site and the listed buildings is considered to be sufficient to mean there would be no loss of viability to bring forward restoration of these heritage assets in the longer term.
- There is nothing in legislation or policy which requires a decision-maker to preserve the setting of a listed building; it is however a desirability to which they must afford considerable importance and weight in determining the planning application.

The HIS concludes that as the 'impacts' noted above derive from the 'principle' of development on the site, as opposed to any aspect of the detailed proposals now submitted for the delivery of this allocation, it is evident there is no heritage reason why planning should not be permission granted.

Local Planning Authority's Assessment

As aforementioned, Section 66(1) of the 1990 Act requires the LPA to have 'special regard to the desirability of preserving the building or its setting or any features of special architectural or historic interest which it possesses.' In applying this test the LPA has to consider the Heritage Impact Statement and other supporting information submitted with the application, relevant legislation and planning policies/guidance, and responses from relevant statutory consultees and third parties.

The LPA agrees with the HIS in that there is no direct impact on any heritage assets, and that the main consideration at hand is the indirect impact on the setting of listed buildings. In this respect the LPA also agrees that there will be no impact on the setting of the Grade II* listed church. It is prudent to note that no third parties or statutory consultees have raised concerns in this respect and that the main area of contention seems to be the impact of the proposed development on the setting of the two listed buildings (Grade II* Farmhouse and Grade II outbuilding) at Court Farm.

Cadw's guidance 'Setting of Historic Assets in Wales' (2017) states that 'the setting of a historic asset includes the surroundings in which it is understood, experienced and appreciated, embracing present and past relationships to the surrounding landscape. Its extent is not fixed and may change as the asset and its surroundings evolve. Elements of a setting may make a positive, negative or neutral contribution to the significance of an asset.'

The Guidance advises that setting is not itself a historic asset, and the document goes on to advise that it needs to be established what the setting contributes to the significance of a historic asset and then evaluate the potential impact on that significance.

Planning Policy Wales provides the national planning policy framework for the consideration of the historic environment and this is supplemented by guidance contained in Technical Advice Note 24. These documents are consistent with Cadw's guidance in terms of assessing impact upon the setting of a listed building.

Paragraph 1.26 of TAN24 is particularly useful and states that ".....For any development within the setting of a historic asset, some of the factors to consider and weigh in the assessment include:-

- the significance of the asset and the contribution the setting makes to that significance;
- the prominence of the historic asset;
- the expected lifespan of the proposed development;
- the extent of tree cover and its likely longevity;
- non visual factors affecting the setting of the historic asset such as noise.

Paragraph 1.28 of TAN 24 goes on to acknowledge that "....Mitigation of damaging effects could be achieved through good design and in some cases screening or landscaping".

The HIS places a lot of emphasis upon the allocated status of the application site in the Adopted LDP, and the previous UDP. The LPA agrees that this is an important material planning consideration, however notwithstanding this, the LPA still has to consider the impact upon the setting of these listed buildings as part of this detailed planning application.

The LPA acknowledges that Cwrt Farm's historic setting was one of being within a large estate and that the two fields that form the application site were part of this estate. However as the aforementioned guidance acknowledges, setting can change and evolve over time, which it has in this instance with the expansion of Pembrey northwards along Mountain Road. The County road effectively defines the eastern boundary of the listed buildings. Whilst this in itself does not justify any further expansion of the village northwards the LPA agree with the HIS in that on the ground the functional relationship between the listed buildings and the fields that form the application site cannot be readily appreciated and experienced. There are a number of reasons for this which are explored in more detail below.

As aforementioned, the listed buildings at Court Farm are located at an elevated position in comparison to the application site. The base of the Court Farm outbuilding for instance is approximately 8m higher than the ridge height of Plot 77 which is one of the closest residential dwellings proposed. This difference in level ensures that views from the listed buildings extend over the application site and out across the Burry inlet beyond.

The above mentioned changes in levels along with the separation distances concerned and boundary definition again make it difficult appreciate past or present relationships between the listed buildings and the application site. The historic maps included within the HIS clearly indicate that Mucky Lane is a historic lane and has always been a defining feature between the listed buildings and the application site. This sunken lane, which is to remain undisturbed by the proposed development, is defined on both sides my dense mature trees which in the majority screen views of the listed buildings from the application

site and vice versa, especially during summer months ensuring a lack of inter-visibility. These clearly defined mature boundaries again make it difficult to appreciate the relationship between the application site and the listed buildings at Court Farm, and in turn the contribution that the application site makes to the setting of these listed buildings. It is also worthy to note that the northern boundary landscaping will be enhanced as part of the proposed development, which in addition to the open green space proposed to the north east corner of the layout will further shield the listed buildings from the proposed development.

The LPA agree that it is important to ensure that the listed farmhouse and outbuilding have the potential to retain economic viability, however in light of the expansion of the village northwards and surrounding land being in separate ownership it must be acknowledged that their future as the centre of an economically active farm are now over. The Authority's Senior Built Heritage Officer considers that providing a buffer around the property in the form of land for a garden, or sufficient land to shield the property from any residential development to the north of Mucky Lane is necessary, however the proposed development does not affect these considerations. On the point of future viability, the LPA is currently considering separate full and listed building consent applications to undertake consolidation and repair works to stabilise the vulnerable parts of the upper walls of the listed buildings (S/38591 & S/38592).

Therefore whilst the development will affect the historic setting of the listed buildings in the sense that it involves residential development on agricultural land that formed part of the original estate, the LPA does not consider that the effect on this setting adversely affects the significance of these historic assets.

In coming to this conclusion reference is drawn to relevant consultation responses. Based upon the revised HIS produced in line with up to date guidance and other revised supporting information received, the Authority's Senior Built Heritage Officer has concluded that in her opinion the proposed development is unlikely to cause damage to the setting of the listed buildings. Therefore she raises no objection towards the proposed development as shown and referred to in the most recent revised submission.

In its response CADW has confirmed that the proposed development will not cause damage to the setting of any scheduled monument whilst it does not raise concern in terms of any impact upon the historic landscape. CADW state that it does not provide an assessment of the likely impact of development on listed buildings, as this is a matter for the local authority.

Finally the Authority's Archaeological advisors, Dyfed Archaeological Trust has raised no objection and confirmed that no further archaeological investigation is necessary.

Highways

In terms of highway related matters, significant concerns and objection have been raised in relation to highway and pedestrian safety. These relate to increased traffic generation and congestion on the main A484 both close to the site and further afield, and inadequate access and visibility at the junction to serve the proposed development. It is envisaged that further tailbacks at the Garreglwyd junction will occur and that the priority junction arrangement proposed will not address this issue. The concerns relate to both construction traffic during building works and operational traffic when the development is occupied. It is also opined that there is a lack of pavements and crossings points, and inadequate public transport services.

The application when originally submitted in 2009 was accompanied by a Transport Assessment (TA). This TA has been updated over time with the most recent one dated May 2016. This TA considers the highway and transportation issues associated with a proposed residential development of 100 houses on land allocated for residential development in the Adopted LDP. A Construction traffic management plan has also been submitted.

As aforementioned in this report, when the application was originally submitted, two separate vehicular access points were proposed, one from Mountain Road to the east and one from Garreglwyd to the west. Due to objections received from the Local Highway Authority to the proposed Mountain Road access in terms of lack of visibility, inadequate carriageway width and lack of scope to achieve suitable pedestrian facilities, the application was amended in 2016 to only propose one access point via Garreglwyd. The revised TA reflects this change.

In terms of trip generation to and from the proposed development the most recent TA reveals that the vehicular trip generation will be low, at just 56 and 63 two-way movements in the AM and PM peak hours respectively. This represents a worst case trip generation in the peak hour of approximately one additional vehicular movement every minute, which is a negligible increase in the TA's opinion.

The capacity analysis undertaken of the A484/Garreglwyd priority junction demonstrates that there is sufficient capacity in all assessment scenarios to cope with the proposed development, the impact of which will be negligible according to the TA.

The trip distribution and junction capacity analysis data supplied within the TA has been considered in detail and accepted by the Authority's Head of Transport.

In terms of the access to the proposed site, it is proposed to achieve this via a new priority T-junction off Garreglwyd with priority retained for existing Garreglwyd traffic.

The proposed highway works drawing included within Appendix B of the TA includes a local narrowing to the existing highways geometry, providing a minimum carriageway width of 3.5m within a Vehicular Priority Order (VPO), with priority afforded to traffic travelling north.

The TA states that this lateral shift traffic calming feature will help to curtail traffic speed through this road section. It also facilitates the proposed improvement to the western footway, which currently has an approximate width of 0.9m. The proposal is to increase the footway width on the western side to approximately 1.8m. Where land ownership permits, a 2m wide pedestrian footway will be provided on the eastern side of Garreglwyd.

The junction of Dan Lan Road and Garreglwyd will be improved to provide clear priority markings, along with additional footway provision improvements, linking the site with the wider footway network.

The aforementioned priority junction arrangement has already been subject to a Traffic Regulation Order (TRO) consultation and approval by the Local Highway Authority. As such, the proposed arrangement which is acceptable to the Head of Transport can be secured via an appropriately worded Grampian condition prior to occupation of any of the dwellings.

The Authority's Head of Transport accepts that the proposed internal road layout has been designed to encourage low vehicle speeds with suitable 5.5m wide carriageway and 2m footways either side. The applicant's agent has confirmed that this internal road will be put forward for adoption by the Local Authority. The parking provision within the scheme is provided in line with CSS Wales Parking Standards (2008).

In terms of encouraging sustainable modes of travel, it is considered that the application site benefits from good sustainable transport provision and will be accessible on foot, bicycle and by bus. The aforementioned pedestrian facility improvements will benefit not only future residents but existing residents of Garreglwyd. The closest bus stop is located to the south of the site at Danlan Road. In terms of cycle links, it is worth noting that an affordable housing scheme currently under construction at the western end of Garreglwyd will provide a new cycle/footway link on to the existing shared use facility that runs along the line of the old mineral railway line. This will allow residents in the area to use this facility to access Randell Square in Pembrey, and Burry Port further to the east without going along the main road network. The Authority's Head of Transport has requested the imposition of a condition requiring the submission and subsequent approval of a Travel Plan to reinforce sustainable modes of travel.

The TA concludes that the development should be considered acceptable in terms of highways and transportation and that there are no reasons in highway and transportation terms why the proposed development should not be granted planning permission.

The Authority's Head of Transport has considered the TA, Construction traffic management plan and detailed drawings submitted with the application and has raised no objection towards the proposed development subject to the imposition of a series of conditions on any planning permission granted and as listed below in the report.

Foul Drainage & Water Quality

A significant number of the objections raised relate to foul drainage, with objectors stating that the development will exacerbate existing problems with the sewerage system and that the infrastructure is inadequate in this respect.

Such concerns primarily relate to health and safety concerns with objectors stating that drains already overflow resulting on occasions in sewerage back flowing into properties. Reference is also made to overflow discharges directly into the estuary/CBEEMS during heavy rainfall events. The above has resulted in DCWW needing to undertake recent major improvements at Danlan Park. Reference is drawn to the further sewerage network improvements proposed as a result of this development with the objectors questioning why the budget has reduced from £750,000 to £400,000. It is also opined that there is a lack of capacity at the Pembrey Waste Water Treatment Works themselves.

In terms of this issue, the Drainage Strategy states and provides plans indicating that the foul flows from the development will connect into the existing 300mm diameter DCWW system at Dan Lan Road.

As aforementioned in this report, during the time that the application was received by the LPA, there were concerns relating to water quality in the European Protected Estuary. As a result, and like many other planning applications received around that time, the LPA issued a positive screening opinion under the Environmental Impact Assessment

Regulations, requiring the application to be accompanied by an Environmental Statement. Shortly afterwards, and following advice from the then Environment Agency and Countryside Council for Wales, the LPA issued a Scoping Opinion requiring a tightly scoped EIA to assess water quality and drainage issues.

In order to inform this EIA, the applicant originally commissioned Dwr Cymru/Welsh Water to undertake a Development Impact Assessment of the existing drainage infrastructure serving the Pembrey area. The purpose of the DIA was to quantify the effects, if any, of the proposed development on the existing drainage system and to identify notional solutions to resolve any potential detriment.

The assessment concluded that the development would cause detriment to the network and that mitigation measures would be required to allow foul flows from the development to connect to the foul sewer network.

Since this report was produced further discussions have taken place with Dwr Cymru Welsh Water (DCWW) and a further option for improvement has been discussed with DCWW. This fourth option along with the three previous options are summarised in a Technical Note recently submitted that deals with offsite sewer improvements. The four options all provide additional capacity within the network and are summarised as follows:-

- Option 1a and 1b involves an online sewer upsize in the network with additional offline storage at The Links pumping station.
- Option 2 involves a new pumping station at the application site to attenuate flows, new rising main and new sewer with additional storage at The Links pumping station.
- Option 3 increasing the diameter of a new sewer proposed by DCWW as part of AMP6 works.

It is understood that the cost of the above improvement works vary from £400,000 to £750,000 depending upon which option is pursued. This applicant/developer will cover this cost. In their most recent response DCWW has raised no objection towards the proposed development subject to conditions. The first condition requires the drainage to be implemented in accordance with the plans contained within the drainage strategy. The second condition relates specifically to the four improvement options proposed within the technical note. All four options are considered to be feasible and will create necessary improvements within the network. However prior to works commencing on the development, the condition requires the applicant to confirm which option is be pursued and provide a timetable for its implementation. Thereafter that improvement scheme will need to be completed prior to the occupation of any dwelling. This condition will be a Grampian style condition relating to offsite works. The applicant/developer will need to agree the cost and pay DCWW outside of the planning process to undertake the works in accordance with the condition.

It is considered that the proposed improvement works will not only enable the development to proceed but will also improve existing long standing local capacity issues within the sewerage network in Pembrey. This in turn will hopefully reduce the instances of DG5's (backflow of sewerage) and CSO discharges. The provisions of the CBEEMS Memorandum of Understanding and the requirement to provide betterment do not apply in Pembrey as the waste water drains to the Pembrey treatment works. The improvements

are necessary to resolve existing local capacity issues. DCWW has confirmed that there is capacity in the treatment works itself to accommodate the foul flows from the development. This was confirmed during the LDP allocation process.

As such the proposed development is considered acceptable from a foul drainage and water quality perspective with the relevant statutory undertaker, namely DCWW raising no objection subject to conditions.

Surface Water Drainage and Flooding

A number of the representations received object on the basis that the proposed development will result in increased surface water runoff from the site to existing properties below the site which already experience flooding. Some photographs of flooded gardens have been submitted to the LPA.

It is stated that existing properties along Gwscwm Road and the allotments already flood and that this would be exacerbated by the development of this Greenfield sloping site at a higher level. The site at present is a natural soakaway but the ground is already saturated and has a high water table. The objectors ask that assurances be given that the proposed attenuation tanks will work and seek clarification on who will maintain them. Concern is also raised over surface water runoff to properties and allotments during construction.

Objectors state that the eastern ditch which is piped underneath properties along Gwscwm Road is too small and that permission will not be given to improve this pipework. The ditches outfall to the canal where the old railway is now a cycle path. This cycle path which is a safe routes path currently floods and therefore objectors ask who will be responsible for cleaning and dredging the canal.

As aforementioned the existing Greenfield site is divided into two field parcels of pasture land by a hedgerow running north-south through the site. The site slopes down from its highest point in the north east corner to the lowest point towards the south west. The Drainage Strategy confirms that there are no DCWW surface water sewers near the site.

The Drainage Strategy states that there are a number of drainage ditches which run through the sunken lane to the north of the site which subsequently connect into an inlet at Garreglwyd. These ditches will intercept any run off north of the development.

The Drainage Strategy informed by a topographical survey states that the surface water runoff from the existing site is split into a western and much smaller eastern catchment. Along the boundary of the eastern catchment area are a series of ditches which surround the allotments. These ditches discharge into a 300mm diameter culvert which passes under a domestic garage and garden of 133 Gwscwm Road and continues across the A484 until it ultimately discharges into an existing reen system/watercourse.

The western catchment of the site benefits from an existing drainage ditch at the south of the site running east to west into an existing culvert under Garreglwyd. The existing culvert is initially 450mm diameter until it crosses the A484 at which point it becomes a 600mm diameter. The system discharges behind a garage into the existing reen system/watercourse.

The proposed drainage strategy has been informed by infiltration tests undertaken at 10 different locations across the site. The tests were undertaken in accordance with BRE365

and concluded that there negligible infiltration was achieved and thus soakaways are not feasible on the site. These tests have been scrutinised and accepted by the Authority's Drainage Engineers.

As aforementioned in this report, the original surface water drainage strategy proposed to install engineered attenuation tanks below the estate road, before discharging surface water at a Greenfield runoff rate to the existing culverts to the eastern and western sides of the site. Whilst it is still proposed to attenuate rates to greenfield rates and discharge the western part of the site to the Garreglwyd culvert and the smaller eastern part of the site to the eastern culvert, the means of attenuation has now changed from engineered tanks below ground to two attenuation ponds that form part of areas of open space within the site. The detention basin to the western catchment will provide 585m3 of storage and the eastern 170m3. These volumes are inclusive of all storm events up to the 1 in 100 year plus 30% climate change event. It has been confirmed that these attenuation ponds will be adopted and maintained by Dwr Cymru/Welsh Water. DCWW has confirmed that whilst there are no standard management/maintenance schedules for the attenuation basin as the specifics of each asset can vary from site to site, this will be tailored accordingly to the scheme in due course.

The Local Authority drainage engineers have been in liaison with the applicant's engineers for many years on this proposed development. To inform their consideration of the proposed surface water drainage strategy the applicant's engineers was asked to undertake CCTV surveys of both the eastern and western culverts. Whilst some cracks and fractures were identified within the western culvert there was no displacement or broken sections. It is proposed clean out and jet this culvert as part of site works. In terms of the eastern culvert, a broken section was identified, however again only some minor jetting is proposed within the drainage strategy. The strategy acknowledges that more intrusive works to fully remediate the eastern culvert system would require access into a private property. The Authority's Drainage Engineers have stated that whilst the developer nor Carmarthenshire County Council are obligated to undertake improvement works to the culverts, it may be prudent to discuss further possible mitigation measures with the developer.

The Authority's Drainage Engineers have confirmed that the proposed drainage has been designed to maintain the status quo with regards to flow rates from the site and as such, in line with the policy requirements, there no increased flood risk. However it is likely that further water will find its way through this system as a result of this development and because there is an existing issue pertaining to the infrastructure below the proposed development site which the Authority would like to address a financial contribution of £50,000 has been requested from the applicant to facilitate improvements towards offsite culvert improvements. The applicant has confirmed that they are willing to provide such a contribution which will be secured via a Section 106 agreement. The improvement works will then be undertaken by the Authority's Land Drainage Division under the provisions of the Land Drainage Act which grants powers of entry to construct or improve a watercourse to prevent or mitigate flooding.

The above discussion has largely focussed on dealing with surface water runoff from the completed development. Due to the site's characteristics and elevated position in comparison to properties to the south, the applicant was also asked to provide information as to how surface water runoff will be dealt with during construction works. This resulted in

the submission of a Drainage Construction Method Statement and plan showing measures for dealing with surface water drainage during construction.

It is indicated that the western attenuation pond will be constructed within the first build phase to manage discharge water during site clearance and construction. The top soil strip will be undertaken in phases to manage surface water runoff on the site. The ditches on the southern and northern boundary of the site would be reinforced prior to the construction phase to ensure that surface water is drained into the ditch and runs off to the south east and south west of the site through the existing drainage system. Silt fences and sedimats will be placed along the boundary of the ditches to the south of the site to act as silt traps and to aid in silt management. Additional sedimats and straw bales will be placed across the site in key locations to again act as silt traps and assist with surface water and silt management.

Any additional surface water discharges from the site during construction will be managed through the use of other forms of silt traps on site, where necessary, including silt traps in gullies and forest gully bags and in conjunction with the Silt Management Plan. This includes a checklist to ensure that silt traps and bags are clean, that the surface water outfall is clean, that the watercourse downstream of the construction site is clean and that stockpiles/bunds are sealed.

Therefore to summarise, the proposed surface water drainage strategy has been designed to utilise existing culverts and to mimic the existing situation in terms of catchments within the site and Greenfield runoff rates. Notwithstanding this however, it is acknowledged that there are existing problems with the eastern culvert that result in localised flooding, and therefore the applicant has agreed to provide a financial contribution to facilitate improvements to this culvert. The detailed surface water drainage strategy relating to measures both during construction and post operation have been scrutinised by the Authority's Drainage Engineers who raise no objection.

Pollution (Noise Disturbance, Air Quality and Environmental Damage)

The concerns and objections raised in this respect primarily relate to the envisaged adverse impact on residential amenity from noise and disruption both during construction and from the additional traffic associated with the development. Concern is also raised from a health perspective over air pollution and dust, whilst environmental damage has also been raised.

In relation to noise, the application was originally accompanied by a Construction Noise Assessment and Noise Management Scheme. This stated that the predicted noise level of the noisiest part of the operation would be 64 dB LAeq (1 hour). This level is based on assumed plant working for 100% of the time over 1 hour periods between the hours of 07:00-19:00 Monday to Friday and Saturday 07:00-13:00 hours. In light of the information submitted and provided this noise level can be achieved, the Authority's Public Health division has raised no objection and has not recommended imposing any noise limit conditions on the proposed development.

During the site clearance and construction phases, all works and ancillary operations undertaken on site shall only be audible beyond the site boundary, or at noise sensitive residential properties within the hours of 07:00 - 19:00 Monday – Friday, Saturday 07:00 - 13:00 and not at all on Sundays, Bank or Public Holidays. Work in relation to construction must be undertaken in compliance with BS 5228 (Parts 1 - 4) in order to minimise noise

disturbance and with regard to the content of the Noise Management Scheme on pages 8 – 10 of the Construction Noise Assessment and Noise Management Scheme submitted with the application.

Therefore to ensure that the development is undertaken in accordance with Noise Assessment it is recommended that a suitably worded condition is imposed on any planning permission granted. As with any construction work the noisiest part is usually at the beginning when groundworks are being done. The latter stages of a development tend to be quieter, and of course such impacts are only on a short term basis. When the development is complete it is considered that the proposed residential end use, and associated traffic etc. is compatible with surrounding land uses. There are sufficient separation distances between the proposed dwellings and existing well established dwellings to ensure that there are no residential amenity implications in terms of overlooking or overbearance.

In terms of air quality, an Air Quality Assessment report was originally submitted with the application whilst a Dust Emission Control Plan has subsequently been received setting out measures to suppress dust. These documents have been scrutinised by the Authority's Public Health division who has confirmed that in their opinion the proposed development will not have a significant adverse impact on air quality as regulated under the Environment Act 1995 and in relation to the requirements of Local Air Quality Management.

Again it is recommended that a condition is imposed on any planning permission granted to ensure that the proposed development is undertaken in strict accordance with the measures outlined in these reports.

In terms of potential environmental damage, the submission of a Construction Management Plan and Construction Method Statement and Drainage Construction Method Statement have been welcomed by Natural Resources Wales who has raised no objection towards the proposed development subject to the imposition of conditions to ensure that the development is undertaken in accordance with these reports.

Ground Conditions

In this respect it has been opined that the nature of the ground is not suitable for development.

The planning application and proposed scheme design has been informed by a detailed Site Investigation Report. This report has not identified any geotechnical reason why the site cannot be developed in the manner proposed.

The Authority's Public Health division has assessed this report, and notwithstanding the site's Greenfield nature has adopted a precautionary approach by recommending the imposition of a condition requiring a Preliminary Risk Assessment to be undertaken in the first instance. This will identify any potential contamination levels that may present risks to human health or the surrounding environment, and if such risks do exist subsequently propose any mitigation or remediation measures.

Visual amenity & Landscape Character

In terms of visual impact and landscape character, objectors opine that the proposed construction of 100 dwellings will destroy the visual amenity of an attractive Greenfield site that has a rural aspect. Reference is drawn to the exposed and elevated position of the site which is adjacent to a Special Landscape Area (SLA). The proposed development consists of 100 dwellings of the same style and character, is high density and represents an overdevelopment of the site. Concern is also raised that the proposed development will result in a loss of trees and hedgerows and therefore the focus should be on developing brownfield sites in the locality.

As aforementioned in this report, the application site represents a long standing housing allocation in the current Adopted LDP, and its predecessor the Adopted Unitary Development Plan (UDP). Therefore there is no in principle policy objection to developing the site for residential use. As is discussed later on in this report, the proposed density is not considered excessive for such a large application site. A variety of house types are proposed of differing scales and designs, with the pallet of external materials proposed being vernacular to the area. The western section of the proposed development is more dense than the eastern, whilst the highest part of the site to the north eastern corner is to remain un-developed with additional planting proposed.

In order to inform the consideration of the proposed development in terms of landscape impact the application has been accompanied by a significant number of supporting reports and information which include the following:-

- Design and Access Statement;
- Tree Survey, Arboricultural Assessment and Constraint Report;
- Tree Technical Note:
- Detailed Soft Landscaping Proposals;
- Landscape Specification and Management Plan;
- Management Company Plan identifying areas within the site that will be maintained by a management company;
- Detailed cross section drawings taken throughout the site.

These documents have been scrutinised by relevant consultees, including the Authority's Landscape Officer.

In terms of the landscape constraint and protection information, the Tree Technical Note identifies the requirement for specific methods of construction, and protection measures in proximity to existing landscape elements identified for retention. In this respect the Authority's Landscape Officer recommends the imposition of a planning condition on any planning permission granted requiring the submission of an Arboricultural Method Statement and Tree Protection Plan prior to works commencing on the development.

The proposed Landscape Design Scheme seeks to retain and enhance as many existing trees and hedgerows as possible. The northern boundaries trees, which includes some that are protected by virtue of Tree Preservation Orders are being retained. A section of the hedgerow to be removed to facilitate the proposed development will be translocated to the north eastern boundary of the site, and in addition further native tree and hedgerow planting are proposed within the scheme. Native woodland planting is proposed to the north east corner in addition to sections along the northern boundary to re-inforce this buffer. Further hedgerow planting is proposed to the southern boundary.

The Authority's Landscape Officer has confirmed acceptance of the proposed Landscape Design Scheme, subject to the imposition of conditions requiring a hedge translocation method statement; the implementation of the approved landscape design elements and rectification of defects; and implementation of the maintenance and management information. The latter information indicates that the landscaped areas within the application site are to be managed by a management/maintenance company.

The Authority's Landscape Officer has concluded that the development proposals as defined in the reviewed documents demonstrate the potential for the effective delivery of relevant landscape policy objectives subject to the imposition of relevant conditions.

The land beyond the northern site boundary is defined as a Special Landscape Area in the Adopted LDP, which represents a non-statutory designation which was identified following an assessment of the landscape qualities of the County. The proposed development itself however does not encroach into this area, whilst as aforementioned the proposed development and its landscape strategy has considered to be acceptable by the Authority's Landscape Officer. As such it is considered that the proposed development will not have an adverse effect on the character of the SLA.

The proposal lies close to the north boundary of the Taf and Tywi Estuary Landscape of Outstanding Historic Interest, which is included in the Register of Landscapes of Historic Interest in Wales. Whilst this is again a non-statutory designation it is considered a material consideration in the determination of this application.

The sections of Pembrey and Burry Port that form part of that landscape contrast from the urban character of Burry Port where little trace of the heavy industrialised past remains other than the harbour, to the Pembrey Airfield with its former military associations and to Pembrey Mountain where reference is drawn to the 19th Century enclosed and regular field systems and dispersed farms. The latter is probably most relevant to the application site, however as aforementioned in this report, the urban form of Pembrey has expanded northwards in more recent years with residential development surrounding the site other than to the immediate north beyond a well-defined and dense tree line.

The application site is allocated for housing in the Adopted LDP, whilst the proposed layout and landscape strategy are considered to be appropriate. From a distance the site will be viewed within the context of the expanded urban form of Pembrey, and will be fully contained within existing well defined boundaries that are also proposed to be re-enforced as part of the landscape strategy. The Authority's Archaeological Advisors Dyfed Archaeological Trust and Cadw, both of who were involved in developing the historic landscape register, have raised no objection to the proposed development in this respect.

Therefore the LPA considers that the proposed development will not have an adverse impact on the open countryside nature of the Pembrey Mountain part of the designation, and thus conclude that the proposal will not adversely affect the Taf and Tywi Landscape of Outstanding Historic Interest.

Ecology

In this respect objectors have opined that the proposed development will have an adverse impact on ecology including foxes, badgers, birds, bats, dormice, slow worm, and voles. The site is a natural wildlife habitat and will be lost.

The application was originally accompanied by an ecological survey, ecological mitigation statement and Bat and Reptile assessment, and such surveys have subsequently been updated in 2016 and 2018. The most recent updates have taken on board advice previous advice provided by both NRW and the Authority's Planning Ecologist.

These reports have been scrutinised by both Natural Resources Wales and the Authority's own Planning Ecologist. NRW have raised no objection towards the proposed development on Ecological grounds subject to the imposition of conditions in relation to identified mitigation measures relating to Dormice, a European Protected Species.

In a similar vein the Authority's Planning Ecologist has confirmed that she is satisfied with the level of assessment made, the findings of the submitted assessments, and the ecological recommendations provided within the aforementioned documents. She therefore considers that the recommendations meet the LDP policy objectives listed above and the requirements of the Environment Act Wales 2016.

The most recent consultation response from both NRW and the Authority's Planning Ecologist focus on matters relating to Dormice and Protected Sites.

In terms of Dormice, it is noted from the Ecological Appraisal report that habitats suitable to support dormouse, a European protected species, were recorded on site. Although the survey was limited to a single visit on 1 September 2017 and no species-specific surveys of the site have been undertaken to date, the report assumes dormice to be present within the boundary hedgerows and trees as records exist of dormice within 1 km in connected habitat.

NRW has welcomed the mitigation measures for dormice detailed in section 4.1 of the ecological appraisal including the creation of a new woodland area in the north east corner of the site and bolstering of the northern boundary with additional planting 3-10m in width. In addition, the translocation of the central hedgerow to the north eastern boundary of the site and that existing hedgerows on the southern boundary will be strengthened with new planting and gaps filled in along its length. NRW advise that habitat being provided as mitigation for dormice (i.e. bolstered vegetation/ woodland/buffers) will need to be separated from the development plots by a wall or close boarded fence of a minimum height of 1.8m. Furthermore, any mitigation measures to be provided need to fall outside the curtilage of any individual development plots to ensure its longevity and protection.

Subject to the implementation of the above measures, NRW consider that these features can maintain suitable dormouse habitat on site in the long term. NRW therefore consider that the submitted proposals provide an adequate basis upon which to make an informed assessment of the likely impact on dormice and that it should be possible to address the conservation of dormice via the imposition of suitable conditions attached to any planning permission granted.

As Dormice are a European Protected Species by virtue of their listing under Annex IV of EC Directive 92/43/EEC ('The Habitats Directive'), a European Protected Species (EPS) Licence is required for this development. This Directive has been transposed into British Law under the Conservation of Habitats and Species Regulations (2017). As the survey revealed the likely presence of dormice, work will require derogation in the form of a licence from NRW, which the developer has to apply for. Before such a licence can be granted, the following tests (specified in Article 16 of the EU Habitats Directive and in regulation 55 (9) of the 2017 Regulations) must be satisfied:

- (i) there is "no satisfactory alternative" to the derogation;
- (ii) the derogation is "not detrimental to the maintenance of the populations of the species concerned at a favourable conservation status in their natural range";
- (iii) the derogation is "in the interests of public health and public safety, or for other imperative reasons of overriding public interest, including those of a social or economic nature and beneficial consequences of primary importance for the environment".

Planning Policy Wales states that to avoid developments with planning permission subsequently not being granted a licence in relation to a EPS, planning authorities must take the three requirements for a derogation into account when considering development proposals where a EPS is present and must be satisfied a where an EPS licence is required it will be granted by NRW.

In terms of the first and third tests, the alternative of not developing the site is not considered satisfactory as this will not contribute to delivering the LDP's strategic objectives in terms of housing, whilst the proposed development will result in social benefits by providing modern new housing including a significant element of affordable housing.

The proposed development is not considered to be detrimental to the favourable conservation status of Dormice as appropriate mitigation measures have been proposed and confirmed to be acceptable by both NRW and the Authority's Planning Ecologist.

Therefore the LPA considers that the proposed development does satisfy the above tests of derogation.

In terms of protected sites, there are several designated sites within the locality of the application site. The Carmarthen Bay and Estuaries Special Area of Conservation (SAC) is 1.1km from the site, the Burry Inlet Special Protection Area (SPA) and Burry Inlet Ramsar site is 1km from the site, the Carmarthen Bay Dunes (SAC) is 1km from the site and the Carmarthen Bay SPA is 2.9km from the site. The site will be hydrologically connected to the designated sites via surface water connections, whilst the foul water connection is also a consideration.

As a competent authority under Regulation 63 of the Conservation of Habitats and Species Regulations 2017 the council has to consider the impact of development on the features for which the aforementioned site is designated. A Test of Likely Significant Effect (TLSE) and Appropriate Assessment (AA) has been done for the site, and this has been sent to NRW for comment.

The TLSE and AA have been informed by the Habitat Regulations Assessment (HRA) Report submitted by the applicant. The HRA Screening for the site identifies the following potential impacts:-

- Construction phase impacts on water quality by pollution run-off.
- Impacts on water quality during operation.

As the applicant has proposed mitigation measures specifically incorporated in the scheme, that are likely to be necessary to remove the risk of significant effects, it is conceded that an appropriate assessment is necessary for the project elements for which mitigation relates.

In terms of the AA, one of the key issues discussed in the ES addendum is the potential impact that any revised or additional water discharges, either foul or surface, will have on the local drainage systems and, further afield and the potential impact on the nearby nationally and internationally important coastal features around the CBEEMS and Carmarthen Bay Dunes SAC in terms of water quality. The existing hydrological regime of the area discharges into the CBEEMS.

In terms of construction impacts there are no existing watercourses on the site other than existing ditches along the southern boundary. The Indicative Construction Layout Plan identifies the proposed management of the surface water drainage at the site through the construction phase. Attenuation 'pond A' would be constructed within the first build phase to manage discharge water during site clearance and construction. The top soil strip will be undertaken in phases to manage surface water runoff on the site. The ditches on the southern and northern boundary of the site would be reinforced prior to the construction phase to ensure that surface water is drained into the ditch and runs off to the south east and south west of the site through the existing drainage system.

During construction, sediment will be generated from a number of activities which may include excavation, additional vehicle movements, material and earth stock piling and through vegetation clearance. Where sediments enter a surface water body, the level of suspended solids would increase which would result in an increase in turbidity and potentially a reduction in dissolved oxygen. Both of these would affect the chemical water quality. As a result, increased sedimentation could reduce the potential for the site to support aquatic life. Sediments could also act as transporters of pollutants and enable hazardous material produced from construction activities to migrate off site.

The storage and use of fuel, chemicals, and other potentially polluting substances close to watercourses or other surface water bodies including drains, may lead to a pollution incident whereby a water body is contaminated. This could result in chemical pollution detrimental to fish and other aquatic organisms. Common chemicals that are likely to be used and stored on site include diesel, synthetic lubricating oil, mineral lubricating oils and paint.

Potential pollution effects can chemically impair biological functions and the latter are sediments which smother feeding and breeding grounds. The various construction activities, may result in sediments and pollutants entering the watercourses which would affect downstream water quality and could have a short term impact on the biology, including invertebrates and fish.

The area of the site and its potential discharge quantity into the estuary is considered very small when compared to the total estuaries catchment. Based on the site and its potential to effect the estuary it is considered that any pollution incident on site would have a minor magnitude of impact on the estuary.

Sufficiently detailed mitigation measures have been submitted to enable the competent authority to be satisfied that there would not be the likelihood of a significant effect on water quality however due to the recent European Court ruling that states that measures

intended to reduce harm (mitigation) to European sites should not be considered when screening a plan or project therefore this appropriate assessment is being undertaken.

As part of the application the applicant has provided a Construction Method Statement which proposes the following measures to reduce impacts to the SAC:-

- Silt Management Plan and Site daily checklist.
- Wheel cleaning and wash down regimes.

The applicant has also submitted the following details:-

- Drainage Plan for Construction received 05/12/18;
- Construction Management Plan received 05/12/18;
- Mitigation Measures detailed in the Environmental Statement Addendum dated November 2018;
- Appendix C of the HRA Screening Report Received 27/02/18.

If the mitigation measures as listed above are implemented accordingly then there are unlikely to be any significant impacts on water quality within the designated sites during construction.

On the basis of the submitted information and taking account of the conservation objectives of the site it is considered that the proposal would not contribute to deterioration of water quality within the designated site alone or in combination with other plans and projects, if the competent authority (CCC) imposes following conditions.

In terms of foul water the main concern is that the capacity improvements intended in the AMP 4 programme for the Pembrey catchment have not been fully implemented and currently the capacity of the system is insufficient to accommodate the proposed development. In this case the applicant is prepared to undertake reasonable up-grading works in order to facilitate the development. A series of improvements and a drainage strategy have been agreed with DCWW.

The design of the proposed works are detailed in the Drainage Technical Note and on the Drainage Strategy plans.

The planned improvements will provide significant betterment to the existing system with no additional surface water entering the combined system in future. Following the implementation of the up-grading works, foul sewage emanating from the development will discharge by gravity to an existing public sewer (combined) which will discharge via the pumped transfer system to Pembrey Waste Water Treatment Works (WwTW). Treatment at the WwTW is consented for Biological Oxygen Demand (BOD), Suspended Solids (SS) and Ammonia only and it is understood that the facility is currently operating within its consent parameters.

The WwTW is not designed or consented for nutrients (i.e. nitrates and phosphates). In this case nutrient removal has not previously featured although some nutrient removal occurs through the existing treatment process. It is clear however that, with the exception of nutrient removal, and following the up-grading works to be agreed with DCWW, the treatment facilities at Pembrey WwTW will be of a capacity which can accommodate the currently proposed development of 100 dwellings.

At Pembrey WwTW the existing treatment process results in a percentage of the nitrates being removed from the effluent before discharge to the Estuary. The consent standards for the treated effluent include an ammonia restriction and all consent standards are understood to have been achieved in recent times.

In the longer term as surface water is progressively removed from the combined systems and further up-grading works are undertaken on the sewerage network then less spillages will occur at the CSOs for any given event and as such more of the nitrates will be pumped to the WwTW (as opposed to discharging into the Estuary via the CSO's) for treatment. This should result in an increase in the removal of nitrates through the treatment process at the WwTW and consequently there would be a decrease in the load of nitrates discharged into the Estuary.

Discussions with NRW have resulted in agreement that generally the only mitigation which is reasonably under the control of the developers would be the removal of surface water from brown field developments and the provision of separate foul and surface water sewers serving new developments. For catchments not fully compliant with the Shellfish Waters Directive there may be the requirement to provide temporary supplementary on-site storage to reduce the potential for spillages. The removal of any surface water from the combined system would be greatly beneficial in that the removal would result in fewer CSO spills thereby reducing bacterial and nutrient impact on the controlled waters.

If the mitigation measures as listed above are implemented accordingly then there are unlikely to be any significant impacts on water quality within the designated sites as a result of foul water disposal. On the basis of the submitted information and taking account of the conservation objectives of the site it is considered that the proposal would not contribute to deterioration of water quality within the designated site alone or in combination with other plans and projects, if the competent authority (CCC) imposes conditions on any planning permission granted.

In light of the best scientific knowledge, the planning authority is convinced that there would be no adverse effects on the integrity of the Carmarthen Bay and Estuaries SAC or Burry Inlet SPA and Ramsar site, Carmarthen Bay SPA and Carmarthen Bay Dunes SAC as a result of the development. No reasonable scientific doubt remains as to the absence of such effects because of conditions and restrictions that will be imposed on the consent as detailed within the AA.

The AA therefore concludes that the proposed development will not result in any adverse effects that will affect the integrity of the Carmarthen Bay and Estuaries European Marine Site (CBEEMS) which collectively comprises the Carmarthen Bay and Estuaries Special Area of Conservation, Carmarthen Bay Special Protection Area and the Burry Inlet Special Protection Area & Ramsar Site or the Carmarthen Bay Dunes SAC as the proposal will not undermine the area's conservation objectives. As aforementioned this AA has been sent to NRW for sign off, and any response received will be reported to Members as part of the addendum.

Welsh Language & Culture

A number of the objectors have opined that the proposed development will have an adverse effect on the Welsh language and culture of the community.

Whilst a full Welsh Language Impact Assessment has not been required by the LPA, a Welsh Language Action Plan Statement dated November 2018 has been submitted by the applicant and will be reviewed in this section of the report.

Paragraph 3.26 of Planning Policy Wales states that planning authorities must consider the likely effects of their development plans on the use of the Welsh language as part of the Sustainability Appraisal. Planning authorities should seek to ensure a broad distribution and phasing of development that takes into account the ability of the area or community to accommodate development without adversely impacting use of the Welsh language.

Paragraph 2.1.5 of TAN 20 re-enforces this position by stating that when producing LDPs it is possible to assess the potential cumulative effects of development on the Welsh language across the plan area. This provides an opportunity to consider effects on local communities and the wider plan area together. Furthermore, one of the key benefits of a plan-led system is to give certainty and confidence to developers and to communities; the best way of doing this is to consider the use of the Welsh language during the preparation of LDPs.

In this respect the application site is a long standing housing allocation, being firstly allocated in the former Adopted Unitary Development Plan, 2006, and carried forward as an allocation in the current Adopted Local Development Plan, 2014. The LDP was subject to Sustainability Appraisal which addressed the Welsh language. As such there is no in principle objection to developing the site for housing.

This plan led approach is further emphasised in the following paragraphs of TAN 20:-

- 3.1. In determining individual planning applications and appeals, considerations relating to the use of the Welsh language may be taken into account so far as they are material. Section 70 (2) TCPA does not give any additional weight to the Welsh language above any other material consideration and decisions on all applications for planning permission must be based on planning grounds only and be reasonable.
- 3.1.3 Planning applications should not routinely be subject to Welsh language impact assessment, as this would duplicate the SA and LDP site selection processes. Provided that the SA has given due consideration to the Welsh Language, an impact assessment at application stage would not be based on any further information than that which has been presented during the plan preparation stage.

Notwithstanding the above, this is an important material planning consideration as emphasised in the Wellbeing of Future Generations Act 2015 and hence the request for the applicant to submit a statement addressing the matter.

The Statement submitted, using the average household size for the Pembrey Ward as derived from the 2011 Census information - 2.4 persons per household, states that the proposed development will result in a population increase of 240 (2.4 x 100). According to the 2017 mid-year populations estimates by ONS the ward of Pembrey has a population of 4,128, a reduction of 173 (- 4%) since 2011. The proposed development could therefore result in just short of a 6% increase in population in the ward of Pembrey.

The 2011 census identified that 31.1% of the Pembrey ward could speak Welsh, one of the lowest proportions within Carmarthenshire albeit higher than the national average of 19%. The percentage in Carmarthenshire as a whole was 43.9%.

It is nevertheless evident that the Welsh Language forms an important role and feature of the community of Pembrey. As such it needs to be ensured that any proposed development within this community wherever possible protects and promotes the Welsh language, as well as mitigate any negative impacts such a development may introduce.

Policy SP18 of the LDP states that the interests of the Welsh language will be safeguarded and promoted. It goes on to state that proposals for residential developments of 10 or more dwellings in Service Centres, located on sites within communities where 60% or more of the population are able to speak Welsh, will be subject to a requirement for phasing. As the percentage of Welsh speakers in Pembrey is 31.1% the proposed development does not need to be subject to a phasing agreement, although its impact on the Welsh language still needs to be considered and mitigation should be proposed in accordance with PPW and TAN 20 where relevant.

Examples of mitigation measures may include Welsh/bilingual signage and bilingual marketing material (for residential sites); features that promote the Welsh language as an intrinsic element of design and layout, provision of affordable housing for local needs, support for the provision of Welsh medium schools and support funding for language and cultural awareness initiatives.

The proposed development is estimated to increase the population of Pembrey by 240 but as noted the population has declined in the ward from 2011 to 2017. The increase in population may not necessarily come from outside the County. The supporting statement refers to information from Persimmon at their new site in Hendy where 89% of purchasers came from Carmarthenshire or Swansea authorities. Only 4% of purchasers on that development came from outside Wales.

Based on the above statistics the report estimates that 60 of the 240 new residents will be able to speak Welsh. This is purely an estimate but could be higher as the percentage of Welsh speakers in Pembrey is less than other wards in the County and therefore if residents and their children move in from other wards they are more likely to be able to speak Welsh. The statement opines that non Welsh speaking purchasers may want to learn to become part of the community and thus have a positive effect.

The supporting statement opines that the new housing proposed will not result in out migration. Again reference is drawn to the fact that the population has decreased within the ward in recent years, whilst the new build rates in Carmarthenshire as a whole have been low. The proposed development of 100 houses will provide a mix of house sizes, tenures and affordability, which will be suitable as starter or family homes but also provide larger houses to those looking for opportunities to upsize. 20% of the units will be affordable and secured as such in perpetuity. The house prices for the dwellings will be based on an analysis of the local housing market.

The supporting statement states that there is no evidence to suggest that existing local welsh speaking households will leave the ward as a result of the proposed development.

The statement concludes that the proposed development will mainly have neutral or positive effects on the Welsh language. Whilst not identifying any negative impacts it does

suggest some mitigation measures to promote the Welsh language and facilities i.e. schools, local Welsh lessons in the community in sales promotions and making use of bilingual marketing materials.

Therefore to summarise, the application site is allocated for housing in the Adopted LDP, which itself was subject of a detailed Sustainability Appraisal, that amongst other things considered the impact of proposed developments and allocations on the Welsh language. Whilst the proposed development is estimated to increase the current population of Pembrey by 240, the population of the ward has declined by 173 since 2011 and 2017. Even though the Welsh language and culture is clearly an important community factor in Pembrey, the Ward at present has a low percentage of Welsh speakers.

According to the developers own sales information on one of their other sites in Carmarthenshire, purchasers of new dwellings on their developments are normally quite local, with limited numbers from outside of Wales. Based upon the statistics it is estimated that at least 60 of the additional 240 people will be able to speak Welsh, which would have a positive impact. The proposed development will provide a variety of housing opportunities including 20% affordable units, which could potentially improve the current trend of out migration by increasing the local offer. The applicant has also agreed to provide a contribution of £146,000 towards local school improvements.

The LPA agrees with the reasoned opinions made in the supporting statement and on balance it is considered that the proposed development will not have a detrimental effect on the Welsh language and culture or undermine its long term viability in Pembrey. Notwithstanding this, the proposed mitigation measures suggested are welcomed and can be secured via an appropriately worded condition. As such, the proposed development in the LPA's opinion accords with the provisions of PPW, TAN 20 and Policy SP18 of the LDP in terms of the Welsh language.

Non-Compliance with Local Development Plan

Objectors have opined that the application site was incorrectly allocated for housing in the LDP in the first place as there is no local demand and that there was a lack of local involvement in that process. Notwithstanding this, objectors opine that the proposal to build 100 houses does not conform to the LDP as the site is allocated for 75 units. Reference is also drawn to the cumulative impact of a development of this scale with LDP candidate sites.

Dealing with each matter in turn, the application site represents a long standing housing allocation that was originally allocated for housing in the Adopted Carmarthenshire Unitary Development Plan, 2006 (UDP), and was carried through as an allocation into the current adopted LDP. Its status as a housing allocation in the Adopted LDP was confirmed by a Planning Inspector appointed by Welsh Government following a thorough examination process during the course of which objectors to the scheme made both written, and verbal representations at the examination in public. The relevant LDP preparation process was subject to all relevant statutory consultation and involvement.

The allocated status of the site confirms that the principle of a suitably designed housing led development on this site is reflective of, and in accordance with, planning policy. The intention of developing this site within the Plan period a view to confirming its deliverability and potential contribution towards meeting the Plan's strategic objectives is welcomed in this respect. The figure of 75 units referred to in the LDP against the allocation is for

indicative purposes only and is not the maximum figure considered appropriate for the site. The proposed development of 100 houses on a 4.6ha site represents a density of 21.7 dwellings per hectare, which is not considered overly dense.

In terms of the reference made to the cumulative impact of the proposed development with candidate sites put forward as part of the current LDP review process, it is important to note that the candidate sites are purely that at this stage, and are not confirmed allocations in that respect. Their acceptability will be assessed as part of the LDP review process.

Local Infrastructure

It is opined that the local infrastructure is insufficient to cope with the scale of development proposed. In addition to the concerns raised over sewerage and highways which have already been addressed in this report, objectors opine that the proposal will have an adverse effect on local schools which are up to capacity and over-subscribed. Reference is also drawn to the impact on local health services including the local surgery and dental practices, and emergency services which are already stretched. It is stated that there are a lack of local amenities in the village in terms of a post office, shops and banks whilst reference is also made to low water pressure, which is envisaged to further reduced as a result of the development.

In terms of the impact on local schools, it has been calculated that the proposed development will result in a pupil yield of 40 for primary, and 20 for secondary. The relevant primary schools, namely Pembrey (English Medium) and Parc Y Tywyn (Welsh) have 24 surplus spaces each. The relevant secondary schools namely Glan Y Mor and Stradey have 288 and 147 surplus spaces each. As is noted in the following section of this report, using the relevant formulas included within the Planning Obligations SPG, a financial contribution of £146,000 has been requested from the development towards improving local education facilities. The applicant has agreed to this contribution which will form part of the S.106.

As aforementioned in the previous section of this report, the application site represents a long standing housing allocation that was subject to both the previous UDP and current LDP plan preparation process. As part of that process, local service providers, including the local Health Board would have been consulted on the proposed allocations.

The proposed development of 100 houses is not considered to be excessive in scale, and in terms of the amenities listed by objectors it is not uncommon for residents to travel further afield to gain access to such facilities.

In terms of water pressure, reference is drawn to the consultation response received from Dwr Cymru Welsh Water who has raised no objection towards the proposed development.

Community Benefits

As aforementioned Policy GP3 of the LDP states that the Council, where necessary seek developers to enter into Planning Obligations (Section 106 Agreements), to secure contributions to fund improvements to infrastructure, community facilities and other services to meet requirements arising from new development. Policy AH1 and REC2 are also relevant in this respect.

The LPA has also produced Supplementary Planning Guidance on planning obligations, with specific reference made to affordable housing, education, and leisure, recreation and open space.

With regards to this application the applicant has agreed to the following community benefit contributions:-

- 20% on site affordable housing units to be secured and managed through a Section 106 agreement;
- £146,000 financial contribution towards improving local education facilities;
- On site provision of a Local Area of Play (LAP). The exact detail of the LAP and its provision will be secured via an appropriately worded condition.

Other Matters

As Members of the Planning Committee will be aware, ownership and boundary disputes and devaluation of property are not material planning considerations.

In terms of lack of publicity and consultation, the original planning application submission in 2009 and all subsequent re-consultation exercises listed above have been publicised in strict accordance with relevant requirements.

The development as proposed will not affect the existing right of way along the sunken path to the north. It will be the responsibility of the developer to ensure that this footpath is not obstructed or encroached upon at any time.

With regards to the notice that has been served on the Authority's Highways section, the reason for this is because the extent of the application site red line encompasses the section of road at Garreglwyd where the priority junction arrangement is proposed.

CONCLUSION

The application site is located within the defined settlement limits of Pembrey as delineated within the Adopted LDP and is allocated for housing. Therefore there is no inprinciple objection to developing the site for residential use. The development of this site contributes towards meeting the strategic housing objectives of the LDP.

The application has been accompanied by a significant amount of supporting information which has been updated as required over time. This information has been considered in detail by relevant statutory consultees who have raised no objection to the proposed development on technical or policy grounds.

The proposed development does provide agreed community benefit contributions towards affordable housing, education and open space, whilst the planned improvements in terms of surface water culverts and foul network improvements will also be of benefit to the locality.

The application has generated a lot of opposition however it is considered that the material reasons for objection raised have adequately been addressed as part of the above appraisal.

Members should be aware that Welsh Ministers have received a Section 77 call in request on this application. In order to consider this call in request they have issued an Article 18 direction restricting the LPA from granting planning permission at this time. This direction does not prevent the LPA from making a resolution on this application, however no decision, other than a refusal can be issued at this time.

The decision considers the duty to improve the economic, social, environmental and cultural well-being of Wales, in accordance with the sustainable development principle, under section 3 of the Well-Being of Future Generations (Wales) Act 2015 (the WBFG Act). The decision takes into account the ways of working set out at section 5 of the WBFG Act and it is considered that this decision is in accordance with the sustainable development principle through its contribution towards one or more of the Welsh Ministers' well-being objectives set out in section 8 of the WBFG Act.

On balance after careful examination of the site and its surrounding environs in the context of this application, together with the representations received to date it is considered that the proposal does accord with the Policies contained within the Adopted LDP. As such the application is put forward with a recommendation for approval subject to the following conditions, the successful completion of a S.106 agreement and sign off from NRW on the Appropriate Assessment.

Recommendation – Approval

CONDITIONS

- 1 The development hereby approved shall be commenced before the expiration of five years from the date of this permission.
- The development hereby permitted shall be carried out strictly in accordance with the following schedule of plans:-
 - Site location plan (LP-01) 1:1250 @ A3 received 27th May, 2016;
 - Topographical survey 1:500 @ A0 received 5th December, 2018;
 - Site section A-A to H-H @ A3 (SS01-Rev B) received 5th December, 2018;
 - Construction management plan (393.PL-01 Rev M) 1:1000 @ A3 received 5th December, 2018;
 - Drainage plan during construction (393. PL-01 Rev M) 1:1000 @ A3 received 5th December, 2018;
 - Proposed vehicle priority order 1:250; 1:500 @ A3 (PM02) received 5th December, 2018;
 - Roseberry (Village) floor plans and elevations 1:100 @ A3 (RS-WD16-Rev U) received 5th December, 2018;
 - Strand (Village) floor plans and elevations 1:100 @ A3 (ST-WD10-Rev L) received 5th December, 2018;
 - Mayfair (Village) floor plans and elevations 1:100 @ A3 (MY-WD10-Rev J) received 5th December, 2018;
 - Harley (Village) floor plans and elevations 1:100 @ A3 (HY-WD10-Rev N) received 5th December, 2018;
 - Marleyborne (Village) floor plans and elevations 1:100 @ A3 (ME-WD10-Rev H) received 5th December, 2018;

- Chedworth (Village) floor plans and elevations 1:100 @ A3 (CD-WD10-Rev T) received 5th December, 2018;
- Hanbury (Village) floor plans and elevations 1:100 @ A3 (HB-WD16-Rev W) received 5th December, 2018;
- Souter (Village) floor plans and elevations 1:100 @ A3 (SU-WD16-Rev Z) received 5th December, 2018;
- Chatsworth (Village) floor plans and elevations 1:100 @ A3 (CT-WD11-Rev F) received 5th December, 2018;
- Hatfield (Village) floor plans and elevations 1:100 @ A3 (HT-WD16-Rev U) received 5th December, 2018:
- Clayton (Village) floor plans and elevations 1:100 @ A3 (CA-WD16-Rev G) received 5th December, 2018;
- Fenchurch (Village) floor plans and elevations 1:100 @ A3 (FH-WD10-Rev J) received 5th December, 2018;
- The Alnwick (Village) floor plans and elevations 1:100 @ A3 (AN-WD16-Rev L) received 10th December, 2018;
- Floor plan and elevations 1:100 @ A3 (628-WHQS-WD01) received 8th January 2019;
- Floor plan and elevations 1:50 @ A1 (835-WHQS-WD01 Rev F) received 8th January 2019;
- Construction Management Plan received 8th July, 2019;
- External details 600mm brick wall with hit and miss fence 1:20 @ A3 received 8th July, 2019;
- External details 1200mm timber post and two rail fence 1:20; 1:5 @ A4 (D32) received 8th July, 2019;
- External details 1800mm timber hit and miss fence 1:20; 1:5 @ A4 (D17) received 8th July, 2019;
- Management Company Plan 1:500 @ A1 (393-MCP-01 Rev D) received 8th July, 2019;
- Detailed soft landscape proposals plan (TDA.2185.01 Rev F) 1:500 @ A0 received 8th July, 2019;
- Planning layout plan (393 PL-01 Rev N) Construction Traffic Management Plan 1:500 @ A1 received 8th July, 2019;
- Planning layout plan (393 PL-01 Rev Q) 1:500 @ A1 received 8th July, 2019;
- Engineering Drawing (Sheet 1 of 2) 10217-100-01 Rev F 1:250 @ A0 received 8th July, 2019;
- Engineering Drawing (Sheet 2 of 2) 10217-100-02 Rev F 1:250 @ A0 received 8th July, 2018.
- Prior to the use of the approved estate road by vehicular traffic, visibility splays in compliance with Technical Advice Note 18 (Transport) page 44 shall be formed and thereafter retained in perpetuity, either side of the centre line of the access road in relation to the nearer edge of carriageway.
- Prior to the beneficial occupation of any of the dwellings herewith approved, the required access roads and foot(ways/paths) from the existing public highway shall be laid out and constructed strictly in accordance with the plans herewith approved, to at least the base course levels, and with the visibility splays provided.
- 5 Prior to the beneficial occupation of any of the dwellings herewith approved, the approved vehicular priority order on Garreglwyd shall be constructed strictly in

accordance with Appendix B of the Transport Assessment drawing ref: (15-00412/PM02 Rev B) received on 5th December, 2018; which includes the localised widening of the existing highway geometry, providing a minimum carriageway width of 3.5m within a Vehicular Priority Order (VPO), with priority afforded to traffic travelling north.

- The parking spaces and layout shown on the plans herewith approved shall be provided prior to any use of the development herewith approved. Thereafter, they shall be retained, unobstructed, for the purpose of parking only.
- Prior to the commencement of development a detailed Travel Plan, setting out ways of reducing car usage and increasing walking and cycling to and from the development, shall be submitted to and agreed in writing by the local planning authority. The detailed Travel Plan shall be implemented in accordance with the approved details at a timescale to be approved in writing by the local planning authority.
- 8 No development shall take place until a detailed Construction Traffic Management Plan is submitted for the written approval of the local planning authority and thereafter shall be implemented in full and as agreed.
- Prior to the commencement of development, the written approval of the local planning authority is to be obtained for a scheme detailing the provision and frequency of use of facilities for washing down the wheels of vehicles prior to entering the public highway. The scheme shall then be implemented as approved.
- The development hereby approved shall be undertaken in strict accordance with the measures proposed in the Dust Emission Control Plan received by the local planning authority on 5th December, 2018.
- 11 The development shall be undertaken in strict accordance with the Construction Noise Assessment and Noise Management Scheme submitted with the application and received by the local planning authority on 20th February, 2012.
- 12 No development shall take place on the application site until the applicant has:-
 - Prepared a desktop study (Preliminary Risk Assessment) which shall include the identification of previous land uses, potential contaminants that might reasonably be expected given those uses and other relevant information, such as pathways and exposure to potential receptors. This information shall also be presented in tabular or diagrammatical form (Conceptual Site Model) for the site and all potential contaminant sources, pathways and receptors shall be included. In order to complete the conceptual site model, it may be necessary at this stage to undertake limited exploratory sampling. The Preliminary Risk Assessment shall be submitted to and be approved by the local planning authority.
 - Prepare a detailed scheme for the investigation and recording of contamination for the site (where necessary). The detailed site investigation report (Quantitative Risk Assessment) shall be submitted to and approved by the local planning authority.

The report shall be prepared in accordance with recognised current best practice, legislation, relevant guidance, documentation and British Standards.

- Submitted detailed proposals for site remediation and verification (Remediation Strategy) which may involve the removal, containment or otherwise rendering harmless such contamination. The proposals shall be prepared in accordance with recognised current best practice, legislation, relevant guidance, documentation and British Standards and shall be submitted to and have received in writing the approval of the local planning authority prior to commencing the works.
- Prior to occupation of any part of the development, a verification report demonstrating completion of the works set out in the approved remediation strategy and the effectiveness of the remediation shall be submitted to and approved, in writing, by the local planning authority. The report shall include results of sampling and monitoring carried out in accordance with the approved verification plan to demonstrate that the site remediation criteria have been met. It shall also include any plan (a "long-term monitoring and maintenance plan") for longer-term monitoring of pollutant linkages, maintenance and arrangements for contingency action, as identified in the verification plan, and for the reporting of this to the local planning authority.
- If, during development, contamination not previously identified is found to be present at the site then no further development shall be carried out until the developer has submitted and obtained written approval from the local planning authority for, an amendment to the remediation strategy detailing how this unsuspected contamination shall be dealt with.
- Prior to the importation of any soil a copy of the certificate of analysis, details of the source of the topsoil and an interpretation of the analytical results by a suitably qualified individual shall be submitted to and approved in writing by the local planning authority.
- The development hereby approved should be implemented in strict accordance with the mitigation measures and recommendations detailed in section 4.1 of the Ecological Appraisal and described on drawing references 'TDA.2185.01' and '393 PI-01 Rev M' received by the local planning authority on 10th December, 2018.
- Prior to the commencement of works on the development hereby approved the provision of a lighting plan consistent with the measures outlined in section 4.3.4 of the Ecological Appraisal to ensure that lighting measures do not conflict with the use of the site by protected species needs to submitted to and approved in writing by the local planning authority. The plan should include details of the siting and type of lighting to be used, measures to control light spill and ensure that boundary vegetation is not illuminated, and that dark corridors are maintained. The plan is to be implemented as agreed.
- Prior to the commencement of works on the development hereby approved a scheme to conserve dormice is to be prepared and agreed in writing by the local planning authority. The scheme should include (but not exclusively) measures to ensure that dormice are conserved during the course of vegetation clearance works; details of the 3-10m buffer zone, including any proposed planting; confirmation that these features will lie outside of the curtilage of properties; details

of appropriate management to ensure the establishment and favourable management of these habitat features for dormice in the long term. The scheme shall then subsequently be implemented as agreed.

- No development shall commence until such time as the local planning authority is provided with written confirmation of which offsite sewerage network upgrade option identified in the Drainage Technical Note received on 8th July, 2019 is to be implemented along with a timetable for its implementation. Thereafter, no dwelling shall be beneficially occupied until such time as written confirmation is received from Dwr Cymru/Welsh Water that the selected sewerage network upgrade option has been completed and this confirmation is submitted for the written approval of the local planning authority.
- The foul sewerage system in the application shall only be connected to the public sewerage system at or upstream of manhole number SN42014303 as indicated on the Drainage Strategy plans reference 10217-100-01 Rev F and 10217-100-02 Rev F.
- 21 The development shall be undertaken in strict accordance with the Drainage Strategy Report September 2018 which was received by the local planning authority on 8th July, 2019.
- The development must be carried out in strict accordance with following:-
 - Sections 4.0 4.6 of the Ecological Appraisal received 10th December, 2018;
 - Mitigation Measures detailed in the Environmental Statement Addendum received 5th December, 2018;
 - Site Management Daily Checklist received 5th December, 2018;
 - Construction Method Statement and Drainage Construction Method Statement -Land off Garreglwyd, Pembrey received 5th December, 2018;
 - Construction Management Plan received 5th December, 2018;
 - Drainage Plan for Construction received 5th December, 2018;
 - Appendix C of the HRA Screening Report Received 27th February, 2018.
- Prior to the commencement of any works associated with the development (including site vegetation clearance, demolition of existing structures, excavation, heavy machinery entering site or the on-site storage of materials) the following shall be undertaken in compliance with the recommendations of BS5837 and submitted to and agreed in writing by the local planning authority:
 - i) Arboricultural Method Statement (AMS) which provides details, as necessary, of construction operations and specific design solutions to be undertaken within the root protection areas of all trees, large shrubs and hedges identified for retention:
 - ii) Tree Protection Plan (TPP) which provides details of all protective measures, operations and construction exclusion zones for all trees, large shrubs and hedges identified for retention;

The scheme should then be implemented as approved.

- No development or site clearance shall take place until a method statement for the translocation of the existing hedge/ hedgerow(s) to the north-western boundary has been submitted to and approved in writing by the local planning authority. The method statement shall include an implementation programme and should then be implemented in strict accordance with the approved statement.
- The hedge/ hedgerow translocation method statement as approved to discharge condition 25 shall be fully implemented as stated in the implementation programme. Any section of existing hedge/hedgerow translocated in accordance with the approved method statement which, within the lifetime of the approved development is removed; dies; becomes diseased; damaged or otherwise defective, to such extent that, in the opinion of the local planning authority, the function of the existing hedge/hedgerow(s) in relation to this planning approval is no longer delivered, shall be replaced in the next planting season with replacement elements of similar size and specification.
- The approved Landscape Design Scheme (LDS), as defined in the Landscape Specification and Management Plan and Detailed soft Landscape Proposals Plan received on 8th July, 2019 shall be fully implemented during the first available planting and seeding seasons following the completion of the last dwelling.

Any of the hereby scheduled specific landscape elements as defined in the approved LDS which, within the lifetime of the approved development are removed; die; become diseased; damaged or otherwise defective, to such extent that, in the opinion of the local planning authority, the function of the landscape elements in relation to this planning approval is no longer delivered, shall be replaced in the next planting season with replacement elements of similar size and specification and in such positions as may be agreed with the local planning authority, and thereafter likewise conditioned for the lifetime of the approved development.

- i) All existing hedge line boundaries identified for retention.
- ii) All exiting trees identified for retention.
- iii) Woodland buffer planting to the south of the northern boundary (keyed as 'proposed native woodland planting' within the hereby approved documents).
- iv) Hedge planting to the southern site boundary.
- v) Tree planting at site entrance (comprising 6 no. Prunus sp.).

All new landscape elements constructed, planted or seeded in accordance with the approved LDS not hereby specifically scheduled, which, within a period of 5 years after implementation are removed; die; become diseased; damaged or otherwise defective, to such extent that, in the opinion of the local planning authority, the function of the landscape elements in relation to this planning approval is no longer delivered, shall be replaced in the next planting or seeding season with replacement elements of similar size and specification.

The approved landscape maintenance and management information, as defined in the Landscape Specification and Management Plan and Management Company Plan shall be fully implemented as approved.

- No development shall commence until a Landscape Ecological Management Plan (LEMP) for the provision, management and maintenance of the landscape and ecological features for a specific phase of the development, has been submitted to and approved by the local planning authority. The LEMP shall include:
 - Details of habitats, landscape, environmental and ecological features present or to be created at the site.
 - Details of the desired conditions of features (present and to be created) at the site.
 - Details of scheduling and timings of activities.
 - Details of short and long-term management proposals, monitoring proposals and maintenance operations of new and existing landscape, environmental and ecological features at the site to deliver and maintain the desired landscape and ecological conditions and functions.
 - Details of monitoring of landscape and ecological features and required post construction monitoring.
 - Details of replacement measures should any landscape or environmental features die, be removed or become seriously damaged or diseased within the lifetime of the development.
 - Details of management and maintenance responsibilities.
 - Details of timescales, length of plan, the method to review and update plans (informed by monitoring) at specific intervals as agreed between interested parties.
 - Mechanisms to be used for reporting.
 - The LEMP must deliver all mitigation and enhancement requirements for the operational phase as referenced in all associated documents.

The LEMP shall be carried out in accordance with the approved details.

- The development should be undertaken in strict accordance with the mitigation measures outlined in the Welsh Language Action Plan received by the local planning authority on 5th December, 2018.
- Prior to the beneficial occupation of any of the dwellings hereby approved, full details of the Local Area of Play shall be submitted to and approved in writing by the local planning authority. The play area shall be provided in strict accordance with the agreed details prior to the first occupation of Plots 88-100, as shown on the submitted plans.

REASONS

- 1 Required to be imposed pursuant to Section 91 of the Town and Country Planning Act 1990.
- 2 In the interest of visual amenity.
- 3-9 In the interest of highway safety.
- 10-11 To preserve residential amenity.
- 12-15 To protect the environment and human health and comply with Local Development Plan Policy.
- 16-18 To ensure that the proposed development is not detrimental to the maintenance of the population of Dormice.
- 19-20 To prevent hydraulic overloading of the public sewerage system, to protect the health and safety of existing residents and ensure no pollution of or detriment to the environment.
- To ensure a satisfactory form of surface and foul water drainage.
- 22 To prevent pollution of controlled waters and the wider environment and in the interest of biodiversity.
- 23-27 To ensure that the development retains, incorporates and does not adversely affect existing landscape or other features which contribute to local qualities and distinctiveness and to ensure that the development enhances the character and appearance of the site and ensures the use of good quality hard and soft landscaping, embracing opportunities to enhance biodiversity and ecological connectivity.
- In the interest of biodiversity and ecology.
- In the interest of preserving and enhancing the Welsh language and culture.
- To provide a satisfactory on site Local Area of Plan and to comply with Local Development Plan Policy.

REASONS FOR GRANTING PLANNING PERMISSION

The decision to grant planning permission has been taken in accordance with Section 38 of the Planning and Compulsory Purchase Act 2004, which requires that, in determining a planning application the determination must be in accordance with the Development Plan (LDP) unless material considerations indicate otherwise.

• It is considered that the proposal complies with Policy SP1 of the LDP in that the proposed development is environmentally sustainable.

- It is considered that the proposal complies with Policy SP2 of the LDP in that the proposed development is resilient to the impact of climate change and accords with the provisions of TAN15.
- It is considered that the proposal complies with Policy SP3 of the LDP in that the proposed development accords with the LDP's settlement framework.
- It is considered that the proposal complies with Policy SP4 of the LDP in that it will
 ensure that a strategic site is developed in an appropriate manner thus contributing to
 the implementation of the LDP strategy.
- It is considered that the proposal complies with Policy SP5 of the LDP in that it involves the development of a housing allocation in an appropriate manner.
- It is considered that the proposal complies with Policy SP6 of the LDP in that the applicant has agreed to provide a financial contribution towards affordable housing.
- It is considered that the proposal complies with Policy SP9 of the LDP in that the proposed development is located in a sustainable location, accessible by a variety of transport means.
- It is considered that the proposal complies with Policy SP13 of the LDP in that the proposed development respects, and will not adversely affect the built and historic environment or its setting.
- It is considered that the proposal complies with Policy SP14 of the LDP in that proposed development protects and does not adversely affect the natural environment.
- It is considered that the proposal complies with Policy SP17 of the LDP in that the proposed development will be served by appropriate infrastructure.
- It is considered that the proposal complies with Policy SP18 of the LDP in that the interests of the Welsh language will be safeguarded and promoted.
- It is considered that the proposal complies with Policy GP1 of the LDP in that the proposed development is sustainable and will enhance the character and appearance of the area.
- It is considered that the proposal complies with Policy GP2 of the LDP in that the majority of the site is located within the defined settlement limits of the growth area of Llanelli.
- It is considered that the proposal complies with Policy GP3 of the LDP in that the application will be subject to a Planning Obligation to meet the requirements arising from the development.
- It is considered that the proposal complies with Policy GP4 of the LDP in that adequate infrastructure is proposed to serve the proposed development.
- It is considered that the proposal complies with Policy H1 of the LDP in that it involves the development of a housing allocation in an appropriate manner.

- It is considered that the proposal complies with Policy AH1 of the LDP in that the applicant has agreed to provide 20% affordable housing.
- It is considered that the proposal complies with Policy TR1 of the LDP in that the proposal does not restrict traffic movement or compromise safety of the primary road network.
- It is considered that the proposal complies with Policy TR2 of the LDP in that the proposed development is located in a highly accessible and sustainable location.
- It is considered that the proposal complies with Policy TR3 of the LDP in that the proposed development would not be detrimental to highway safety or cause significant harm to the amenity of residents.
- It is considered that the proposal complies with Policy EQ1 of the LDP in that the proposed development preserves the built and historic environment
- It is considered that the proposal complies with Policy EQ4 of the LDP in that the proposed development will not have an adverse impact on priority species, habitats and features of principal importance.
- It is considered that the proposal complies with Policy EQ5 of the LDP in that the proposal does not adversely affect ecological corridors, networks and features of distinctiveness.
- It is considered that the proposal complies with Policy EQ6 of the LDP in that the proposal does not adversely the Special Landscape Area to the north of the site.
- It is considered that the proposal complies with Policy EP1 of the LDP in that the proposed development will not lead to a deterioration of either the water environment and/or the quality of controlled waters.
- It is considered that the proposal complies with Policy EP2 of the LDP in that the proposed development will not result in any adverse pollution issues.
- It is considered that the proposal complies with Policy EP3 of the LDP in that the impact of surface water drainage and the effectiveness of incorporating SUDS has been fully investigated.
- It is considered that the proposal complies with Policy REC2 of the LDP in that sufficient on site open space is provided.

NOTES

The applicant/developer is advised that this consent is subject to the applicant entering into a legal agreement with the local planning authority under Section 106 of the Town and Country Planning Act 1990. This agreement shall cover the requirement for the applicant/developer to provide on-site affordable housing and pay financial contributions towards education facilities and offsite drainage culvert improvements.

- 2 Comments and guidance received from consultees relating to this application, including any other permissions or consents required, are available on the Authority's website.
- Please note that this consent is specific to the plans and particulars approved as part of the application. Any departure from the approved plans will constitute unauthorised development and may be liable to enforcement action. You (or any subsequent developer) should advise the Council of any actual or proposed variations from the approved plans immediately so that you can be advised how to best resolve the matter.

In addition, any Conditions which the Council has imposed on this consent will be listed above and should be read carefully. It is your (or any subsequent developers') responsibility to ensure that the terms of all Conditions are met in full at the appropriate time (as outlined in the specific condition).

The commencement of development without firstly meeting in full the terms of any Conditions which require the submission of details prior to the commencement of development will constitute unauthorised development. This will necessitate the submission of a further application to retain the unauthorised development and may render you liable to formal enforcement action.

Failure on the part of the developer to observe the requirements of any other Conditions could result in the Council pursuing formal enforcement action in the form of a Breach of Condition Notice.

Application No	S/38939
Application Type	Full Planning
Proposal & Location	SINGLE STOREY REAR EXTENSION AND NEW DRIVEWAY TO FRONT AT 46 HEOL NANT, SWISS VALLEY, LLANELLI, SA14
	8EN
Applicant(s)	MR JULIAN BELTON, 46 HEOL NANT, SWISS VALLEY, LLANELLI, SA14 8EN
Case Officer	Zoe James
Ward	Swiss Valley
Date of validation	07/06/2019

Reason for Committee

This application is being reported to the Planning Committee following the receipt of more than one objection from third parties.

Site

The application site consists of the curtilage of a detached bungalow located in Heol Nant in Swiss Valley. The bungalow is situated towards the front of the plot with a raised parking area to the front, sloped driveway to the side of the dwelling in front of a detached outbuilding and grassed garden to the rear. The dwelling fronts onto Heol Nant with three windows on the front elevation and the main access door. The house has a brick finish and the surrounding estate consists of a mix of semi-detached and detached bungalows, albeit these are of differing design.

Proposal

The application seeks full planning permission for a single storey rear extension to the existing dwelling. The proposed extension is up to 7m in total length from the existing dwelling to the rear and is the width of the existing property. The proposed development is to allow internal reconfiguration to create a new larger open plan kitchen and living area to the rear, a utility room and change the layout of the existing bedrooms and create a new dressing room and en-suite to the main bedroom now proposed to be situated to the rear.

The extension will comprise a pitched roof with the external finish of the extension to consist of a smooth rendered finish and cladding to provide interest and a contrast that of the existing brick property. The roof will be clad with matching roof tiles. New double

French doors and a window are proposed on the rear elevation. To the south side elevation, the position of the existing door is proposed to be re-positioned and two new windows and velux roof windows are proposed. To the north side elevation, two new windows are proposed within the existing bungalow, each of this are for bathroom/en-suite so will be obscure glazing and one new velux rooflight within the extension.

To the front of the property a new driveway has partially been constructed to increase the parking provision at the property.

It is worthwhile noting that the application has been amended numerous times by the applicant in order to try and achieve an amenable scheme. The submission initially proposed a smaller extension to the rear but included creation of a first floor through provision of a rear dormer extension. The plans were amended following discussion and concerns raised from neighbouring occupiers. The size of the rear extension was then reduced following discussion with the Planning Officer in line with requirements of Local Development Plan Policy GP6.

Planning Site History

There are no records of any previous applications at the site.

Planning Policy

In the context of the Authority's current Local Development Plan (LDP) the site is located within the Development Limits of Llanelli. Reference is drawn to the following policies of the Plan:-

Carmarthenshire Local Development Plan (Adopted December 2014) ('the LDP')

GP1 Sustainability and High Quality Design GP6 Extensions

Carmarthenshire Supplementary Planning Guidance

National Planning Policy and Guidance is provided in <u>Planning Policy Wales</u> (PPW) Edition 10, December 2018 and associated <u>Technical Advice Notes</u> (TANs) published by Welsh Government.

Summary of Consultation Responses

Head of Transportation & Highways - No observations received to date.

Lianelli Rural Council – Objects to the extension as it is not subordinate to the existing dwelling in terms of scale and will considerably extend the footprint of the bungalow and have an adverse impact on its original character.

Local Member - Councillor Giles Morgan submitted revised comments following submission of the first amended plans stating his objection remains to the scale of size of the rear extension and it will be visible from the road and look out of character with the surroundings. [Comments received prior to latest amended plan].

Planning Ecology – No objection, issued bat advisory.

Dwr Cymru/Welsh Water – No objection subject to condition.

Sustainable Drainage Approval Body – Proposal is acceptable, no further comments.

All representations can be viewed in full on our <u>website</u>.

Summary of Public Representations

The application was the subject of notification by way of neighbouring letters and a site notice posted outside the application site.

Four representations were received, all of which object and the matters raised are summarised as follows:-

- Proposed roof height will block out light.
- Proposed length of extension will result in living conditions of being in a tunnel and will expedite existing claustrophobia.
- No sunlight in garden after 2pm negatively impacting on plants and wildlife.
- Proposed roof height exceeds height of neighbouring bungalows making the building larger and more predominant. Will alter the character and nature of the estate.
- Potential for overlooking from Juliet balcony negatively impacting on privacy.
- Proposed extension fails to comply with Policy GP6.

Please note the comments were received prior to the amended plans being submitted, yet no revised comments have been received following submission of the latest plans.

All representations can be viewed in full on our <u>website</u>.

Appraisal

The proposed extension extends to the rear of the existing dwelling house 7m in total on the north elevation, 6m on the north elevation and is the entire width of the property. Whilst the extension proposed is a sizeable increase to the existing dwelling it extends to the rear and is not visible from the front elevation. As such, the proposed extension does not alter the character or appearance of the host dwelling or streetscene as required by Policy GP6. Similarly, the plot benefits from a generous garden so the proposed extension does not result in overdevelopment of the site.

The proposed extension comprises a pitched roof to match the existing with the addition of three velux roof windows. The extension is proposed to be a mix of render and cladding, with roof tiles to match the existing. The proposed materials whilst not matching the existing property are not considered unsuitable at the site. Based on the above it is considered that the proposal complies with the relevant policy criteria within GP1 and GP6.

In terms of its impact on neighbouring properties, concerns have been raised regarding loss of light and privacy. Following submission of the amended plans, the proposed extension no longer proposes to increase the roof height. The extension is no closer to the site boundary with neighbouring occupiers than the existing dwelling. On the south elevation and boundary with no. 44 Heol Nant, the existing shed/outbuilding presently on site will be removed to accommodate the proposed extension and therefore no loss of light is considered to be caused by the extension. In terms of potential for overlooking and loss of privacy, the positioning of the windows coupled with the condition to increase the height of the boundary fence ensures that the proposal will not adversely affect amenities of the neighbouring property. To the north on the boundary with no. 48 Heol Nant, the site is set at a slightly lower level and two windows are proposed within the existing dwelling, both are which are to be obscure glazing. On this basis, there is not considered to be any detriment to the amenity of the adjacent occupier through loss of light or privacy. As a result, the proposal it is not considered to adversely affect the amenity of neighbouring developments.

The new driveway area to the front of the property has been partially constructed and provides additional space for vehicular parking at the property. No concerns have been raised in respect of this area.

The proposal does not impact upon the highway network and there are no ecological/environmental considerations, a bat advisory has been issued to the applicant.

The proposal is therefore considered to be in accordance with the objectives of policies GP1 and GP6 in terms of its likely impact upon the residential amenity of neighbouring occupiers.

Planning Obligations

None

Well-being of Future Generations (Wales) Act 2015

The decision considers the duty to improve the economic, social, environmental and cultural well-being of Wales, in accordance with the sustainable development principle, under section 3 of the Well-Being of Future Generations (Wales) Act 2015 (the WBFG Act). The decision takes into account the ways of working set out at section 5 of the WBFG Act and it is considered that this decision is in accordance with the sustainable development principle through its contribution towards one or more of the Welsh Ministers' well-being objectives set out in section 8 of the WBFG Act.

Conclusion

After careful consideration of the scheme as submitted, the site and its surrounding environs, together with the representations received to date it is concluded on balance that the scale and design of the proposed extension is considered to be acceptable and have no detrimental impact on the character and appearance of the existing property and surrounding residential area. The extension is compatible to the size, design and character of the host dwelling and the amenities of adjacent occupiers will not be adversely affected by the development.

The proposal is in accordance with the policies of the adopted Local Development Plan and is therefore put forward with a favourable recommendation subject to the below conditions.

Recommendation – Approval

Conditions

- 1 The development hereby permitted shall be commenced before the expiration of five years from the date of this permission.
- 2 The development hereby permitted shall be carried out strictly in accordance with the details shown on the following plans:-
 - Site Location Plan scale 1:1250 received 21 May 2019;
 - Proposed Site Plan, Existing and Proposed Ground Floor Plans and Elevations scale 1:200 and 1:50 drawing no. JJ-100-02 Rev B received 29 July 2019.
- Before the development hereby permitted is first brought into use the bathroom and en-suite windows (as shown on Plans drawing no. JJ-100-02B) shall be fitted with obscure glazing and shall be permanently retained in that condition thereafter.
- 4 Before the development hereby permitted is first brought into use the side boundary fence of the subject property and no. 44 Heol Nant shall be increased in height to 1.8 metres.

Reasons

- 1 Required to be imposed pursuant to Section 91 of the Town and Country Planning Act 1990.
- 2 In the interests of visual amenity and to confirm the extent of the permission.
- 3+4 In the interests of privacy.

Notes/Informatives

Please note that this consent is specific to the plans and particulars approved as part of the application. Any departure from the approved plans will constitute unauthorised development and may be liable to enforcement action. You (or any subsequent developer) should advise the Council of any actual or proposed variations from the approved plans immediately so that you can be advised how to best resolve the matter.

In addition, any Conditions which the Council has imposed on this consent will be listed above and should be read carefully. It is your (or any subsequent developers') responsibility to ensure that the terms of all Conditions are met in full at the appropriate time (as outlined in the specific condition).

The commencement of development without firstly meeting in full the terms of any Conditions which require the submission of details prior to the commencement of

development will constitute unauthorised development. This will necessitate the submission of a further application to retain the unauthorised development and may render you liable to formal enforcement action.

Failure on the part of the developer to observe the requirements of any other Conditions could result in the Council pursuing formal enforcement action in the form of a Breach of Condition Notice.

- 2 Comments and responses received from consultees and third parties can be found on the Authority's website (www.carmarthenshire.gov.uk). They may also relate to other permissions or consents required or include further advice and guidance.
 - Please see the relevant responses from Dwr Cymru/Welsh Water and the Council's Planning Ecologist and refer to the recommendations and advice contained therein.

Application No	S/38967
Application Type	Full Planning
Proposal & Location	PROPOSED CONVERSION OF EXISTING GARAGE, LINK EXTENSION AND FRONT PORCH AT 29 SARON ROAD, BYNEA, LLANELLI, SA14 9LT
Applicant(s)	S MORSE, 29 SARON ROAD, BYNEA, LLANELLI, SA14 9LT
Agent	DIMENSION DRAWING SERVICES - IAN JONES, 15 STEBONHEATH TERRACE, LLANELLI, SA15 1NE
Case Officer	Zoe James
Ward	Bynea
Date of validation	13/06/2019

Reason for Committee

This application is being reported to the Planning Committee following the receipt of more than one objection from third parties.

Site

The application site consists of the curtilage of a detached two storey house located on Saron Road in Bynea. The property is set in a substantial plot with the dwelling being situated to the north east of the site. The property benefits from a dedicated driveway and garden area to the rear with a separate garage accessed via the narrow private roadway which leads from Saron Road. The house has a roughcast render finish and grey rooftile.

Adjacent to the site to the east is existing residential development no.27 Saron Road, with further residential properties no. 27A and 25 Saron Road situated to the south and north of the site respectively.

Proposal

The application seeks full planning permission for the conversion of the existing garage, provision of a new link between the existing dwelling and garage and construction of a new porch off the existing sun room to the front of the property. The proposal includes additional floorspace through the extension between the existing garage and dwelling of approximately 7.5m and a new porch to the west of the front elevation of approximately 2.7m.

The proposed conversion of the existing garage seeks to allow internal reconfiguration to allow for creation of a ground floor bedroom, en-suite bedroom and adjoined lounge area. New obscure glazing is proposed to the rear elevation in place of the existing garage doors. The new link extension will provide a utility room and storage area, a new window is proposed on this elevation looking onto the private garden. The proposed porch provides a separate access to the property via the porch rather than directly through the sun lounge.

The conversion will be on the same footprint of the existing garage with the roof height increasing approximately 0.4m. The proposed conversion seeks to utilise a roughcast render external finish and grey roof tile to match the existing property with white uPVC windows and doors.

Planning Site History

The following previous applications have been received on the application site:-

S/29710 Single storey front extension
Full planning permission 10 April 2014

S/21020 Retrospective application for the creation of new access and driveway
Withdrawn 02 July 2009

S/18386 Residential development
Outline Refused 04 April 2008

Planning Policy

In the context of the Authority's current Local Development Plan (LDP) the site is located within the Development Limits of Llanelli. Reference is drawn to the following policies of the Plan:-

<u>Carmarthenshire Local Development Plan</u> (Adopted December 2014) ('the LDP')

GP1 Sustainability and High Quality Design GP6 Extensions TR3 Highways in Developments – Design Considerations EQ4 Biodiversity

Carmarthenshire Supplementary Planning Guidance

National Planning Policy and Guidance is provided in <u>Planning Policy Wales</u> (PPW) Edition 10, December 2018 and associated <u>Technical Advice Notes</u> (TANs) published by Welsh Government.

Summary of Consultation Responses

Head of Transportation & Highways - No observations received to date.

Head of Public Protection - No adverse comments to make.

Environmental Health (Contaminated Land) - No adverse comments to make.

Llanelli Rural Council – Objection unless there are no highway safety concerns associated with conversion of the garage and off road parking and the conversion and extension to the property is not considered to be an incongruous form of development at the property.

Local Member - Councillor Cundy has confirmed no objection.

Sustainable Drainage Approval Body – No comments on the application.

Dwr Cymru/Welsh Water - No observations received to date.

All representations can be viewed in full on our website.

Summary of Public Representations

The application was the subject of notification by way of neighbouring letters and a site notice posted outside the site.

Two representations were received, both of which object, and the matters raised are summarised as follows:

- Access to the neighbouring properties must be available 24/7 due to health conditions of adjacent occupiers.
- Concerned that the construction work in associated with the proposed development will damage the access road which was recently resurfaced. Road is a private road and is maintained by residents.
- All deliveries should take place on site and keep the access road clear.
- Object to the provision of a box gutter between the site and no. 27 Saron Road.
- Building of a new wall so close to and on the boundary of the adjacent property could cause damage to this property, especially in relation to new foundations.

All representations can be viewed in full on our website.

Appraisal

The proposed development comprises the conversion of the existing garage into living accommodation to provide additional living accommodation through the provision of ground floor bedroom adjoining lounge area and en-suite. Whilst it is noted that the conversion will require construction work there is no increase in floorspace as part of this element of the proposal. The roof height will be increased by approximately 0.4m in height from the existing garage. The additional floorspace proposed at the property amounts to around 10sq m through the creation of the utility room in the proposed link extension and new porch to the front of the property. Neither of which will have any impact on

neighbouring properties nor are considered to be out of character with the existing property.

The materials proposed for the conversion, extension and porch complement the existing dwelling and the conversion is considered to result in an improved appearance to the existing garage and outbuilding presently at the property. Based on the above it is considered that the proposal complies with the relevant policy criteria within GP1 and GP6.

Objections from third parties raise concerns regarding the access road remaining available and unobstructed throughout the construction period and that the private road will be damaged by delivery vehicles during the construction period. The applicant has submitted a letter advising that they are aware of the need for the road to remain unobstructed and that all deliveries will be via the driveway of no. 29 Saron Road. They have also confirmed that any damage caused to the access road as a result of the development will be met by themselves.

In terms of the concerns regarding the party wall, the applicant has confirmed that this has been discussed directly with the neighbour and a Party Wall Agreement has been served. The applicant has also confirmed box guttering is not proposed to be used and the guttering will be replaced to match existing at the property.

The concerns raised regarding loss of parking at the property through conversion of the garage are mitigated through the large driveway and parking area available to the south of the property. In addition, the applicant has advised that the existing garage has not been used for parking provision due to its location and poor accessibility and also uneven floor level. Highways have not commented on the scheme to date but given the level of existing parking available to the south of the property, the proposal is not considered to be detrimental to highway safety or cause significant harm to the amenity of residents as required by Policy TR3.

A Bat Survey has been requested by the Planning Ecologist given the conversion of the existing garage. The agent has confirmed that this is in the process of being undertaken and will be submitted to the authority for consideration prior to the determination of the application.

Planning Obligations

None

Well-being of Future Generations (Wales) Act 2015

The decision considers the duty to improve the economic, social, environmental and cultural well-being of Wales, in accordance with the sustainable development principle, under section 3 of the Well-Being of Future Generations (Wales) Act 2015 (the WBFG Act). The decision takes into account the ways of working set out at section 5 of the WBFG Act and it is considered that this decision is in accordance with the sustainable development principle through its contribution towards one or more of the Welsh Ministers' well-being objectives set out in section 8 of the WBFG Act.

Conclusion

After careful consideration of the scheme as submitted, the site and its surrounding environs, together with the representations received to date it is concluded on balance that the scale and design of the proposed development is considered to be acceptable and have no detrimental impact on the character and appearance of the existing property and surrounding residential area. The concerns raised by neighbouring occupiers can be adequately mitigated through planning conditions and it is not considered that there is any detriment to highway safety as a result of the proposal. A Bat Survey is required in advance of determination of the application.

The proposal is in accordance with the policies of the adopted Local Development Plan and is therefore put forward with a favourable recommendation subject to the below conditions and approval of the bat survey from the Planning Ecologist.

Recommendation – Approval

Conditions

- 1 The development hereby permitted shall be commenced before the expiration of five years from the date of this permission.
- The development hereby permitted shall be carried out strictly in accordance with the details shown on the following plans:-
 - Location Plan and Site Block Plan scale 1:1250 and 1:500 drawing no. LP-01 received 3 April 2019;
 - Existing Floor Plans and Elevations drawing no. SDM-01 received 3 April 2019;
 - Proposed Floor Plans and Elevations drawing no. SDM-02 received 3 April 2019.
- All deliveries during the construction period shall be made via the existing driveway to the south of the property at no. 29 Saron Road unless otherwise agreed in writing with the local planning authority.
- Before the development hereby permitted is first brought into use the en-suite bathroom windows (as shown on Proposed Plans and Elevations drawing no. SDM-02) shall be fitted with obscure glazing and shall be permanently retained in that condition thereafter.
- The materials to be used in the construction of the external surfaces of the conversion, extension and porch shall be as specified on Proposed Plans and Elevations drawing no. SDM-02 match those used in the existing building.

Reasons

- 1 Required to be imposed pursuant to Section 91 of the Town and Country Planning Act 1990.
- 2 In the interests of visual amenity and to confirm the extent of the permission.
- 3 To ensure access to existing adjacent properties is unhindered by the proposal.

- 4 In the interest of privacy.
- 5 In the interest of visual amenity.

Notes

Please note that this consent is specific to the plans and particulars approved as part of the application. Any departure from the approved plans will constitute unauthorised development and may be liable to enforcement action. You (or any subsequent developer) should advise the Council of any actual or proposed variations from the approved plans immediately so that you can be advised how to best resolve the matter.

In addition, any Conditions which the Council has imposed on this consent will be listed above and should be read carefully. It is your (or any subsequent developers') responsibility to ensure that the terms of all Conditions are met in full at the appropriate time (as outlined in the specific condition).

The commencement of development without firstly meeting in full the terms of any Conditions which require the submission of details prior to the commencement of development will constitute unauthorised development. This will necessitate the submission of a further application to retain the unauthorised development and may render you liable to formal enforcement action.

Failure on the part of the developer to observe the requirements of any other Conditions could result in the Council pursuing formal enforcement action in the form of a Breach of Condition Notice.

2 Comments and responses received from consultees and third parties can be found on the Authority's website (www.carmarthenshire.gov.uk). They may also relate to other permissions or consents required or include further advice and guidance.

Application No	S/39013
Application Type	Full Planning
Proposal & Location	NEW TEACHING AND PRACTICE BAYS AT ASHBURNHAM GOLF CLUB, CLIFF TERRACE, BURRY PORT, SA16 0HN
Applicant(s)	ASHBURNHAM GOLF CLUB, CLIFF TERRACE, BURRY PORT, SA16 0HN
Agent	DESIGN INTENT - MARK DAVIES, RHYDHYWEL FACH, CRWBIN, KIDWELLY, SA17 5DE
Case Officer	Robert Davies
Ward	Pembrey

Reason for Committee

19/06/2019

Date of validation

This application is being reported to the Planning Committee following the receipt of more than one objection from third parties.

Site

The application site is located in a well-established practice area associated with Ashburnham Golf Club in Burry Port. It is understood that this area of land, which is under the ownership of the Golf course has been used for practice purposes for approximately 70 years, with golfers regularly hitting balls in both directions without any reported problems.

Proposal

As part of a drive by the Golf club to try and get more juniors and ladies to play golf they have been successful in obtaining a Sports Wales grant to create a small academy course on the current practice area and is association with this seek full planning permission to construct a three bay undercover teaching and practice bay.

The proposed green steel clad structure is 10.5m wide, 4.5m deep and has a maximum height of 3.5m. The proposal is sited to southern boundary of the practice area and golfers having lessons will hit the balls northwards.

Planning permission was granted in 2018 for a small golf practice facility building to house a simulator. This has recently been constructed next to the clubhouse itself.

Planning Site History

S/37934	Construction of new building forming go	If practice facility
	Full planning permission	15 November 2

S/36973 Construction of new building forming golf practice facility

Full planning permission 30 April 2018

D5/17269 Extension to existing ladies toilets and shower room

Full planning permission 23 November 1995

2018

D5/15659 Extension to existing dining room, extension to golf shop,

provision of new changing rooms for men, relocate club secretary's office in existing golf shop and convert existing changing rooms at first floor into games room or lounge

Full planning permission 31 March 1994

D5/15433 Extension to provide professional shop, secretary's office,

junior room & trolley store

Withdrawn 17 March 1993

D5/9890 First floor function room

Approved 22 June 1987

D5/3075 Entrance porch and lobby

Approved 18 May 1978

Planning Policy

Carmarthenshire Local Development Plan (Adopted December 2014) ('the LDP')

SP1 Sustainable Places and Spaces

SP14 Protection and Enhancement of the Natural Environment

GP1 Sustainability and High Quality Design

TR3 Highways in Developments – Design Considerations

EQ4 Biodiversity

Carmarthenshire Supplementary Planning Guidance

National Planning Policy and Guidance is provided in <u>Planning Policy Wales</u> (PPW) Edition 10, December 2018 and associated <u>Technical Advice Notes</u> (TANs) published by Welsh Government.

Summary of Consultation Responses

Pembrey and Burry Port Town Council – Recommend approval.

Local Members – Councillor H Shepardson supports the application however has advised that he is a member of the golf club.

Councillor S Matthews has not responded to date.

Network Rail – No objections.

All representations can be viewed in full on our website.

Summary of Public Representations

The application was advertised by the posting of two site notices. To date, two neighbouring properties have raised the following concerns and objections:-

- Is the area to be fenced off and flood lit?
- People use this area to walk dogs;
- Health and safety risks balls could hit people and/or property;
- The proposed open side structure will be used by youngsters to drink and cause antisocial behaviour – the building should be secured when not in use;
- Access and parking problems on private road;
- Noise:
- Devaluation of property.

All representations can be viewed in full on our website.

Appraisal

Is the area to be fenced off and flood lit?

The golf club has confirmed that the area is not to be fenced off or flood lit.

People use this area to walk dogs

The well-established practice area is privately owned by the Golf club, and whilst members of the public can physically gain access to this area there is no public right of way or right of access.

Health and safety risks – balls could hit people and/or property

As aforementioned the well-established practice area is privately owned by the Golf club, and whilst members of the public can physically gain access to this area there is no public right of way or right of access. The Golf club has explained that most golfers are right handed and most beginners tend to slice the ball to the right. Therefore a decision has been made to site the proposed teaching bay to the southern boundary. The three bay facility will have internal dividers to prevent balls being hit towards the houses at The Links.

The proposed open side structure will be used by youngsters to drink and cause anti-social behaviour – the building should be secured when not in use

This is merely speculation. Whilst the proposed structure is open sided it will be the responsibility of the Golf course to manage and prevent such behaviour occurring. The structure has been placed quite close to the maintenance facility.

Access and parking problems on private road

The Golf club has its own parking facilities and members that will use this facility will walk down from the car park and club house itself. The Golf club will inform members and parents etc. of juniors having lessons not to park at The Links itself. The LPA is unaware of any current problems in this respect associated with the practice area.

Noise

The area concerned is already used for practice purposes and there it is not envisaged that the proposal will result in a discernible increase in noise and disturbance.

Devaluation of property

This is not a material planning consideration.

Well-being of Future Generations (Wales) Act 2015

The decision considers the duty to improve the economic, social, environmental and cultural well-being of Wales, in accordance with the sustainable development principle, under section 3 of the Well-Being of Future Generations (Wales) Act 2015 (the WBFG Act). The decision takes into account the ways of working set out at section 5 of the WBFG Act and it is considered that this decision is in accordance with the sustainable development principle through its contribution towards one or more of the Welsh Ministers' well-being objectives set out in section 8 of the WBFG Act.

Conclusion

The proposed development is considered to be acceptable in size, scale and design terms in keeping with its immediate environs.

It is considered that there are no loss of amenity issues associated with the proposed development whilst the issues of concern and objection raised have adequately been addressed as part of the above appraisal.

On balance after careful examination of the site and its surrounding environs in the context of this application, together with the representations received to date it is considered that the proposal does accord with the Policies contained within the Adopted LDP. As such the application is put forward with a recommendation for approval subject to the following conditions.

Recommendation – Approval

Conditions

- 1 The development hereby approved shall be commenced before the expiration of five years from the date of this permission.
- The development hereby permitted shall be carried out strictly in accordance with the following schedule of plans:-
 - Location plan (A100) 1:1250 @ A3 received 17th June, 2019
 - Block plan (102) 1:500 @ A3 received 17th June, 2019
 - Elevations and level 0 plans (A101) 1:100 @ A3 received 15th July, 2019.

Reasons

- 1 Required to be imposed pursuant to Section 91 of the Town and Country Planning Act 1990.
- 2 In the interest of visual amenity.

Reasons for Granting Planning Permission

The decision to grant planning permission has been taken in accordance with Section 38 of the Planning and Compulsory Purchase Act 2004, which requires that, in determining a planning application the determination must be in accordance with the Development Plan unless material considerations indicate otherwise.

- It is considered that the proposal complies with Policy SP1 of the LDP in that the proposed development is environmentally sustainable
- It is considered that the proposal complies with Policy SP14 of the LDP in that proposed development protects and does not adversely affect the natural environment
- It is considered that the proposal complies with Policy GP1 of the LDP in that it is appropriate in terms of scale and design, and will not cause unacceptable loss of amenity to neighbouring uses.
- It is considered that the proposal complies with Policy TR3 of the LDP in that the proposed development would not be detrimental to highway safety or cause significant harm to the amenity of residents
- It is considered that the proposal complies with Policy EQ4 of the LDP in that the proposed development will not have an adverse impact on priority species, habitats and features of principal importance

Notes/Informatives

Please note that this consent is specific to the plans and particulars approved as part of the application. Any departure from the approved plans will constitute unauthorised development and may be liable to enforcement action. You (or any subsequent developer) should advise the Council of any actual or proposed variations from the approved plans immediately so that you can be advised how to best resolve the matter.

In addition, any Conditions which the Council has imposed on this consent will be listed above and should be read carefully. It is your (or any subsequent developers') responsibility to ensure that the terms of all Conditions are met in full at the appropriate time (as outlined in the specific condition).

The commencement of development without firstly meeting in full the terms of any Conditions which require the submission of details prior to the commencement of development will constitute unauthorised development. This will necessitate the submission of a further application to retain the unauthorised development and may render you liable to formal enforcement action.

Failure on the part of the developer to observe the requirements of any other Conditions could result in the Council pursuing formal enforcement action in the form of a Breach of Condition Notice.

2 Comments and guidance received from consultees relating to this application, including any other permissions or consents required, is available on the Authority's website (www.carmarthenshire.gov.uk).

Eitem Rhif 5

Ardal Gorllewin/ Area West

ADRODDIAD PENNAETH CYNLLUNIO, CYFARWYDDIAETH YR AMGYLCHEDD

REPORT OF THE
HEAD OF PLANNING,
DIRECTORATE OF ENVIRONMENT


AR GYFER PWYLLGOR CYNLLUNIO CYNGOR SIR CAERFYRDDIN

TO CARMARTHENSHIRE COUNTY COUNCIL'S PLANNING COMMITTEE

AR 22 AWST 2019

ON 22 AUGUST 2019

I'W BENDERFYNU FOR DECISION



Mewn perthynas â cheisiadau y mae gan y Cyngor ddiddordeb ynddynt un ai fel ymgeisydd/asiant neu fel perchennog tir neu eiddo, atgoffir yr Aelodau fod yna rhaid iddynt anwybyddu'r agwedd hon, gan ystyried ceisiadau o'r fath a phenderfynu yn eu cylch ar sail rhinweddau'r ceisiadau cynllunio yn unig. Ni ddylid ystyried swyddogaeth y Cyngor fel perchennog tir, na materion cysylltiedig, wrth benderfynu ynghylch ceisiadau cynllunio o'r fath.

In relation to those applications which are identified as one in which the Council has an interest either as applicant/agent or in terms of land or property ownership, Members are reminded that they must set aside this aspect, and confine their consideration and determination of such applications exclusively to the merits of the planning issues arising. The Council's land owning function, or other interests in the matter, must not be taken into account when determining such planning applications.

COMMITTEE:	PLANNING COMMITTEE
DATE:	22 AUGUST 2019
REPORT OF:	HEAD OF PLANNING

INDEX - AREA WEST

REF.	APPLICATIONS RECOMMENDED FOR APPROVAL	PAGE NO.
W/38894	Propose to change existing shop to residential use at 15 Bridge Street, Carmarthen, SA31 3JS	93 - 98

APPLICATIONS	RECOMMENDED	FOR	APPROVAL	
APPLICATIONS	RECOMMENDED	FOR	APPROVAL	

Application No	W/38894
Application Type	Full Planning
Proposal & Location	PROPOSE TO CHANGE EXISTING SHOP TO RESIDENTIAL USE AT 15 BRIDGE STREET, CARMARTHEN, SA31 3JS
Applicant(s)	MATTHEW DAVIES, SCHOOL HOUSE, MYNYDDYGARREG, KIDWELLY, UNITED KINGDOM, SA17 4RL
Case Officer	Paul Roberts
Ward	Carmarthen South
Date of validation	24/05/2019

Reason for Committee

This application is being reported to the Planning Committee following the receipt of more than one objection from third parties.

Site

The application site consist of a vacant ground floor shop located on the southern end of Bridge Street on the outskirts of Carmarthen town centre. It is an end of terrace property and its side elevation is orientated towards Coracle Way to the south.

The shop is of modest proportions consisting of a relatively small retail area and associated storage and ancillary facilities to the rear. Its front elevation is characterised by a large window opening while access to the shop is via an adjacent front doorway which also serves a first floor residential flat located above the shop. The property has a small rear courtyard and does not have the benefit of any off road parking facilities.

Bridge Street is characterised by a narrow roadway that is flanked by terraced properties which consist of a mix of commercial and residential premises. The commercial properties consist of a mix of office and retail uses. The application property falls within the Carmarthen Town conservation area and Carmarthen Castle is located immediately to the rear.

Proposal

The application seeks full planning permission for the change of use of the vacant shop to residential use in the form of a ground floor flat. The flat is to provide one bedroom accommodation with a lounge and kitchen area to the front of the property and a bedroom

and bathroom to the rear. Access will be via the existing front doorway which will serve both the ground and first floor flats. There will be no external alterations to the building as a result of the proposal.

The applicant has submitted a unilateral undertaking which secures a financial contribution towards affordable housing as part of the proposal.

Planning Site History

D4/11548 Change of use to licensed restaurant with take away food Full planning permission 5 July 1984

Planning Policy

<u>Carmarthenshire Local Development Plan</u> (Adopted December 2014) ('the LDP')

- SP1 Sustainable Places and Spaces
- SP5 Housing
- SP8 Retail
- GP1 Sustainability and High Quality Design
- H2 Housing within Development Limits.
- AH2 Affordable Housing
- RT4 Principal Centres (Growth Areas): Town Centre Zone
- TR3 Highways in Developments Design Considerations.
- EQ1 Protection of Buildings, Landscapes and Features of Historic Importance.
- SP13 Protection and Enhancement of the Built and Historic Environment.

Summary of Consultation Responses

Carmarthen Town Council - No objection.

Local Member - County Councillor A Lenny is a member of the Planning Committee and has made no prior comment on the application. County Councillor G John has also not commented on the application to date.

All representations can be viewed in full on our website.

Summary of Public Representations

The application was the subject of notification by way of the posting of a site notice within the vicinity of the site.

Two representations have been received from the owners of nearby businesses on Bridge Street who object to the application. The matters raised are summarised as follows:

- The property should be retained for future business use.
- Increased domestic waste which can cause problems with vermin.
- Lack of parking.
- Noise problems associated adjoining businesses.
- Lack of privacy from the large window opening.
- The property is located within a commercial area of the town.

Tudalen 94

- The property is designed for business with a large ground floor window.
- Anti-social problems associated with residential use.
- Changing to residential will not help existing businesses in the street.

All representations can be viewed in full on our website.

Appraisal

The main issue in the determination of the application is the principle of the proposed use of the application property as a residential unit and its impact upon the retail character and function of Carmarthen town centre.

The application site is located in the southern periphery of Carmarthen town centre as designated in the Local Development Plan. However, it does not fall within the primary or secondary retail frontages of the town centre, as designated in the Plan, which have the highest concentrations of retail and commercial uses and wherein there is a general presumption against non-retail proposals that would undermine the retail character and function of the town centre.

Policy RT4 of the Plan permits proposals for non-retail uses within those areas of the town centre falling outside the primary and secondary retail frontages subject to them achieving a diversity of uses appropriate to a town centre location and not having an adverse impact upon its function, visual character and quality.

Bridge street can be seen to consist of a mix of commercial and residential properties with the former consisting of a number of offices, a training centre and small number of retail units. The latter are primarily located in the northern part of the street close to the retail area of Nott Square although there is a hair salon adjacent to the application property. There is a large residential property directly opposite the application property which consists of a number of residential flats and there are further residential properties along the street particularly at first floor level. The mix of uses along the street is characteristic of its location on the periphery of the town centre and it is not considered that the loss of the small shop and its replacement with a residential flat will unacceptably harm the retail and commercial function of the town centre or its visual quality.

The application property has been vacant for over a year and has only been occupied on an intermittent basis since 2010. The applicant has had three commercial tenants in the property over this time, however, the duration of two of the tenancies did not extend further than a 6 month period while latterly it was used a hair dressing salon for a two year period before becoming vacant again. Despite actively marketing the property for retail and commercial purposes it has only therefore been occupied for a three year period since 2010 which the applicant suggests is unsustainable form a financial perspective. The property's location on the periphery of the town centre and the lack of pedestrian movements along Bridge Street are key contributory factors for the lack of commercial interest in the property and this is unlikely to change whereby the property would potentially remain vacant in the future.

The proposal will provide a beneficial residential use of the vacant and underused commercial property being located in a sustainable town centre location while being compatible with neighbouring commercial and residential uses in Bridge Street. It will also contribute towards the supply of smaller units of residential accommodation within the town while at the same time making a financial contribution towards the provision of

affordable housing within the wider area in accordance with the requirements of Policy AH1 of the LDP.

The proposal is therefore in accord with the objectives of Policies SP1 and RT4 of the LDP in that it will re-use a vacant and underused building while not resulting in any adverse impacts upon the function and visual character of the town centre. Moreover, it is in compliance with the policy objectives of advice contained in paragraphs 4.3.36 and 4.3.37 of Planning Policy Wales which recognise that an emphasis on retaining retail uses in town centre locations which have been vacant for some time can undermine a centre's viability and vitality and consideration should be given to alternative uses that can increase the diversity and vacancy levels. It also highlights the benefits that residential uses can have on retail and commercial centres by contributing to their viability and vibrancy.

Turning to the other matters raised by the respondents, whilst concerns regarding the lack of parking are noted, nonetheless the property is located in a sustainable town centre location within walking distance of a number of public car parks as well as the train and bus stations in the town. The proposal is therefore in accord with policy TR3 of the LDP in terms of its likely parking and highway impacts.

Concerns regarding anti-social behaviour resulting from the development are outside the scope of planning control and it is not envisaged that the creation of a small new residential flat will result in any unacceptable refuse or vermin impacts. Contrary to the respondents' suggestion that existing businesses will impact upon the living conditions of the new occupiers, there are already number of existing residential properties within the street and the use of the building as a residential flat is considered to be compatible with the adjoining hair salon and other neighbouring commercial uses.

Finally, whilst it is acknowledged that the large window to the front of the property is not normally associated with residential properties, nonetheless it does not preclude the use of the property for such purposes nor is it a sound basis upon which to refuse permission. Moreover, the retention of the window in its current form will allow for the potential re-use of the property for retail purposes in the future should the need arise. It will also ensure there will be no unacceptable impact upon the character and appearance of wider conservation area wherein it is located in accordance with the policy requirements of Policies EQ1 and SP13 of the LDP

Planning Obligations

A Unilateral Undertaking has been submitted to secure an affordable housing contribution in accordance with Policy AH1 of the LDP.

Well-being of Future Generations (Wales) Act 2015

The decision considers the duty to improve the economic, social, environmental and cultural well-being of Wales, in accordance with the sustainable development principle, under section 3 of the Well-Being of Future Generations (Wales) Act 2015 (the WBFG Act). The decision takes into account the ways of working set out at section 5 of the WBFG Act and it is considered that this decision is in accordance with the sustainable development principle through its contribution towards one or more of the Welsh Ministers' well-being objectives set out in section 8 of the WBFG Act.

Conclusion

After careful consideration of the scheme as submitted, together with the representations received, it is concluded on balance that the proposal is acceptable and in compliance with the policy objectives of the Authority's adopted LDP and national planning policy. The proposal will provide a beneficial use for a vacant and underused building in the town centre without causing any unacceptable harm to the function, visual character and quality of Carmarthen town centre. Furthermore there are no sustained highway, amenity or historic conservation objections to the development.

The application is therefore put forward with a favourable recommendation subject to the completion of a Unilateral Undertaking securing an affordable housing contribution as part of the development.

Recommendation – Approval

Conditions

- The works hereby granted consent shall be commenced before the expiration of five years from the date of this permission.
- The works hereby granted consent shall be carried out strictly in accordance with the details shown on the following schedule of plans and information received on 9 May 2019:-
 - 1:1250 scale location;
 - 1:50 scale existing and proposed ground floor plan: Internal.

Reasons

- 1 Required to be imposed pursuant to Section 91 of the Town and Country Planning Act 1990.
- 2 To ensure that only the approved works are carried out.

Notes/Informatives

Please note that this consent is specific to the plans and particulars approved as part of the application. Any departure from the approved plans will constitute unauthorised development and may be liable to enforcement action. You (or any subsequent developer) should advise the Council of any actual or proposed variations from the approved plans immediately so that you can be advised how to best resolve the matter.

In addition, any Conditions which the Council has imposed on this consent will be listed above and should be read carefully. It is your (or any subsequent developers') responsibility to ensure that the terms of all Conditions are met in full at the appropriate time (as outlined in the specific condition).

The commencement of development without firstly meeting in full the terms of any Conditions which require the submission of details prior to the commencement of development will constitute unauthorised development. This will necessitate the submission of a further application to retain the unauthorised development and may render you liable to formal enforcement action.

Failure on the part of the developer to observe the requirements of any other Conditions could result in the Council pursuing formal enforcement action in the form of a Breach of Condition Notice.

- 2 Comments and guidance received from consultees relating to this application, including any other permissions or consents required, is available on the Authority's website (www.carmarthenshire.gov.uk).
- The applicant is advised that this planning permission is subject to a Unilateral Undertaking requiring the payment of a financial contribution of £3,135.37 towards the provision of affordable housing.

PWYLLGOR CYNLLUNIO

Dydd Iau, 25 Gorffennaf 2019

YN BRESENNOL: Y Cynghorydd A. Lenny (Cadeirydd)

Y Cynghorwyr:

S.M. Allen, J.M. Charles, I.W. Davies, J.A. Davies, P.M. Edwards, W.T. Evans, S.J.G. Gilasbey, D. Jones, J.K. Howell, J.D. James, H.I. Jones and B.D.J. Phillips

Yr oedd y swyddogion canlynol yn gwasanaethu yn y cyfarfod:

- J. Edwards, Rheolwr Datblygu & Treftadaeth Adeiledig
- G. Noakes, Uwch Swyddog Rheoli Datblygu (y Dwyrain)
- J. Thomas, Uwch Swyddog Rheoli Datblygu (y De)
- S. Murphy, Uwch-gyfreithiwr
- Z.A. Evans, Uwch-dechnegydd (Cyswllt Cynllunio)
- M.S. Davies, Swyddog Gwasanaethau Democrataidd

Hefyd yn bresennol:

Mr G. Morgan, Cynlluniwr Trafnidiaeth gyda Atkins Framework

Siambr, - Neuadd y Sir, Caerfyrddin. SA31 1JP. 10.00 yb - 11.30 yb

1. YMDDIHEURIADAU AM ABSENOLDEB

Derbyniwyd ymddiheuriadau am absenoldeb gan y Cynghorwyr A.C. Jones, J. Lewis, K. Madge, G.B. Thomas a J.E. Williams.

2. DATGAN BUDDIANNAU PERSONAL.

Ni ddatganwyd unrhyw fuddiannau personol.

3. RHANBARTH Y DWYRAIN - PENDERFYNU AR GEISIADAU CYNLLUNIO

PENDERFYNWYD caniatáu'r ceisiadau cynllunio canlynol yn amodol ar yr amodau yn Adroddiad/Atodiad y Pennaeth Cynllunio a/neu y rhoddwyd gwybod amdanynt yn y cyfarfod:-

E/38833	Variation of conditions 2 and 13 of E/33695 at Godre Garreg, Llangadog, SA19 9DA;
E/38956	2.8 metre high fence to left, rear and right boundary at 2 Parc Y Llan, Llandybie, Ammanford, SA18 3HY

4. RHANBARTH Y DE - PENDERFYNU AR GEISIADAU CYNLLUNIO

4.1 PENDERFYNWYD YN UNFRYDOL ganiatáu'r ceisiadau cynllunio canlynol yn amodol ar yr amodau yn adroddiad/atodiad y Pennaeth Cynllunio a/neu y rhoddwyd gwybod amdanynt yn y cyfarfod:-

S/37922	Cynllun ffordd ynghyd â chadw deunydd mewnlenwi
	anadweithiol i godi lefelau'r safle er mwyn hwyluso
	draenio ar y safle ar gyfer datblygiad preswyl yn y



	dyfodol ar dir y tu ôl i Y Garreg Llwyd, Heol Ebenezer, Llanedi, Llanelli;
S/38899	Estyniad unllawr ym mlaen yr adeilad fel rhan o gais am grant anabledd yn 8 Penybryn, Llanelli, SA14 8PS;

4.2 PENDERFYNWYD YN UNFRYDOL ohirio ystyried y ceisiadau cynllunio canlynol er mwyn i'r Pwyllgor Cynllunio ymweld â'r safleoedd:-

S/38535	Helaethu'r safle teithwyr S/34755 [a gymeradwywyd ar 20.03.2018] er mwyn caniatau trydedd lain ar gyfer aelod o'r teulu, yn ogystal â newidiadau i'r cynllun tirweddu a chaniatau i'r safle gael caniatâd parhaol ar dir yn Hillside View, yr Hendy, Llannon, Llanelli, SA14 8JX;
	RHESWM: Galluogi'r Pwyllgor i gael golwg ar y safle o ystyried y pryderon yn ymwneud â diffyg cydymffurfiaeth i amodau sydd ynghlwm ag unrhyw ganiatâd blaenorol.
	Yn unol â phrotocol y Pwyllgor Cynllunio roedd y gwrthwynebwyr oedd wedi gofyn am gael siarad ynghylch yr eitem hon wedi dewis cyflwyno eu sylwadau yn y cyfarfod ar ôl yr ymweliad â'r safle.
S/38787	Adeiladu dau dŷ deulawr ar wahân, safle'r hen glwb bowlio a chymdeithasol, 38 Heol Fair, Cydweli, SA17 4UD; RHESWM: Galluogi'r Pwyllgor i gael golwg ar y safle yng
	nghyd-destun pryderon amwynder a phreifatrwydd.
S/38916	Estyniad unllawr ar ochr yr eiddo, sy'n cynnwys ffenestri yn y to yn lle'r tŷ allan presennol cysylltiedig, decin wedi'i godi a tho gwastad yn Nhre Neddyn, Pontarddulais, Abertawe, SA4 0FP.
	RHESWM: Galluogi'r Pwyllgor i gael golwg ar y safle yng nghyd-destun pryderon preifatrwydd

- 5. RHANBARTH Y GORLLEWIN PENDERFYNU AR GEISIADAU CYNLLUNIO
 - 5.1 PENDERFYNWYD YN UNFRYDOL ohirio ystyried y cais cynllunio canlynol er mwyn i'r Pwyllgor ymweld â'r safle:-

W/37120	Datblygu safle drwy adeiladu bwyty annibynnol a siop goffi annibynnol, ill dau â chyfleusterau gyrru drwyddo cysylltiedig. Gosod ffordd fynediad, maes parcio cysylltiedig, patio, offer echdynnu a gwaith gysylltiedig ehangach i'r safle ar dir wrth gylchfan Sanclêr, Hen Heol Dinbych-y-pysgod, Sanclêr, Sir Gaerfyrddin, SA33 4JW



	Yn unol â phrotocol y Pwyllgor Cynllunio roedd y gwrthwynebwyr oedd wedi gofyn am gael siarad ynghylch yr eitem hon wedi dewis cyflwyno eu sylwadau yn y cyfarfod ar ôl yr ymweliad â'r safle.
	RHESWM : Galluogi'r Pwyllgor i gael golwg ar y mynediad i'r safle.
amodol a	YNWYD YN UNFRYDOL ganiatáu'r cais cynllunio canlynd r yr amodau yn adroddiad/atodiad y Pennaeth Cynll
ariica y iii	oddwyd gwybod amdanynt yn y cyfarfod:-
W/38412	Newid defnydd o storfa amaethyddol i breswylfa 4 ystafell wely anghenion lleol gan gynnwys estyniad yng nghefn yr eiddo, yn dilyn cais cynllunio W/13476 yn Cystanog, Capel Dewi, Caerfyrddin, SA32 8AY;
W/38412 PENDERF	Newid defnydd o storfa amaethyddol i breswylfa 4 ystafell wely anghenion lleol gan gynnwys estyniad yng nghefn yr eiddo, yn dilyn cais cynllunio W/13476

[SYLWER: Mae'r cofnodion hyn yn dilyn trefn y materion oedd ar agenda'r cyfarfod, a allai fod yn wahanol i drefn y materion mewn unrhyw weddarllediad gan y byddid wedi ymdrin gyntaf ag unrhyw geisiadau yr oedd aelodau o'r cyhoedd yn bresennol i siarad amdanynt.]

DYDDIAD



5.2

5.3

CADEIRYDD

