Pecyn Dogfennau



sirgar.llyw.cymru carmarthenshire.gov.wales

DYDD IAU, 29 HYDREF 2020

AT: HOLL AELODAU'R PWYLLGOR CYNLLUNIO

YR WYF DRWYHYN YN EICH GALW I FYNYCHU **CYFARFOD RHITHWIR** O'R **PWYLLGOR CYNLLUNIO** A GYNHELIR AM **10.00 YB**, **DYDD IAU**, **5ED TACHWEDD**, **2020** ER MWYN CYFLAWNI'R
MATERION A AMLINELLIR AR YR AGENDA SYDD YNGHLWM

Wendy Walters

PRIF WEITHREDWR

Swyddog Democrataidd:	Janine Owen
Ffôn (Ilinell uniongyrchol):	01267 224030
E-bost:	Democraticservices@sirgar.gov.uk

Wendy Walters Prif Weithredwr, Chief Executive, Neuadd y Sir, Caerfyrddin. SA31 1JP County Hall, Carmarthen. SA31 1JP

PWYLLGOR CYNLLUNIO

20 AELOD

_				
$V \land DWD$			40	
YCHRWPI	PI AII)	CAIMIKII	7111	$\Delta \vdash I (II)$
I OIVVI I		CYMRU -	10	ALLUD

1.	Y Cynghorydd Mansel Charles	Aelod o Gyngor Cymuned Llanegwad
2.	Y Cynghorydd Tyssul Evans	Aelod o Gyngor Cymuned Llangyndeyrn
3.	Y Cynghorydd Jeanette Gilasbey	Aelod o Gyngor Tref Cydweli
4.	Y Cynghorydd Ken Howell	, ,
5.	Y Cynghorydd Carys Jones	
6.	Y Cynghorydd Alun Lenny	Aelod o Gyngor Tref Caerfyrddin
	(Cadeirydd)	, -
7.	Y Cynghorydd Jean Lewis	
8	Y Cynghorydd Dorian Phillips	
9.	Y Cynghorydd Gareth Thomas	Aelod o Gyngor Cymuned Llanedi
10	Y Cynghorydd Eirwyn Williams	

Y GRŴP LLAFUR – 4 AELOD 1. Y Cynghorydd Penny Edwards

1.	i Cynghorydd Penny Edwards	
2.	Y Cynghorydd John James	Aelod o Gyngor Tref Pen-bre a Phorth Tywyn
3.	Y Cynghorydd Dot Jones	Aelod o Gyngor Cymuned Llannon
5.	Y Cynghorydd Kevin Madge	Aelod o Gyngor Tref Cwmaman

Y GRŴP ANNIBYNNOL - 4 AELOD

1.	Y Cynghorydd Sue Allen	Aelod o Gyngor Tref Hendy-Gwyn
2.	Y Cynghorydd Ieuan Davies	
3.	Y Cynghorydd Joseph Davies	
4.	Y Cynghorydd Irfon Jones (Is-	Aelod o Gyngor Cymuned Bronwydd
	Gadeirydd)	, , , , , , , , , , , , , , , , , , , ,

Y GRŴP ANNIBYNNOL NEWYDD – 2 AELOD 1. Lie Gwag

- 2. Lle Gwag

CANIATEIR EILYDDION TAN Y 30AIN O EBRILL 2021

AGENDA

1.	YMDDIHEURIADAU AM ABSENOLDEB	
2.	DATGAN BUDDIANNAU PERSONOL	
3.	RHANBARTH Y DWYRAIN - PENDERFYNU AR GEISIADAU CYNLLUNIO	5 - 16
4.	RHANBARTH Y DE - PENDERFYNU AR GEISIADAU CYNLLUNIO	17 - 40
5.	LLOFNODI YN GOFNOD CYWIR GOFNODION Y CYFARFOD A	41 - 44



ADRODDIAD PENNAETH CYNLLUNIO, CYFARWYDDIAETH YR AMGYLCHEDD


REPORT OF THE HEAD OF PLANNING, DIRECTORATE OF ENVIRONMENT

AR GYFER PWYLLGOR CYNLLUNIO CYNGOR SIR CAERFYRDDIN

TO CARMARTHENSHIRE COUNTY COUNCIL'S PLANNING COMMITTEE

AR 05 NOVEMBER 2020 ON 05 TACHWEDD 2020

I'W BENDERFYNU/ FOR DECISION Ardal Dwyrain/ Area East



Mewn perthynas â cheisiadau y mae gan y Cyngor ddiddordeb ynddynt un ai fel ymgeisydd/asiant neu fel perchennog tir neu eiddo, atgoffir yr Aelodau fod yn rhaid iddynt anwybyddu'r agwedd hon, gan ystyried ceisiadau o'r fath a phenderfynu yn eu cylch ar sail rhinweddau'r ceisiadau cynllunio yn unig. Ni ddylid ystyried swyddogaeth y Cyngor fel perchennog tir, na materion cysylltiedig, wrth benderfynu ynghylch ceisiadau cynllunio o'r fath.

In relation to those applications which are identified as one in which the Council has an interest either as applicant/agent or in terms of land or property ownership, Members are reminded that they must set aside this aspect, and confine their consideration and determination of such applications exclusively to the merits of the planning issues arising. The Council's land owning function, or other interests in the matter, must not be taken into account when determining such planning applications.

COMMITTEE:	PLANNING COMMITTEE
DATE:	05.11.2020
REPORT OF:	HEAD OF PLANNING

INDEX - AREA EAST

REF.	APPLICATIONS RECOMMENDED FOR APPROVAL	PAGES NOS
PL/00112	ELEVATIONAL ALTERATIONS, BUT NO MATERIAL CHANGE OF USE TO THE BUILDING ITSELF AT FORMER CO-OPERATIVE SUPERMARKET, COLLEGE STREET, AMMANFORD, SA18 3AB.	9-16

APPLICATIONS RECOMMENDED FOR APPROVAL

Application No	PL/00112
Application Type Proposal & Location	FULL PLANNING ELEVATIONAL ALTERATIONS, BUT NO MATERIAL CHANGE OF USE TO THE BUILDING ITSELF AT FORMER CO-OPERATIVE SUPERMARKET, COLLEGE STREET, AMMANFORD, SA18 3AB.
Applicant(s)	Mr Tristan Hobbs, Tretan Developments, Eastmarket Street, Caerphilly, CF83 1NX
Agent	Ken Morgan Design and Building Management Ltd, The Studio, Little Greenway, Crinow Road, Narberth, SA67 8TA

Reason for Committee

This application is being reported to the Planning Committee following the receipt of more than one objection from third parties

ANDREW FRANCIS

AMMANFORD

3rd August 2020

Site

Case Officer

Date registered

Ward

This application site is the well-known former Co-operative building situated off the north eastern flank of College Street, close to the town centre of Ammanford. The building became empty fairly recently as the Co-operative store moved to a brand new store approximately 90 metres to the north west on the site of the former Police Station on the junction of College Street and Margaret Street. As a result, this larger building, built in the early 1980's is now vacant but occupies a strategically important site, directly adjacent to Ammanford's Bus Station and large Council controlled car park.

The irregularly shaped building has a red brick façade up to wall plate, with a slightly angled slate roof leading to a large flat roof. The roof is in two sections, with approximately half of the building at the longer southern end at single storey and typical single storey height, with the remainder at the shorter northern end being taller, made up of a taller roof section.

Most of the walls are solid brick, leading to a fairly imposing and unwelcoming impression if approaching the building from most angles. The existing small entrance doors and windows all face the eastern elevations towards the car park.

The building has an overall length of 49 metres, with a minimum width of 18.9 metres and a maximum width of 40.2 metres.

Proposal

The application is simply to provide changes to the external elevations to the building in order to potentially make the building more viable to commercial interests in the current market. As such, this application DOES NOT seek to change the use of the building or to subdivide the building into different retail/commercial units. Plans showing artist impressions of the elevations with names above different potential access points are purely to show how the building might look and does not imply that "Designer Outlet", "Caffi Amman" or "Tafarn Amman" are going to occupy the building. As stated, this application is not looking at the potential change of use of the building or any subdivision that may be required as the end user(s) is/are not known.

In terms of the elevation changes proposed, the majority of the changes are shown on the north west and south west elevations. The existing north west elevation is blank, with some vents in the side roof profile for the internal plant. The proposed north west elevation shows that new box profile windows are to be introduced into the side profile of the taller roof section, with large new glazing panels, particularly on the walls towards the western end of the building towards the College Street section. Looking at the building directly from College Street, as proposed, the currently blank walls will be extensively glazed and the level up to the access points of the building will be ramped to current DDA standards behind the existing stone wall. All around the building the windows and doors are to be anthracite grey and the currently white eaves are to be improved and clad with grey uPVC. At different points around the building, that are intended to be entrances, they will be marked out by a distinct modern looking rendered or uPVC clad entrance feature.

The proposed south east elevation is shown to have one additional glazed and featured entrance whilst the north east elevation will feature a large glazed area in the lower roof section and a glazed area where the current delivery door is located.

Planning Site History

E/25206 - PROPOSED INSTALLATION OF 24 HOUR ATM CASH MACHINE INTO ELEVATION IN SECURE LAMINATE PANEL TO INCLUDE SECURITY LIGHT AND USED SLIP BOX - FULL GRANTED 3rd October 2011

E/21390 - INSTALL NEW SHOPFRONT TO FRONT ELEVATION - FULL GRANTED 17th August 2009

E/20853 - 4 X FASCIA SIGNS, 2 X DIRECTIONAL SIGNS - ADVERTISEMENT GRANTED 07^{th} May 2009

E/07988 - INSTALLATION OF AUTOMATIC TELLER MACHINE (CASHPOINT) - FULL GRANTED 04th October 2004

AM/03374 - 4 X COOP LOGO/TOWN NAME LOZENGES, 1 X MENU BOARD, 5 X GRAPHIC PANELS (RE-SUBMISSION OF APPLICATION NO E/03040 WITHDRAWN ON 14.10.02) - ADVERTISEMENT GRANTED 24th March 2003

E/03040 - 10 X GRAPHIC PANELS, 4 X LOZENGE SIGNS, 1 X MENU BOARD, 1 X TOTEM SIGN - WITHDRAWN. 14th October 2002

E/00363 - FASCIA SIGNS - ADVERTISEMENT GRANTED - 21st February 1997

P6/22/96 - EXTENSION AND REFURBISHMENT - APPROVED 15th February 1996

P6/69/95 – ADDITION OF CONDENSER UNIT ON UPPER ROOF TO MAINTAIN CURRENT FOOD REGS/MAINTAIN HIGH STANDARD OF TEMP CONTROL – APPROVED 10th March 1995

P6/68/95 – ADVERT – APPROVED 10th March 1995

P6/14462/88 – NEW COVERED WAY TO ENTRANCE LOBBY – APPROVED 06th October 1988

P6/11389/85 – BIN COMPOUND – APPROVED 10th September 1985

P6/5448/79 - FOOD SUPERMARKET - APPROVED 05th June 1980

Planning Policy

Only list policy headings e.g.

Carmarthenshire Local Development Plan (Adopted December 2014) ('the LDP')

SP1 Sustainable Places and Spaces

SP2 Climate Change

SP3 Sustainable Distribution- Settlement Framework

GP1 Sustainability and High Quality Design

RT1 Retail Hierarchy

RT4 Retail Centres (Growth Areas): Town Centre Zone

TR1 Primary and Core Road Networks

TR3 Highways in Developments – Design Considerations

EQ 4 Biodiversity

National Planning Policy and Guidance is provided in <u>Planning Policy Wales</u> (PPW) Edition 10, December 2018 and associated <u>Technical Advice Notes</u> (TANs) published by Welsh Government.

TAN 4: Retail and Commercial Development

Summary of Consultation Responses

Head of Transportation & Highways - No observations received to date.

South Wales Trunk Roads Agency – Has no observations to make on this application.

Head of Public Protection – Has no objections to the proposal.

Ammanford Town Council - No observations received to date.

Local Member - Councillor D E Harries has not commented to date.

All representations can be viewed in full on our website.

Summary of Public Representations

The application was the subject of notification by way of two site notices.

Two representations were received, both generally supporting the intention to develop the old store but are raising objections and the matters raised are summarised as follows:

- The proposal shows new windows on the north east elevation which will directly overlook the houses in the first section of Margaret Street, up to No. 9. This would allow overlooking of gardens and into the backs of these houses through their existing windows.
- The proposed elevations show a public house named 'Tafarn Amman; would be included within the complex. This would be too close to the existing homes on Margaret Street and the road that runs along the north east is the only route to the primary schools. The access road and surrounding area is always severely congested at peak times, with queues all around the main car parks, the access road and Margaret Street. It would be inappropriate to have a public house so close to schools and also object to the inevitable disturbance that would ensue from such establishments.
- The existing residents already have issues regarding parking at the rear entrances of the Margaret Street properties, despite the area being private land, due to its proximity to the car park and people's reluctance to pay car parking charges. Despite the homeowners legal rights, this unauthorised car parking causes a daily issue. The proposal could cause this issue to get worse and as such, would require assurance that the risk of the objector's right of way being compromised will be mitigated and how. Some people in the street have significant medical issues and this parking issue directly affects health and quality of life.
- Despite the access road having a 20 mph speed limit, this doesn't stop cars from speeding with the Police not able to control it. With the increase in footfall a safe crossing should be considered.

All representations can be viewed in full on our website.

Appraisal

Principle of development

The application seeks to provide changes to the large, strategically important building in the town centre of Ammanford, in order to make it more viable for current retail and commercial requirements. The building is not being extended, nor is this application looking to consider any changes of use, it is purely to consider the design changes to the external elevations of this building which seek to modernise the building. This should then

allow it to be marketed based on a building with large glass frontages offering any potential occupiers a more vibrant and attractive building to operate out of. As such, as no change of use is being proposed, it is considered that the principle of this proposal is acceptable and would be beneficial for Ammanford.

Impact upon character and appearance of the area

The current building, built in the early 1980's is currently quite ominous with large, blank facades. Since the Co-op left this building it has emphasised its tired appearance which, given the building's strategic location, is a terrible waste of an important site. The design changes successfully modernise the building greatly improving its visual appearance when considered in isolation but also in the context of its location adjacent to the town's Bus Station, car park and close to a historic Arcade that enjoys Listed Building status.

A point of objection raised concern that one of the units shown on the elevations was to be a Public House – "Tafarn Amman". As clarified above, this is just an artistic impression at this stage. A separate planning application would be required to consider the potential subdivision of the units when the floor plan of the building is known. The Use Class of the building is currently A1 – Retail, so any change to a potential A3 – Public House/Sale of Hot Food will also require planning permission, which is not being sought or granted as part of this application.

Privacy Impacts

Another point of objection relates to the concern that the glazing on the new building, and in particular that shown on the north east elevation will impact upon the privacy of the existing occupiers of the existing dwellings addressed as 1-9 Margaret Street. With regards to this point, the large shop front windows are situated at ground floor level and as such, the existing garden wall and outbuildings will provide good levels of privacy to the garden areas from people who may potentially be in the building in the future. New windows are proposed at first floor level, set into the slate cladding. However, it is not known what is to occupy this level as this application does not seek to consider that detail, only the external changes. Should it become apparent that here may be an issue relating to these windows based on future details, it may become necessary to impose conditions relating to them at this stage. However, the windows of the dwellings are at least 32 metres distant and set at an oblique angle. As such, whilst there may be an alteration to the perceived levels of privacy enjoyed, based on the information currently, it is considered that it would not be enough to be considered to be detrimental.

Biodiversity Impacts

No bats were found and the building isn't considered to be suitable to accommodate bats.

Highway Impacts

Further points of objection relate to parking and highways concerns. Again, it is beyond the remit of this application to consider such issues as the consideration to the changes to the elevations do not go on to have highway and parking implications. These would become a consideration when the subdivision and uses of the building are considered. However, given the former and current accepted use of the building and the adjacent Council operated car park, the issues raised relate to parking enforcement rather than planning, particularly given the ultimate intention to bring this building back into beneficial use. As

such, at that time, it may become prudent to consider a safe crossing point as advised by an objector. However, the issue of parking issues, speeding and congestion are concerns that cannot be addressed by changes to the elevation of the building.

Planning Obligations

There are no planning obligations related to this proposed development.

Well-being of Future Generations (Wales) Act 2015

The decision considers the duty to improve the economic, social, environmental and cultural well-being of Wales, in accordance with the sustainable development principle, under section 3 of the Well-Being of Future Generations (Wales) Act 2015 (the WBFG Act). The decision takes into account the ways of working set out at section 5 of the WBFG Act and it is considered that this decision is in accordance with the sustainable development principle through its contribution towards one or more of the Welsh Ministers' well-being objectives set out in section 8 of the WBFG Act.

Conclusion

After careful consideration of the scheme as submitted it is concluded on balance that the proposed modernisation to the external appearance of this strategically important building for Ammanford is an acceptable form of development that will help make the currently redundant and quite featureless building much more attractive as a retail opportunity for new operators. This application does not seek to subdivide the building, so it is not known whether the building will remain as one large retail unit, or split into smaller units. That application will be needed should the marketing of this building be successful, as hoped. The modernisation and reuse of this building should greatly enhance the vibrancy of Ammanford's Town Centre and as the proposal is compliant with local and national planning policy and in the absence of any sustainable planning objections, this application is recommended for approval.

Conditions and Reasons

Condition 1.

The development hereby permitted shall be commenced before the expiration of five years from the date of this permission.

Reason:

Required to be imposed pursuant to Section 91 of the Town and Country Planning Act 1990.

Condition 2.

The development hereby permitted shall be carried out strictly in accordance with the following schedule of plans and documents:

Existing Location and Block Plans, Elevations and 3D View Scale 1:1250, 1:500,
 1:100 @ A1 [01C] received on the 27 July 2020

Proposed Elevations and 3d View Scale 1:100 @ A1 [02 Rev C] received on 30 June 2020.

Reason:

In the interests of visual amenity and for the avoidance of doubt or confusion as to the extent of the permission hereby granted. (LDP policies GP1, RT1, RT4)

REASONS FOR GRANTING PLANNING PERMISSION

The decision to grant planning permission has been taken in accordance with Section 38 of the Planning and Compulsory Purchase Act 2004, which requires that, in determining a planning application the determination must be in accordance with the Development Plan unless material considerations indicate otherwise.

• The proposed development complies with Policy SP1, SP2, SP3, GP1, RT1, RT4, TR1, TR3 and EQ4 of the LDP in that the modernisation of the elevations of this existing building in the town centre of Ammanford, a Primary Growth Centre is in a strategically important location which is easily accessed by public transport and makes effective use of an existing building which no only is of a good design, but which is more ecologically sensitive than providing a new building. The re-use of the building will aid the vitality of the retail elements of Ammanford's Town Centre and is well served off a Trunk Road and by public transport, along with walking and cycling. Furthermore, it would not have any significant adverse effect on visual amenity, residential amenity, general amenity or highway/pedestrian safety.

Note 1.

Please note that this permission is specific to the plans and particulars approved as part of the application. Any departure from the approved plans will constitute unauthorised development and may be liable to enforcement action. You (or any subsequent developer) should advise the Council of any actual or proposed variations from the approved plans immediately so that you can be advised how to best resolve the matter.

In addition, any conditions which the Council has imposed on this permission will be listed above and should be read carefully. It is your (or any subsequent developers') responsibility to ensure that the terms of all conditions are met in full at the appropriate time (as outlined in the specific condition).

The commencement of development without firstly meeting in full the terms of any conditions which require the submission of details prior to commencement of development will constitute unauthorised development. This will necessitate the submission of a further application to retain the unauthorised development and may render you liable to formal enforcement action.

Failure on the part of the developer to observe the requirements of any conditions could result in the Council pursuing formal enforcement action in the form of a Breach of Condition Notice.

Note 2.

Comments and guidance received from consultees relating to this application, including any other permissions or consents required, is available on the Authority's website (www.carmarthenshire.gov.uk).

Eitem Rhif 4

Ardal De/ Area South

ADRODDIAD PENNAETH CYNLLUNIO, CYFARWYDDIAETH YR AMGYLCHEDD


REPORT OF THE HEAD OF PLANNING, DIRECTORATE OF ENVIRONMENT

AR GYFER PWYLLGOR CYNLLUNIO CYNGOR SIR CAERFYRDDIN

TO CARMARTHENSHIRE COUNTY COUNCIL'S PLANNING COMMITTEE

AR 05 TACHWEDD 2020 ON 05 **NOVEMBER** 2020

I'W BENDERFYNU/ FOR DECISION





Mewn perthynas â cheisiadau y mae gan y Cyngor ddiddordeb ynddynt un ai fel ymgeisydd/asiant neu fel perchennog tir neu eiddo, atgoffir yr Aelodau fod yna rhaid iddynt anwybyddu'r agwedd hon, gan ystyried ceisiadau o'r fath a phenderfynu yn eu cylch ar sail rhinweddau'r ceisiadau cynllunio yn unig. Ni ddylid ystyried swyddogaeth y Cyngor fel perchennog tir, na materion cysylltiedig, wrth benderfynu ynghylch ceisiadau cynllunio o'r fath.

In relation to those applications which are identified as one in which the Council has an interest either as applicant/agent or in terms of land or property ownership, Members are reminded that they must set aside this aspect, and confine their consideration and determination of such applications exclusively to the merits of the planning issues arising. The Council's land owning function, or other interests in the matter, must not be taken into account when determining such planning applications.

COMMITTEE:	PLANNING COMMITTEE
DATE:	05 NOVEMBER 2020
REPORT OF:	HEAD OF PLANNING

INDEX - AREA SOUTH

REF.	APPLICATIONS RECOMMENDED FOR APPROVAL	PAGE NOS
PL/00020	PROPOSED SITING OF A DETACHED DWELLING HOUSE - LAND PART OF 1 BAY VIEW, PWLL, LLANELLI, SA15 4BE	21-30
S/40262	CONSTRUCTION OF 7NO. LOCK UP GARAGES AT LAND OFF ANN STREET, LLANELLI, SA15 1TE	31-39

APPLICATIONS RECOMMENDED FOR APPROVAL

Application No	PL/00020	
Application Type	Outline – All Matters Reserved	
Proposal & Location	Proposed siting of a detached dwelling house - Land part of 1 Bay View, Pwll, Llanelli, SA154BE	

Applicant(s)Mr StevensonAgentMs Nicola Steward – Prime Architecture LtdCase OfficerZoe JamesWardHengoedDate registered3 September 2020

Reason for Committee

This application is being reported to the Planning Committee following the receipt of more than one objection from third parties.

Site

The application site consists of a rectangular shaped parcel of land located at the corner of Elgin Road and Tyle Catherine in Pwll. It fronts onto Elgin Road with an existing vehicular access to the east side onto Tyle Catherine.

The site has a width of around 22.5m and depth of around 12 metres. The site slopes in a southerly direction as per Tyle Catherine. The site is bordered by existing walls to the east and west and a retaining wall along its boundary with Elgin Road to the north. To the west lies a two storey dwelling known as Blenhiem House that is separated from the site by high block walling. To the south lie existing garages and an undefined boundary with the rear gardens of properties no. 1 and 2 Bay View.

The site is located in a primarily residential area consisting of a mix of detached and semidetached properties. The neighbouring properties of Elgin Road have long rear gardens while two semi-detached properties immediately to the south have standard sized gardens. To the south east two new properties have been built on the opposite side of Tyle Catherine in recent years.

Proposal

The application seeks outline permission for the construction of a detached dwelling house with all matters reserved for future consideration.

The indicative Proposed Site Layout Plan submitted with the application shows the proposed new house occupying the western half of the site being within close proximity to, and fronting onto Elgin Road. The dwelling is to measure some 8.8-9.2 metres in width and 6.5-7.2 metres in depth, whilst its ridge level is to be approximately 7-7.3 metres in height. It is to have the benefit of a side and rear garden area with the access that currently serves the garage of no.1 Bay View is proposed to be widened to provide a new driveway along the southern boundary of the site. The indicative layout shows provision being made for the parking of 2 vehicles within the curtilage of the proposed new dwelling. The submitted plan also shows that siting of the dwelling in subject position would result in a minimum distance of 15.5 metres between windows of the proposed dwelling and no. 1 Bay View and up to 20 metres between the dwelling and no. 2 Bay View.

As detailed below, the application site has a fairly extensive history and was the subject of four previous applications for outline planning permission for the construction of a detached dwelling, all of which were refused by the Local Planning Authority up to 2010. Following the refusal on 13 May 2010, the applicant appealed the decision under application reference S/22648, and notwithstanding the Authority's concerns the Inspector presiding over the appeal concluded that the development proposed was acceptable within the wider context and subsequently granted outline planning permission on 23 September 2010. This permission then lapsed and in 2016 the Authority granted permission (reference. S/32316) in line with the previous outline consent granted by the Inspector. Most recently in November 2019 a full application was submitted (reference. S/40193) for a 3 bedroomed detached dwelling at the site. The application was withdrawn by the applicant in July 2020.

Planning Site History

The following previous applications have been received on the application site:

TA//80890 - PROPOSED DEVELOPMENT OF A 3 BEDROOM DWELLING - Cancelled

PASAB/00029 - NEW DETACHED DWELLING - SAB Pre-application enquiry

S/40193 - RESIDENTIAL DEVELOPMENT OF A 3 BEDROOM DWELLING - Withdrawn 06/07/2020

S/32316 - DETACHED DWELLINGHOUSE - Outline Granted 05/04/2016

 $\rm S/22648$ - SITING OF DETACHED DWELLING HOUSE - Outline Refusal 13/05/2010 - Appeal Upheld 23/09/2010

S/17781 - RESIDENTIAL DEVELOPMENT - Outline Refused 08/01/2008

S/15917 - 1 NO. DETACHED HOUSE (3 BED) - Outline Refused 27/04/2007

S/07996 - SINGLE DETACHED DWELLING - Outline Refused 28/10/2004

Planning Policy

In the context of the Authority's current Development Plan the site is within the defined development limits of Llanelli as contained in the adopted Local Development Plan (LDP). It is not the subject of any designation or allocation in the Plan. Reference is drawn to the following policies of the Plan:-

Carmarthenshire Local Development Plan (Adopted December 2014) ('the LDP')

SP1 Sustainable Places and Spaces

SP3 Sustainable Distribution- Settlement Framework

GP1 Sustainability and High Quality Design

GP2 Development Limits

GP3 Planning Obligations

GP4 Infrastructure and New Development

H2 Housing within Development Limits

AH1 Affordable Housing

TR3 Highways in Developments

EQ4 Biodiversity

EP2 Pollution

EP3 Sustainable Drainage

Carmarthenshire Supplementary Planning Guidance

National Planning Policy and Guidance is provided in <u>Planning Policy Wales</u> (PPW) Edition 10, December 2018 and associated <u>Technical Advice Notes</u> (TANs) published by Welsh Government.

Summary of Consultation Responses

Head of Transportation & Highways - No objections subject to conditions.

Llanelli Rural Council - Has objected to the application on the following grounds:-

- Area has been over developed resulting in high density of garden development and is not considered appropriate as it will have overbearing effect on neighbouring dwellings being detrimental to amenity and privacy of the properties immediately situated to the west and south.
- There are highway safety concerns in relation to the proposed access/egress arrangements servicing the dwelling. Highway safety concerns regarding poor visibility approaching the site along Elgin Road. High volume of traffic as well as severe on-street parking issues. There appears to be insufficient manoeuvring space in the current design to accommodate this within the site.

Local Member(s) - Councillor Susan Phillips has not commented to date.

Local Member(s) - Councillor Penny Edwards is a member of the Planning Committee and has made no prior comment.

Dwr Cymru/Welsh Water – no objection subject to imposition of conditions.

Natural Resources Wales - no observations on the proposal.

Planning Ecology - no objections subject to conditions.

Sustainable Drainage Approval Body (SAB) – site has SAB approval under reference. SAB/00042.

All representations can be viewed in full on our website.

Summary of Public Representations

The application was the subject of notification by way of neighbouring letters issued.

Six representations were received, all objecting with the matters raised are summarised as follows:

- Any building will compromise the structural integrity of the retaining wall built by the Council to maintain Elgin Road which was built after subsidence problems along the northern boundary of the proposed dwelling.
- Carmarthenshire County Council previously refused permission in 2010, as they did not consider it a suitable site, but this was upheld at appeal, and now in 2020 it is much less suitable than before.
- Hill is one-way, single lane and very steep and the proposed driveway is dangerously close to a blind junction which is used daily. Road safety Act 2006[c49] designed to improve road safety.
- Turning down Tyle Catherine is hazardous and tricky manoeuvre.
- Number of potholes on Tyle Catherine evidencing the strain on the road network.
- Site is close to a school with a number of vulnerable pedestrians walking passed daily and there are no pavements for children walking to and from school.
- Road is too narrow, emergency services already have to ask for cars to be moved to get passed.
- Large removal vehicles and builders merchant vehicles have trouble navigating the junction of Elgin Road and Tyle Catherine resulting in a building merchant refusing to deliver to Elgin Road due to safety concerns.
- Dwelling at this site will sit directly above and behind property no. 2 Bay View taking away all privacy from the back of house and garden.
- In October 2018, part of the retaining wall was removed beside the existing garages to make an entrance for the proposed dwelling just months after the outline planning permission had lapsed. The entrance does not allow space for cars to drive in and out and is close to a blind junction.
- Application is detrimental to community and public.
- Since previous application additional building work has taken place on Elgin Road, overpopulating the street and adding further congestion.
- Construction activity at the site, even for a temporary period will lead to significant safety concerns.
- Requests a site visit is undertaken to appreciate negative and dangerous impact of the proposal.

All representations can be viewed in full on our <u>website</u>.

Appraisal

Principle of development

The principle of residential development at the site has previously been accepted through the granting of outline planning permission at appeal in 2010 and again by the Local Planning Authority in 2016. The time period for submission of reserved matters has now passed albeit the five years outline planning permission runs to April 2021. The site is also located within the defined development limits whereby new residential development is typically supported subject to relevant policies within the LDP.

The application is outline with all matters reserved, yet the submitted information demonstrates that the site, is of sufficient size to accommodate a modest dwelling alongside adequate parking and private amenity space. The parameters proposed are in line with the parameters previously proposed and accepted at the site by both the Inspector and LPA.

Overdevelopment and impact upon character and appearance of the area

The Rural Council raise concerns that the proposal would result in the overdevelopment of the site and result in a cramped form of development. The Inspector in granting the previous outline permission opined that the layout of the development would be consistent with the surrounding pattern of development with sufficient space being provided between and around existing development to ensure it would be compatible in scale and siting with its surroundings. The character of the area surrounding the site comprises existing residential dwellings of a mixture of varying style, design and size. The current application proposes the same parameters for a new dwelling as accepted by the Inspector originally and by the Planning Authority in 2016. As such, the proposal is not considered to appear cramped or harmful to the character and appearance of the locality and in this regard the proposal is considered accord with the objectives of policies GP1, GP2 and H2 of the LDP.

Privacy Impacts

Concerns are also raised from Llanelli Rural Council and third parties regarding privacy. As previously referred the details regarding the siting and design of the dwelling are not being considered at this stage. However, based on the indicative Proposed Site Plan and specified parameters, the proposed dwelling is not considered to adversely impact on privacy of neighbouring properties. This was opined by the Inspector who considered that the placement and orientation of windows in the new dwelling could be designed to ensure no harmful loss of privacy to the two existing properties to the rear of the site while suitable boundary and landscaping treatments could limit the amount of mutual overlooking between neighbouring gardens. As a result, it was concluded by the Inspector and again now by the LPA that there would be no significant loss of privacy beyond that expected in built up areas and sufficient space allows for suitable distances between the development and existing properties. The precise details regarding positioning of the dwelling and window placement will be considered as part of a subsequent reserved matters application. The outline application is considered to comply with the relevant requirements of LDP Policy GP1.

Highway Impacts

One of the main grounds for concern amongst respondents is the inadequacy of the local highway network to safely accommodate the development with particular reference being made to the existing junction of Tyle Catherine, the narrowness of the roadways and the

current level of on street parking. In granting the previous outline permission, the Inspector concluded that the development was acceptable from an access and highway safety perspective. The Authority's own Head of Transport has reviewed the current application and is of the same opinion whereby he offers no objection to the current application subject to the imposition of certain conditions. Conditions relate to vehicle access, visibility, suitable parking scheme and also details to confirm the integrity of the existing highway-retaining wall will not be negatively affected by construction work. The proposal therefore meets the requirements of policy TR3 of the LDP.

Biodiversity Impacts

The Planning Ecologist has raised no objection to the outline planning application subject to certain conditions regarding vegetation clearance. The presence of invasive species, such as Japanese Knotweed, on site was also queried and the agent confirmed that there is no sign of this. The application will be required to be accompanied by details of proposed landscaping as part of future reserved matters submission.

Drainage

As highlighted in the response from the SAB team, the site already benefits from SAB approval (reference. SAB/00042) for drainage matters at the site.

Other Matters

The concerns raised regarding potential damage to neighbouring properties is not a material planning consideration in the determination of the application. Development at the site would need to obtain the relevant building regulations certification at the start and throughout construction.

Planning Obligations

A Unilateral Undertaking is due to be submitted by the applicant regarding a commuted payment to contribute towards the provision of affordable housing in the locality as part of the proposal. As such, the proposal will comply with the requirements regarding affordable housing within LDP Policy AH1 (Affordable Housing).

Well-being of Future Generations (Wales) Act 2015

The decision considers the duty to improve the economic, social, environmental and cultural well-being of Wales, in accordance with the sustainable development principle, under section 3 of the Well-Being of Future Generations (Wales) Act 2015 (the WBFG Act). The decision takes into account the ways of working set out at section 5 of the WBFG Act and it is considered that this decision is in accordance with the sustainable development principle through its contribution towards one or more of the Welsh Ministers' well-being objectives set out in section 8 of the WBFG Act.

Conclusion

After careful consideration of the scheme as submitted, alongside third-party comments and the planning history, it is concluded on balance that the proposed dwelling is acceptable.

The application seeks to renew a previous outline planning permission granted in April 2016 under application reference. S/32316 and prior to that by an Inspector at appeal under application reference S/22648 in May 2010. The proposal has been reviewed again now and there have been no material change in circumstances in the intervening period since the granting of the previous permission that would justify withholding permission in respect of the current application. There are no amenity, highway or public service objections to the development and the proposal complies with the policy objectives of the Authority's LDP.

The concerns regarding privacy and overbearing are considered suitable to be addressed through site positioning and window orientation at reserved matters stage. The concerns regarding the access issues are considered to be adequately dealt with under the proposed planning conditions required by the Highways Officer which ensure there is no detrimental impact to highway safety.

On balance, the proposal is considered to be in accordance with the above identified LDP policies.

The application is therefore put forward with a favourable recommendation subject to the applicant entering into a unilateral undertaking or Section 106 Agreement securing a commuted payment towards the provision of affordable housing in the locality in accordance with the requirements of Policy AH1 of the LDP.

Condition 1

Application for approval of reserved matters must be made to the Local Planning Authority before the expiration of three years from the date of this permission, and the development must be commenced not later than whichever is the later of the following:-

- a) the expiration of five years from the date of this outline planning permission;
- b) the expiration of two years from the date of approval of the last of the reserved matters to be approved.

Reason:

Required to be imposed pursuant to Section 91 of the Town and Country Planning Act 1990.

Condition 2

The permission now granted is an outline permission only, for one single dwelling, within the meaning of the Town and Country Planning (Development Management Procedure) (Wales) Order 2012.

Reason:

The application is in outline only.

Condition 3

Development shall not commence until detailed plans of the layout, scale, appearance and landscaping of the development, together with the means of access thereto, have been submitted to and been approved in writing by the Local Planning Authority.

Reason:

In the interests of visual amenity.

Condition 4

The land subject to this permission is as identified on the 1:1250 scale Site Location Plan and 1:200 Site Block Plan drawing no. 646 02 and Proposed Site Plan scale 1:200 drawing no. 646 01 received 2 September 2020.

Reason:

For the avoidance of doubt.

Condition 5

Any reserved matters application shall be accompanied by full cross sections, finished floor levels and means of enclosure so that the proposal can be seen in the context of the road and the surrounding dwellings.

Reason:

In the interests of visual amenity.

Condition 6

Prior to commencement of any part of the development herewith approved details and calculations shall be submitted to the written approval of the Local Planning Authority establishing that the integrity of the existing highway-retaining wall is not negatively affected by the proposed construction works.

Reason:

In the interest of highway safety.

Condition 7

The new vehicular access shall be laid out and constructed strictly in accordance with Carmarthenshire County Councils (Highways and Transport services) Typical Layout No. 2 (specification for which is attached to this planning permission), prior to the commencement of any other work or development. Thereafter it shall be retained, unobstructed, in this form in perpetuity.

Reason:

In the interest of highway safety.

Condition 8

There shall at no time be any growth or obstruction to visibility over 0.6 metres above the adjacent carriageway crown, over the site's whole Tyle Catherine Road (W5907) frontage within 2.0 metres of the near edge of the carriageway.

Reason:

In the interest of highway safety.

Condition 9

Prior to the commencement of development the written approval of the Local Planning Authority shall be obtained for a scheme of parking within the curtilage of the site, and this shall be dedicated to serve the proposal. The approved scheme is to be fully implemented prior to any part of the development being brought into use, and thereafter shall be retained, unobstructed, in perpetuity.

Reason:

In the interest of highway safety.

Condition 10

All surface water from the development herewith approved shall be trapped and disposed of so as to ensure that it does not flow on to any part of the public highway or shall not be disposed of, or connected into, existing highway surface water drains.

Reason:

In the interest of highway safety.

Condition 11

No surface water and/or land drainage shall be allowed to connect directly or indirectly with the public sewerage network

Reason:

To prevent hydraulic overloading of the public sewerage system, to protect the health and safety of existing residents and ensure no pollution of or detriment to the environment.

Condition 12

Any works affecting vegetation on site must be done outside the nesting season, which is recognised to be from March to August inclusive, unless it can be demonstrated that nesting birds are absent. It should be noted that birds may still be nesting outside this season, therefore care should be taken to ensure that no nesting birds are affected. Vegetation clearance shall be undertaken ensuring no adverse impact on reptiles.

Reason:

To ensure the necessary protection of nesting birds and reptiles.

Notes/Informatives

Note 1

Please note that this permission is specific to the plans and particulars approved as part of the application. Any departure from the approved plans will constitute unauthorised development and may be liable to enforcement action. You (or any subsequent developer) should advise the Council of any actual or proposed variations from the approved plans immediately so that you can be advised how to best resolve the matter.

In addition, any conditions which the Council has imposed on this permission will be listed above and should be read carefully. It is your (or any subsequent developers') responsibility to ensure that the terms of all conditions are met in full at the appropriate time (as outlined in the specific condition).

The commencement of development without firstly meeting in full the terms of any conditions which require the submission of details prior to commencement of development will constitute unauthorised development. This will necessitate the submission of a further application to retain the unauthorised development and may render you liable to formal enforcement action.

Failure on the part of the developer to observe the requirements of any conditions could result in the Council pursuing formal enforcement action in the form of a Breach of Condition Notice.

Note 2

The applicant/developer's attention is drawn to the signed legal agreement pursuant to Section 106 of the Town and Country Planning Act 1990 in respect of an affordable housing contribution of £58.78 per square metre internal floor area.

Note 3

Comments and guidance received from consultees relating to this application, including any other permissions or consents required, is available on the Authority's website (www.carmarthenshire.gov.uk).

 Please see the relevant responses from Dwr Cymru/Welsh Water, The Highway Authority, Planning Ecologist and the Council's Sustainable Urban Drainage Body (SAB) and refer to the recommendations and advice contained therein.

Application No	S/40262
Application Type	Full Planning
Proposal & Location	CONSTRUCTION OF 7NO. LOCK UP GARAGES AT LAND OFF ANN STREET, LLANELLI SA15 1TE

Applicant(s)	MR DAVID LANG, 598 BIRCHGROVE ROAD, GLAIS, SWANSEA SA7 9EN	
Case Officer	Robert Davies	
Ward	Tyisha	
Date registered	21/02/2020	

Reason for Committee

This application is being reported to the Planning Committee following the receipt of more than one objection from third parties.

Site

The application site consists of a level, almost rectangular parcel of land located between a residential property known as 1 Llys y Morwr and the Great Western Railway Public House at Ann Street in Llanelli. There are allotments to the immediate south of the site whilst there are residential dwellings and a complex known as Cwrt Waddle on the opposite side of Ann Street.

The site is approximately 23m in depth by 19m in width.

Proposal

The application seeks full planning permission to construct 7no. lock up garages at the site. The applicant has confirmed that the garages are intended for use by local residents for domestic vehicular parking and personal storage possession.

The proposed garages are laid out in a reverse 'L' format in two separate blocks. The larger block measures 14.3m in width, 6.3m in depth and has a maximum ridge height of 3.1m. The smaller block is 9.4m by 6.3m and is of the same height. The proposed external finishes to the development consist of a mixture of render and facing brick to the walls, grey box profile sheets to the roof and galvanised steel roller shutter garage doors.

A new dropped kerb vehicular access is proposed in a central position off Ann Street, which will be hard surfaced for the first part and then the internal turning area will be surfaced with

porous gravel. The existing 1.8m high feather fencing along the southern and eastern boundaries is being retained, whilst some additional fencing is proposed to prevent access to the rear of the proposed garages.

In addition to the drawings the application has been accompanied by a Coal Mining Risk Assessment.

Planning Site History

The following previous applications have been received on the application site:-

D5/16812 Residential development

Outline planning permission

16 March 1995

Planning Policy

<u>Carmarthenshire Local Development Plan</u> (Adopted December 2014) ('the LDP')

GP1 Sustainability and High Quality Design

TR2 Location of Development – Transport Considerations

TR3 Highways in Developments - Design Considerations

Carmarthenshire Supplementary Planning Guidance

National Planning Policy and Guidance is provided in <u>Planning Policy Wales</u> (PPW) Edition 10, December 2018 and associated <u>Technical Advice Notes</u> (TANs) published by Welsh Government.

Summary of Consultation Responses

Head of Transportation & Highways - No objection.

Llanelli Town Council - Object on the following grounds:-

- The proposed development is felt to contravene Policy GP1 part (g) in that the proposal will create a location where criminal activity such as drug dealing is likely to be undertaken.
- The proposed development is felt to contravene Policy GP1 part (h) and (l) in that traffic problems will likely be created with the number of vehicles entering and leaving the site.
- For the above reasons it is highly likely that the proposed development if approved will have a significantly detrimental impact on the amenity of adjacent residents. The proposal therefore contravenes Policy GP1 (d);
- The proposal is an over development of the site.

Local Member(s) - County Councillors S Curry and A McPherson both object on the following grounds:-

- Concerned that the garages (if built) will give cover to those individuals that perform illegal activities such as drug dealing and use to congregate.
- The development will cause traffic problems with the number of vehicles entering and leaving the site, causing congestion and possibly an accident, as the location is on a blind bend in the road and could be dangerous.
- Due to the matters noted above it is highly likely that the proposed development if approved will have a significantly detrimental impact on the amenity of adjacent residents.
- Over development of the site.
- The site suffers from Japanese Knotweed infestation which has not been treated.
- The local community do not want this development to happen.
- Cllr Curry and Cllr McPherson request that the planning committee make a site visit to see the problems first-hand.

Suds Approval Body – No objection. Confirmed SAB approval required.

Dwr Cymru/Welsh Water – No objection.

The Coal Authority – No objection subject to condition.

All representations can be viewed in full on our website.

Summary of Public Representations

The application was originally the subject of notification by way of both neighbour letters and the posting of site notices. The application was also subject to re-consultation following the receipt of additional information and amended plans. Two letters of representation have been received objecting on the following grounds:-

- An excavator was delivered to site and work commenced before the planning application was decided.
- Highway Safety the site is close to a bend with limited view of oncoming traffic; there is very little parking in the area for residents already and the traffic generated by the development will exacerbate matters; residents may lose on street parking spaces through restrictions to ensure that the access to this site is safe.
- Such garages attract anti-social behaviour, vandalism and drug taking. There is a longstanding problem in the area where many old County Council garages have been demolished because of such anti-social problems.
- The Tyisha ward has been identified for a major regeneration project and such a development could adversely impact that scheme and the wishes of the community.

All representations can be viewed in full on our website.

Appraisal

As Members will have noted, a number of objections have been received from both Local Members, the Town Council and two members of the public. The reasons for concern and objection raised will be addressed individually as part of this appraisal.

The respondents opine that the proposed garages will create a location where criminal activity and anti-social behaviour will occur with vandalism and drug dealing/taking sited as specific concerns. Reference is drawn to long standing problems with old Council garages in other parts of the town. With respect to this issue, the Local Planning Authority (LPA) has liaised with the Designing Out Crime Officer at Dyfed Powys Police, who made the following three recommendations for any Secured by Design development of this nature at this location:-

- Boundary fencing should be Hit and Miss to 1.8m in height, topped with a capping rail.
- The garage area should be illuminated to BS 5489-1 2013 during the hours of darkness to provide safe passage to anyone using the area.
- Pedestrian and vehicular gates should be installed, operated by use of a fob, to prevent unwanted misuse of the area.

These suggestions have been forwarded on to the applicant and amended plans have been submitted which show a 1.8m hit and miss fence with capping rail proposed either side of the garage block to prevent unwanted access to the rear, whilst the plan also shows some high level lighting to the referred BS standard on the proposed garage buildings themselves.

The applicant is not proposing to install pedestrian and vehicular gates on the frontage with Ann Street as any such gates would need to be set back 5m from the edge of the highway, and any fencing below 600mm in height to comply with recommended highway conditions. Notwithstanding this, the application site is highly visible from Ann Street and is naturally surveyed and overlooked by surrounding properties. There is also a streetlight directly outside the application site which lights the area up during hours of darkness coupled with the additional lighting proposed as part of the development. Many of the older problematic garage sites referred to in the Llanelli area are sited in more secluded areas, not open to public viewing.

Therefore, it is considered that there is no justifiable reason to refuse planning permission on the perceived risk of such a development attracting criminal activity. The LPA has received and approved a number of such applications in Llanelli over recent years without reported incident in this respect.

Concerns have also been raised over highway safety with traffic generation, the location of the site on a bend and loss of on street parking sited as specific reasons for concern. As aforementioned, the LPA has received and approved a number of such developments in Llanelli town centre over recent years, whereby the demand is largely driven by town centre residents wanting a safe off-street area to park their vehicles and to store domestic items. The applicant has confirmed that he has already received interest from local residents and believes that the demand is there for such a facility.

With respect to highway safety matters, the Authority's Head of Highways has confirmed that the traffic generated by the proposed development will be low, and the highway infrastructure including access and visibility is sufficient. It is also noted that there are parking restrictions in place in the form of double yellow lines immediately outside the site at Ann Street, and therefore the proposal will not result in the loss of, or displacement of on street parking. As a result, the Authority's Head of Highways has raised no objection subject to conditions.

For the above reasons, objectors are of the opinion that the proposal will adversely affect the residential amenity of adjacent residents. In this regard the proposal is for domestic purposes only and conditions can be imposed on any planning permission granted to ensure that this is the case.

In terms of scale and design, the proposed development is considered to be acceptable and will not result in an overdevelopment of the application site. The proposed garages are domestic and simplistic in appearance, and the proposed pallet of materials is considered vernacular to the area.

The presence of Japanese Knotweed on the site has been highlighted. In this regard the applicant has acknowledged this and has confirmed that a scheme of treatment will be undertaken. It is therefore recommended that a condition requiring the submission of an eradication scheme for Japanese Knotweed is imposed on any planning permission granted.

One of the objectors stated that excavators were seen on the site and witnessed that works commenced on the development before the planning application was determined. In this regard, the works seen taking place on the site were not commencement works, but were intrusive site investigations linked to previous Coal Mining activity in the area. During the course of the planning application process, the Coal Authority requested a Coal Mining Risk Assessment (CMRA) as the application site is located in a Development High Risk Area. Following the receipt of the CMRA, the Coal Authority requested that intrusive site investigations took place to establish the location of mine shafts within the site, their zones of influence and to identify no build zones in order that the design of scheme could avoid them. Such investigations would also identify any remedial preventative and mitigatory measures required. These investigations took place in the form of one site strip across the entire site.

These investigations encountered a single infilled shaft located towards the western corner of the site. The shaft appears to be stable and the CMRA does not consider that deterioration of the fill will occur. Nevertheless, the proposed site layout was revised to avoid the construction of the proposed garages over the infilled shaft or its potential zone of influence. The proposed garages will be built with a reinforced concrete slab foundation, albeit to address issues associated with made ground rather than to address mining legacy.

No further works are proposed to remediate the shaft, although the report does confirm that the mineshaft position will be left undeveloped (grassed), with a fence erected around the shaft in order to prevent pedestrian access over the shaft area.

In light of the above, the Coal Authority has raised no objection to the revised scheme subject to a condition requiring a mitigation strategy principally in the form of fencing to enclose the shaft area to prevent access.

Finally, reference is drawn to the Tyisha regeneration masterplan, and it is opined that the proposed development will adversely impact that strategy for the reasons outlined above. In this respect, whilst the Tyisha ward has been identified for regeneration, there are no confirmed proposals as of yet, and certainly no proposals pertaining to this site. The application site was previously owned by Carmarthenshire County Council and was marketed prior to its sale to the current applicant. It is understood that due to the referenced Coal Mining and Japanese Knotweed issues, the site was not considered by prospective purchasers as a viable site for housing, and therefore the site itself has limited alternative potential.

Planning Obligations

There is no S.106 required in this instance.

Well-being of Future Generations (Wales) Act 2015

The decision considers the duty to improve the economic, social, environmental and cultural well-being of Wales, in accordance with the sustainable development principle, under section 3 of the Well-Being of Future Generations (Wales) Act 2015 (the WBFG Act). The decision takes into account the ways of working set out at section 5 of the WBFG Act and it is considered that this decision is in accordance with the sustainable development principle through its contribution towards one or more of the Welsh Ministers' well-being objectives set out in section 8 of the WBFG Act.

Conclusion

The proposed development is considered acceptable in size, scale and design terms and will be restricted to domestic use only thus ensuring compatibility with its surroundings.

It is considered that there are no loss of amenity issues associated with the proposed development whilst it is considered that the reasons for concern and objection raised have adequately been addressed as part of the above appraisal.

On balance after careful examination of the site and its surrounding environs in the context of this application, together with the representations received to date, the application is put forward with a recommendation for approval subject to the following conditions.

Recommendation – Approval

Conditions and Reasons

Condition 1.

The development hereby approved shall be commenced before the expiration of five years from the date of this permission.

Reason:

Required to be imposed pursuant to Section 91 of the Town and Country Planning Act 1990.

Condition 2.

The development hereby permitted shall be carried out strictly in accordance with the following schedule of plans:-

- Location Plan (01) 1:1250 @ A4 received 19th February, 2020;
- Existing site plan (02) 1:200 @ A3 received 19th February, 2020;
- Proposed drainage plan (08 Rev D) 1:200 @ A3 received 11th September, 2020;
- Streetscene (07 Rev C) 1:100 @ A3 received 11th September, 2020;
- Site section A-A (05 Rev D) 1:75 @ A3 received 11th September, 2020;
- Site section B-B (06 Rev D) 1:75 @ A3 received 11th September, 2020;
- Proposed site plan (03-Rev D) 1:200 @ A3 received 13th October, 2020;
- Proposed floor plans and elevations (04 Rev E) 1:100 @ A3 received 13th October, 2020.

Reason: In the interest of visual amenity.

Condition 3.

Prior to its use by vehicular traffic, the new access point shall be laid out and constructed to a width of at least 4.5 metres at the junction with the W5325 road/Ann Street.

Reason: In the interest of highway safety.

Condition 4.

Any access gates shall be set back a minimum distance of 5.0 metres from the highway boundary, and shall open inwards into the site only.

Reason: In the interest of highway safety.

Condition 5.

There shall at no time be any growth or obstruction to visibility over 0.6 metres above the adjacent carriageway crown, over the site's whole Ann Street Road frontage within 2.0 metres of the near edge of the carriageway.

Reason: In the interest of highway safety.

Condition 6.

The access, visibility splays and turning area required, shall be wholly provided prior to any part of the development being brought into use, and thereafter shall be retained unobstructed in perpetuity. In particular, no part of the access, visibility splays, or turning area, is to be obstructed by non-motorised vehicles.

Reason: In the interest of highway safety.

Condition 7.

The parking spaces and layout shown on the plans herewith approved shall be provided prior to any use of the development herewith approved. Thereafter, they shall be retained, unobstructed, for the purpose of parking only. In particular, no part of the parking or turning facilities is to be obstructed by non-motorised vehicles.

Reason: In the interest of highway safety.

Condition 8.

The access shall be hard surfaced in a bonded material for a minimum distance of 5.0 metre behind the highway boundary, prior to any part of the development approved herewith being brought into use and thereafter maintained in perpetuity.

Reason: In the interest of highway safety.

Condition 9.

Prior to the commencement of development, a mitigatory strategy to address the risk posed by the on-site recorded mine shaft shall be submitted to and approved in writing by the Local Planning Authority. This strategy shall include details of the fencing to be erected to prevent pedestrian and vehicular access over the position of the mine entry. The measures included in the approved mitigatory strategy shall then be implemented in full prior to the development being taken into beneficial use and shall be retained as such thereafter.

Reason: In the interest of land stability and health and safety.

Condition 10.

The lock up garages hereby approved shall be used for domestic purposes in perpetuity, and not for trade or business use.

Reason:

To prevent any separate use on the site, and to ensure that the proposed development does not prejudice the enjoyment of neighbouring occupiers of their properties.

Condition 11.

There shall at no time be any external storage of materials or equipment on the application site.

Reason: In the interest of visual amenity.

Notes

Note 1.

Comments and guidance received from consultees relating to this application, including any other permissions or consents required, are available on the Authority's website.

Note 2.

Please note that this consent is specific to the plans and particulars approved as part of the application. Any departure from the approved plans will constitute unauthorised development and may be liable to enforcement action. You (or any subsequent developer) should advise the Council of any actual or proposed variations from the approved plans immediately so that you can be advised how to best resolve the matter.

In addition, any Conditions which the Council has imposed on this consent will be listed above and should be read carefully. It is your (or any subsequent developers') responsibility to ensure that the terms of all Conditions are met in full at the appropriate time (as outlined in the specific condition).

The commencement of development without firstly meeting in full the terms of any Conditions which require the submission of details prior to the commencement of development will constitute unauthorised development. This will necessitate the submission of a further application to retain the unauthorised development and may render you liable to formal enforcement action.

Failure on the part of the developer to observe the requirements of any other Conditions could result in the Council pursuing formal enforcement action in the form of a Breach of Condition Notice.

PWYLLGOR CYNLLUNIO Eitem Rhif 5

Dydd Mawrth, 20 Hydref 2020

YN BRESENNOL: Y Cynghorydd A. Lenny (Cadeirydd)

Y Cynghorwyr:

S.M. Allen, J.M. Charles, I.W. Davies, P.M. Edwards, W.T. Evans, S.J.G. Gilasbey, J.K. Howell, J.D. James, D. Jones, H.I. Jones, A. Lenny, M.J.A. Lewis, K. Madge, B.D.J. Phillips, G.B. Thomas a/ac J.E. Williams

Hefyd yn bresennol:

Y Cynghorwyr C.A. Davies mewn perthynas â chais cynllunio PL/00101 Y Cynghorwyr H.A.L. Evans mewn perthynas â chais cynllunio W/39346

Yr oedd y swyddogion canlynol yn gwasanaethu yn y cyfarfod:

- L. Quelch, Y Pennaeth Cynllunio
- G. Noakes, Uwch Swyddog Rheoli Datblygu (y Dwyrain)
- J. Thomas, Uwch Swyddog Rheoli Datblygu (y De)
- S. Murphy, Uwch-gyfreithiwr
- Z.M. James, Swyddog Rheoli Datblygu [y De]
- H. Rice, Swyddog Rheoli Datblygu
- K Phillips, Swyddog Rheoli Datblygu
- R. Davies, Swyddog Rheoli Datblygu [De]
- Z.A. Evans, Uwch-dechnegydd [Cyswllt Cynllunio]
- S. Rees, Cyfieithydd Ar Y Pryd
- J. Corner, Swyddog Technegol
- E. Evans, Prif Swyddog Gwasanaethau Democrataidd
- M. Evans Thomas, Prif Swyddog Gwasanaethau Democrataidd
- M.S. Davies, Swyddog Gwasanaethau Democrataidd
- R. Lloyd, Swyddog Gwasanaethau Democrataidd
- K. Thomas, Swyddog Gwasanaethau Democrataidd

Rhith-Gyfarfod -. - 10.00 yb - 12.40 yp

1. YMDDIHEURIADAU AM ABSENOLDEB

Cafwyd ymddiheuriad am absenoldeb gan y Cynghorydd C. Jones.

2. DATGAN BUDDIANNAU PERSONOL

Ni ddatganwyd unrhyw fuddiannau personol.

3. YSTRIED ADRODDIADAU'R PENNAETH CYNLLUNIO YNGHYLCH Y CEISIADAU CYNLLUNIO CANLYNOL [YR YMWELODD Y PWYLLGOR A'U SAFLEOEDD YN FLAENOROL] A PHENDERFYNU AR Y CEISIADAU

SYLWER: Cafodd yr eitem hon ei chynnwys ar yr agenda drwy gamgymeriad.

4. RHANBARTH Y DWYRAIN - PENDERFYNU AR GEISIADAU CYNLLUNIO



PENDERFYNWYD YN UNFRYDOL ganiatáu'r cais cynllunio canlynol yn unol â'r amodau a nodwyd yn Adroddiad y Pennaeth Cynllunio a/neu y rhoddwyd gwybod amdanynt yn y cyfarfod:-

Adeiladu un breswylfa ar dir y tu ôl i Heddfryn, Llansadwrn, Llanwrda

5. RHANBARTH Y DE - PENDERFYNU AR GEISIADAU CYNLLUNIO

PENDERFYNWYD YN UNFRYDOL ganiatáu'r ceisiadau cynllunio canlynol yn amodol ar yr amodau a nodwyd yn Adroddiad y Pennaeth Cynllunio a/neu y rhoddwyd gwybod amdanynt yn y cyfarfod:-

PL/00031	Darparu drws a ffenestr newydd ym mlaen yr eiddo ac ychwanegu system echdynnu dur di-staen i'r cefn mewn cysylltiad â Siop Cludfwyd Twrcaidd newydd yng Ngwesty'r Cambrian, 35 Stryd y Môr, Llanelli, SA15 2NP
PL/00354	Amrywiad i Amod 2 o S/26201 i ddiwygio'r cyfnod caeedig ar gyfer 10 llain o 5 Ionawr i 1 Mawrth bob blwyddyn – Fferm Llwynifan, Safle Carafannau, Heol Troserch, Llangennech, Llanelli, SA14 8AX

6. RHANBARTH Y GORLLEWIN - PENDERFYNU AR GEISIADAU CYNLLUNIO

6.1 PENDERFYNWYD bod y cais cynllunio canlynol yn cael ei gymeradwyo yn amodol ar yr amodau a nodir yn Adroddiad y Pennaeth Cynllunio a/neu a adroddwyd yn y cyfarfod ac i gwblhau'r Asesiad Priodol ar gyfer Ardal Gadwraeth Arbennig Afon Teifi a'r ymgeiswyr i ymrwymo i Gytundeb Adran 106:-

Datblygiad Un Blaned a newid o ddefnydd coedwigaet ddefnydd preswyl a choedwigaeth, Flatwood, Castellnewy Emlyn, SA38 93B	
Gwnaed sylw gan yr Aelod lleol yn gwrthwynebu'r datblygiad am nifer o resymau gan gynnwys y canlynol:-	
 Byddai'n cael effaith andwyol ar y goedwig a'i bywyd gwyllt Gallai ansawdd y pren yn y goedwig arwain at yr angen i fewnforio pren ar gyfer y busnes arfaethedig 	
 Y posibilrwydd i lifogydd ddigwydd o'r tir serth. Nid oedd modd dangos yn ddigonol pa mor serth yw'r tir drwy luniau Drôn. Efallai nad ystyrir bod ansawdd y dŵr o'r cyrsiau dŵr yn addas i'w yfed ac efallai y bydd angen cysylltiad â'r prif bibell dŵr sy'n croesi'r safle 	



- Roedd preswylfa i'w hadeiladu yng nghefn gwlad heb brofi hyfywedd ariannol ymlaen llaw.
- byddai plannu coed i gymryd lle'r rhai a gafodd eu cwympo yn cymryd blynyddoedd lawer i aeddfedu
- lefelau golau annigonol yn y goedwig i dyfu cnydau
- nid ystyriwyd bod y datblygiad yn hyfyw.

Ymatebodd y Pennaeth Cynllunio a'r Swyddog Rheoli Datblygu i'r materion a godwyd

6.2 PENDERFYNWYD

- 6.2.1 bod cais cynllunio PL00101 yn cael ei gymeradwyo, yn groes i argymhelliad y Pennaeth Cynllunio i'w wrthod, gan yr ystyrir bod y datblygiad arfaethedig yn cydymffurfio â Pholisïau GP1, H1, H2 a TR3 y Cynllun Datblygu Lleol yn ogystal â TAN 22 ac ystyrir bod y breswylfa'n gydnaws â byngalos o faint tebyg yn y gymuned leol.
- 6.2.2 Bod awdurdod dirprwyedig yn cael ei roi i'r Pennaeth Cynllunio i atodi amodau priodol i'r hysbysiad caniatâd cynllunio

PL/00101 Preswylfa unllawr newydd, Brodawel, Llanarthne, Caerfyrddin, SA32 8JD

Gwnaed sylw gan yr Aelod lleol yn cefnogi'r cais gan ei bod o'r farn bod y cais yn dod o fewn y diffiniadau o Bolisïau GP1, H1, H2 a TR3 o'r Cynllun Datblygu Lleol ynghyd â darpariaethau TAN 22. Er mwyn esbonio, ystyriwyd y byddai'r datblygiad arfaethedig yn gydnaws ag eiddo o faint tebyg yn yr ardal o ran ei faint a'i leoliad i'r eiddo presennol. Byddai'n arwain at ddarparu lleoedd parcio oddi ar y ffordd, diogelu coed a datblygu eiddo sy'n addas ar gyfer yr 21ain ganrif yn lle'r eiddo di-raen presennol.

7. LLOFNODI YN GOFNOD CYWIR GOFNODION Y CYFARFOD A GYNHALIWYD AR 8FED HYDREF, 2020

PENDERFYNWYD YN UNFRYDOL lofnodi bod cofnodion cyfarfod y Pwyllgor ar 8 Hydref 2020 yn gofnod cywir.

CADEIRYDD	DYDDIAD

[SYLWER: Mae'r cofnodion hyn yn dilyn trefn y materion oedd ar agenda'r



cyfarfod, a allai fod yn wahanol i drefn y materion mewn unrhyw weddarllediad gan y byddid wedi ymdrin gyntaf ag unrhyw geisiadau yr oedd aelodau o'r cyhoedd yn bresennol i siarad amdanynt.]

